

Revision	1				
List ID	53129				
Title	Bid Item List				
Item ID	Item Code	Description	Quantity	Units	Material Labor
881651	201	Clearing And Grubbing (all trees have been removed-stumps/roots still remain)	1	LS	
881652	202	Pavement Removed	585	SY	
881653	202	Walk Removed	1,054	SF	
881654	202	Curb And Gutter Removed	528	FT	
881655	203	Excavation	310	CY	
881656	203	Embankment	120	CY	
881657	204	Subgrade Compaction	574	SY	
881658	204	Proof rolling	2	HOUR	
881659	608	4" Concrete Walk	1,525	SF	
881660	609	Combination Curb And Gutter, Type 2	595	FT	
881661	601	Rock Channel Protection, Type C With Geotextile Fabric	170	CY	
881662	659	Soil Analysis Test	2	EA	
881663	659	Topsoil	72	CY	
881664	659	Seeding And Mulching, Class 2	843	SY	
881665	659	Commercial Fertilizer	0	TON	
881666	659	Lime	0	ACRE	
881667	659	Water	4	MGAL	
881668	832	Erosion Control	5,000	EA	
881669	601	Tied Concrete Block Mat With Type 1 Underlayment	4	SY	
881670	605	4" Base Pipe Underdrains	516	FT	
881671	611	4" Conduit, Type F	47	FT	
881672	611	Catch Basin Adjusted To Grade	2	EA	
881673	611	Manhole Adjusted To Grade	2	EA	
881674	613	Low Strength Mortar Backfill	237	CY	
881675	254	Pavement Planing, Asphalt Concrete	100	SY	
881676	301	Asphalt Concrete Base, PG64-22, (449) 4"	74	CY	
881677	304	Aggregate Base 6"	96	CY	
881678	407	Non-Tracking Tack Coat	89	GAL	
881679	441	Asphalt Concrete Surface Course, Type 1, (449), PG64-22	60	CY	
881680	SPEC	Work Zone Traffic Signal	1	EA	
881681	614	Work Zone Center Line, Class I	0	MILE	
881682	614	Work Zone Edge Line, Class I, 4"	0	MILE	
881683	614	Work Zone Stop Line, Class I	24	FT	
881684	615	Roads For Maintaining Traffic	1	LS	
881685	615	Pavement For Maintaining Traffic, Class B	603	SY	

881686	616 Water	3 MGAL
881687	622 Portable Barrier, Anchored	400 FT
881688	638 8" Water Main Ductile Iron Pipe Ansi Class 52, Push-On Joints And Fittings	243 FT
881689	638 18" Steel Pipe Encasement, Open Cut	48 FT
881690	638 6" Gate Valve	1 EA
881691	638 8" Gate Valve And Valve Box	3 EA
881692	638 Fire Hydrant And Gate Valve Removed And Reset	1 EA
881693	202 Structure Removed, Over 20 Foot Span	1 LS
881694	503 Cofferdams And Excavation Bracing	1 LS
881695	503 Unclassified Excavation	1 LS
881696	509 Epoxy Coated Steel Reinforcement	39,873 LB
881697	511 Class QC1 Concrete With QC/QA, Retaining/Wingwall Not Including Footing	33 CY
881698	511 Class QC1 Concrete With QC/QA, Footing	335 CY
881699	511 Class QC1 Concrete With QC/QA, Headwall	12 CY
881700	512 Sealing of Concrete Surfaces (Epoxy-Urethane)	134 SY
881701	512 Type 2 Waterproofing	142 SY
881702	512 Type 3 Waterproofing	295 SY
881703	516 1" Preformed Expansion Joint Filler	71 SF
881704	518 Porous Backfill With Geotextile Fabric	45 CY
881705	518 4" Perforated Corrugated Plastic Pipe	64 FT
881706	518 4" Non-Perforated Corrugated Plastic Pipe, Including Specials	9 FT
881707	611 Conduit, Type A, Precast Reinforced Concrete Three Sided Flat Topped Culvert, As Per Plan (26' Span x 7'-2" Rise)	72 FT
881708 SPEC	Reinforced Mesh For Transverse And/Or Longitudinal Joints And Cracks	38 SY
881709	614 Maintaining Traffic, As Per Plan	1 LS
881710 SPEC	Construction Layout Stakes And Surveying	1 LS
881711	624 Mobilization	1 LS