

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		KANE	63	1
		ILLINOIS	CONTRACT NO. _____	

INDEX OF SHEETS


- 1 COVER SHEET
- 2-5 GENERAL NOTES
- 6-9 SUMMARY OF QUANTITIES
- 10 TYPICAL SECTIONS
- 11 SOIL BORING LOGS
- 12 ALIGNMENT, TIES AND BENCHMARKS
- 13 EXISTING CONDITIONS AND REMOVAL PLAN
- 14 PLAN AND PROFILE
- 15 DRAINAGE AND UTILITY PLAN
- 16-18 GRADING PLAN
- 19 JOINTING PLAN
- 20-37 STRUCTURAL PLANS AND DETAILS
- 38 EROSION CONTROL AND LANDSCAPING PLAN
- 39 PAVEMENT MARKING AND SIGNAGE PLAN
- 40-42 LIGHTING PLANS AND DETAILS
- 43-44 PEDESTRIAN DETOUR AND STAGING PLAN
- 45-52 CROSS SECTIONS
- 53-63 CONSTRUCTION DETAILS

CITY OF BATAVIA STANDARD DETAILS

- 4.02 STORM SEWER MANHOLE - TYPE "A" OR TYPE "B"
- 4.03 FLARED END SECTION A
- 4.05 STANDARD MANHOLE LID DETAIL
- 4.13 INLET FILTER
- ~~4.14 INLET FILTER MAINTENANCE~~
- 5.08 UTILITY TRENCH SECTION
- ~~7.04 BB.12 BARRIER CURB & GUTTER~~
- 7.07 CURB REPLACEMENT
- 7.08 SIDEWALK
- 7.09 SIDEWALK CONSTRUCTION
- 7.10 CURB RAMPS
- 7.12 ACCESSIBLE PARKING SPACE MARKINGS


IDOT HIGHWAY STANDARDS

701801-06 SIDEWALK, CORNER OR CROSSWALK CLOSURE



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.


J.U.L.I.E.
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION
1-800-892-0123
OR 811



CITY OF BATAVIA
DEPARTMENT OF ENGINEERING

PEACE BRIDGE BIKE RAMP
KANE COUNTY, ILLINOIS


ISSUED FOR CONSTRUCTION
4/25/25



BATAVIA
TOWNSHIP

GROSS LENGTH = 300 FT. = 0.057 MILE
NET LENGTH = 300 FT. = 0.057 MILE

LOCATION MAP
NOT TO SCALE



LOCATION OF SECTION INDICATED THUS: - [rectangle] -

CONTACT

RAHAT BARI, P.E.
CITY OF BATAVIA
DEPARTMENT OF ENGINEERING
(630) 454-2760

Approved _____ 20 _____
City of Batavia, City Engineer

V3
KURT R. CORRIGAN
062-051814
DATE: XX-XX-2025
SIGNATURE AND SEAL APPLY TO
SHEETS: 1-19, 38-63



EXPIRATION DATE: 11-30-2025

V3
WILLIAM J. VEGRZYN
081-004983
DATE: XX-XX-2025
SIGNATURE AND SEAL APPLY TO
SHEETS: 20-37



EXPIRATION DATE: 11-30-2026

1.2 STANDARD SPECIFICATIONS FOR EARTHWORK, PAVEMENT, SIDEWALKS, STRUCTURAL ITEMS, AND RAILINGS:
ALL EARTHWORK, PAVEMENT, CURBING, SIDEWALK, STRUCTURAL ITEMS AND RAILINGS ON THIS PROJECT SHALL BE IN ACCORDANCE WITH THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", LATEST EDITION AS PREPARED BY THE ILLINOIS DEPARTMENT OF TRANSPORTATION (HEREINAFTER I.D.O.T.) AND THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS", LATEST EDITION AS PREPARED BY I.D.O.T.

2.18 EXISTING FIELD TILES OR UNDERDRAINS: THE LOCATION OF ANY EXISTING FIELD TILES OR UNDERDRAINS ENCOUNTERED DURING EXCAVATION SHOULD IMMEDIATELY BE FLAGGED ONSITE AND MARKED ON THE CONTRACTOR'S RECORD PLAN SET. THE CONTRACTOR SHALL RECONNECT ALL FIELD TILES OR UNDERDRAINS OR CONNECT FIELD TILES OR UNDERDRAINS TO THE PROPOSED STORM SEWER IN A MANNER ACCEPTABLE TO THE CITY ENGINEER.

2.23 UNLAWFUL ACTIVITIES--DRIANAGE FACILITIES--EARTHEN BERMS: IT IS UNLAWFUL FOR ANY PERSON TO CONSTRUCT OR CAUSE TO BE CONSTRUCTED ANY DRAINAGE FACILITY FOR THE PURPOSE OF THE DETENTION OR RETENTION OF WATER WITHIN A DISTANCE OF 10 FEET PLUS ONE AND ONE-HALF TIMES THE DEPTH OF ANY DRAINAGE FACILITY ADJACENT TO THE RIGHT OF WAY OF ANY PUBLIC HIGHWAY WITHOUT THE WRITTEN PERMISSION OF THE HIGHWAY AUTHORITY HAVING JURISDICTION OVER THE PUBLIC HIGHWAY. IT IS UNLAWFUL FOR ANY PERSON TO CONSTRUCT OR CAUSE TO BE CONSTRUCTED ANY EARTHEN BERM SUCH THAT THE TOE OF SUCH BERM WILL BE NEARER THAN 10 FEET TO THE RIGHT-OF-WAY OF ANY PUBLIC HIGHWAY WITHOUT THE WRITTEN PERMISSION OF THE HIGHWAY AUTHORITY HAVING JURISDICTION OVER THE PUBLIC HIGHWAY .

2.13 EXISTING STREET AND PEDESTRIAN WAY CLEANLINESS: THE CONTRACTOR(S) SHALL KEEP EXISTING ADJACENT STREET AND PEDESTRIAN WAY PAVEMENTS CLEAN OF DIRT AND DEBRIS. CLEAN PAVEMENTS ON A DAILY BASIS OR MORE OFTEN WHEN NECESSARY AS DIRECTED BY THE CITY ENGINEER.

MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CADD_Sheets\241108-shh-gennotes07.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME	= mfortmann
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED	-	_____
DRAWN	-	_____
CHECKED	-	_____
DATE	-	_____

-	_____
-	_____
-	_____
-	_____

-	_____
-	_____
-	_____
-	_____

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

GENERAL NOTES

SCALE: NONE	SHEET	1	OF	4	SHEETS	STA.	TO STA.
-------------	-------	---	----	---	--------	------	---------

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	2

MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CA-DD_Sheets\DT241108-sh-1108-gmnotes07.dgn

- 3.5 THE PROPOSED GRADING ELEVATIONS SHOWN ON THE PLANS ARE FINISH GRADES. A MINIMUM OF SIX INCHES (6") INCHES OF TOPSOIL IS TO BE RESPREAD ONSITE BEFORE FINISH GRADE ELEVATIONS ARE ACHIEVED, EXCEPT IN BUILDING PADS AND PAVEMENT AREAS, WHICH SHALL BE KEPT FREE OF TOPSOIL.
- 3.6 THE SELECTED STRUCTURAL FILL MATERIAL SHALL BE PLACED IN LEVEL UNIFORM LAYERS SO THAT THE COMPACTED THICKNESS IS APPROXIMATELY SIX INCHES (6"); IF COMPACTION EQUIPMENT DEMONSTRATED THE ABILITY TO COMPACT GREATER THICKNESSES, THEN A GREATER THICKNESS MAY BE SPECIFIED. EACH LAYER SHALL BE THOROUGHLY SCARIFIED DURING SPREADING TO INSURE UNIFORMITY.
- 3.7 EMBANKMENT MATERIAL WITHIN ROADWAY, PARKING LOT AND OTHER STRUCTURAL CLAY FILL AREAS SHALL BE COMPACTED TO A MINIMUM OF NINETY-FIVE PERCENT (95%) OF MAXIMUM DENSITY IN ACCORDANCE WITH ASTM SPECIFICATIONS D-1557 (MODIFIED PROCTOR METHOD), OR TO OTHER SUCH DENSITY AS MAY BE DETERMINED APPROPRIATE BY THE GEOTECHNICAL ENGINEER. EMBANKMENT MATERIAL FOR BUILDING PADS SHALL BE COMPACTED TO MINIMUM OF NINETY-FIVE PERCENT (95%) OF MAXIMUM DENSITY IN ACCORDANCE WITH ASTM DESIGNATION D-1557 (MODIFIED PROCTOR METHOD) OR TO SUCH OTHER DENSITY AS MAY BE DETERMINED APPROPRIATE BY THE GEOTECHNICAL ENGINEER.
- 3.8 EMBANKMENT MATERIAL (RANDOM FILL) WITHIN NON-STRUCTURAL FILL AREAS SHALL BE COMPACTED TO MINIMUM OF NINETY PERCENT (90%) OF MAXIMUM DENSITY IN ACCORDANCE WITH ASTM DESIGNATION D-1557 (MODIFIED PROCTOR METHOD).
- 3.9 THE SURFACE VEGETATION, TOPSOIL AND ANY OBVIOUSLY SOFT UNDERLYING SOIL SHOULD BE STRIPPED FROM ALL AREAS TO RECEIVE CLAY FILL. IF THE UNDERLYING SUBGRADE SOILS RUT DEEPER THEN AN INCH UNDER THE CONSTRUCTION EQUIPMENT OR IF THE MOISTURE CONTENT EXCEEDS THAT NEEDED FOR PROPER COMPACTION, THE SOIL SHALL BE SCARIFIED, DRIED AND RECOMPACTED TO THE REQUIRED SOIL SPECIFICATIONS.
- 3.10 ALL PAVEMENT SUBGRADE SHALL HAVE A MINIMUM IBR=3 AS DETERMINED BY THE GEOTECHNICAL ENGINEER WITH RESULTS SUBMITTED TO THE CITY ENGINEER. IF AREAS OF PAVEMENT SUBGRADE ARE ENCOUNTERED WHICH DO NOT PROVIDE A MINIMUM IBR=3, SUBGRADE REPLACEMENT OR PAVEMENT DESIGN REVISIONS SHALL BE PROVIDED WHICH ARE ADEQUATE TO OBTAIN EQUIVALENT PAVEMENT STRENGTH, AS DETERMINED BY THE ENGINEER AND GEOTECHNICAL ENGINEER.
- 3.11 PRIOR TO UTILITY CONSTRUCTION PROPOSED PAVEMENT AREAS, BUILDING PADS, SIDEWALKS AND YARD/OPEN SPACE AREAS SHALL BE ROUGH EXCAVATED OR FILLED TO PLUS OR MINUS ONE FOOT (1') OF DESIGN SUBGRADE ELEVATION BY THE CONTRACTOR.
- 3.12 THE STREET SUBGRADE SHALL BE SHAPED AND COMPACTED AS SPECIFIED IN SECTION 301 OF THE I.D.O.T. SPECIFICATIONS. JUST PRIOR TO THE CONSTRUCTION OF THE BASE COURSE, THE SUBGRADE SHALL BE PROOF-ROLLED, WITNESSED AND RECORDED FOR THE FILE AND/OR SIGNED OFF BY THE CITY ENGINEER OR REPRESENTATIVE. IF IN THE OPINION OF THE CITY ENGINEER OR THEIR DESIGNEE THAT ANY SUBGRADE AREAS ARE FOUND TO BE UNSTABLE, THEN SAID AREAS SHALL BE REMOVED AND REPLACED WITH AN ACCEPTABLE GRANULAR MATERIAL. IF PRECIPITATION OCCURS AFTER THE SUBGRADE PROOF-ROLLING AND BEFORE THE CONSTRUCTION OF THE BASE COURSE, THEN SAID SUBGRADE PROOF-ROLLING SHALL BE REPEATED TO VERIFY THAT THE SUBGRADE IS STABLE. IF AREAS OF THE SUBGRADE ARE FOUND TO BE UNSTABLE FOLLOWING REPLACEMENT WITH ACCEPTABLE GRANULAR MATERIALS THE GEOTECHNICAL ENGINEER AND THE CITY ENGINEER SHALL COLLECTIVELY DETERMINE THE CORRECTIVE ACTION.
- 3.13 GEOTEXTILE PAVING FABRIC ARE REQUIRED ON ALL STREET SUBGRADE APPLICATIONS AND SHALL CONSIST OF A NONWOVEN GEOTEXTILE FABRIC, 4 OZ/SY MINIMUM, CONFORMING TO ASTM D3776.
- 3.14 THE SUBGRADE SHALL MEET MINIMUM STANDARD OF NINETY-FIVE PERCENT (95%) OF THE STANDARD PROCTOR TEST AND SHALL BE TESTED AT 200 FOOT INTERVALS, MINIMUM.
- 3.15 AGGREGATE BASE COURSE: AFTER APPROVAL BY THE CITY ENGINEER, THE AGGREGATE BASE SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION 351 OF THE I.D.O.T. STANDARD SPECIFICATIONS FOR TYPE A OR TYPE B CONSTRUCTION. THE MATERIAL SHALL BE CRUSHED LIMESTONE CONFORMING TO CA-6 GRADATION. THE MINIMUM COMPACTED THICKNESS SHALL BE AS SHOWN ON THE TYPICAL CROSS-SECTION DETAIL. THE AGGREGATE BASE SHALL BE PROOF-ROLLED ONE DAY PRIOR TO PLANNED APPLICATION OF BINDER COURSE. IF, IN THE OPINION OF THE CITY ENGINEER THE AGGREGATE BASE IS UNSTABLE, IT SHALL BE REMOVED AND REPLACED WITH NEW SUBBASE AND AGGREGATE BASE MATERIAL AND COMPACTED TO NOT LESS THAN NINETY-FIVE PERCENT (95%) OF THE STANDARD LABORATORY DENSITY.
- 3.16 STORMWATER DETENTION AREAS: PROPOSED STORMWATER DETENTION AREAS SHALL BE EXCAVATED TO THE LINES, ELEVATIONS AND SLOPES SHOWN ON THE APPROVED ENGINEERING PLANS. AFTER THE AREA HAS BEEN EXCAVATED AND SHAPED TO ROUGH FINISHED GRADES, THE TOPSOIL MATERIAL SHALL BE SPREAD ON ALL AREAS AND GRADED TO FINISHED ELEVATIONS. THE FINISHED SURFACE SHALL THEN BE PLANTED ACCORDING TO THE APPROVED LANDSCAPE PLAN MEETING THE REQUIREMENTS FOUND IN SECTION 10.7 AFTER ACCEPTANCE OF THE FINISHED SURFACE AND DETENTION STORAGE REQUIREMENTS. ANY DAMAGE TO THE FINISHED SURFACE AFTER ACCEPTANCE SHALL BE REPAIRED BY CONTRACTOR PRIOR TO THE FINAL SEEDING. EROSION AND PONDING AREAS WITHIN DETENTION SHALL BE COMPLETELY RESTORED PRIOR TO FINAL ACCEPTANCE BY THE CITY.

- 3.17 AFTER COMPLETION OF ALL UTILITIES IN THE RIGHT OF WAY THE PARKWAYS SHALL BE TOPSOILED, SEEDED AND BLANKETED. THE PRIMARY METHOD FOR SEEDING IS DRILL OR BROADCAST. HYDROSEEDING CAN BE USED FOR AREAS WITH EROSION ISSUES OR OTHER HARD TO ACCESS AREAS AS ALLOWED BY THE CITY ENGINEER OR THEIR DESIGNEE. AREAS TO BE SEEDED SHALL BE FIRM BUT NOT COMPACTED AND SHALL BE FINE GRADED TO A SMOOTH AND NATURAL CONTOUR PRIOR TO SEEDING. ALL ROCKS, STICKS, ROOTS, CLODS, AND DEBRIS GREATER THAN ONE INCH IN DIAMETER SHALL BE REMOVED AND DISPOSED ON-SITE IN LOCATIONS APPROVED BY THE CITY ENGINEER OR THEIR DESIGNEE.

- 3.18 ROCK EXCAVATION SHALL BE PERFORMED IN ACCORDANCE WITH SECTION 202 OF THE LATEST EDITION OF THE IDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND ALL APPLICABLE LOCAL REGULATIONS. THE CONTRACTOR SHALL ANTICIPATE ENCOUNTERING ROCK DURING EXCAVATION WITHIN THE PROJECT LIMITS AND NOTIFY THE ENGINEER BEFORE PROCEEDING WITH REMOVAL. METHOD OF ROCK EXCAVATION IS SUBJECT TO APPROVAL BY THE CITY OF BATAVIA. ROCK EXCAVATION SHALL BE PAID FOR SEPARATELY. SEE APPROXIMATE ROCK DEPTH IN PLANS. SOIL BORING LOGS AND REPORT ARE INCLUDED IN CONTRACT DOCUMENTS.

4. 4. STORM SEWER CONSTRUCTION

- 4.1 STORM SEWER SHALL TYPICALLY BE REINFORCED CONCRETE SEWER PIPE, CLASS III OR IV AS NOTED, CONFORMING TO ASTM C-76 SPECIFICATIONS WITH RUBBER GASKET JOINTS. WHERE HORIZONTAL SEPARATION FROM WATER MAIN CONTROLS, PVC STORM SEWER OF WATER MAIN QUALITY SHALL BE USED, WITH JOINTS CONFORMING TO ASTM D-2855. NO ALTERNATE PIPE MATERIAL, SUCH AS PVC OR ADS PLASTIC, ETC., SHALL BE CONSIDERED ACCEPTABLE FOR THE MAIN STORM SEWER LINES WITHOUT THE WRITTEN CONSENT OF THE ENGINEER AND THE CITY ENGINEER. UPON REQUEST, THE CONTRACTOR SHALL PROVIDE EACH WITH SUPPLIER'S PRODUCT TEST REPORTS, CATALOG INFORMATION, ALTERNATE BIDS, OR ANY OTHER INFORMATION THEY MAY FIND NECESSARY IN CONSIDERING THE PROPOSED ALTERNATE MATERIAL. THE ACCEPTANCE OF THE PROPOSED ALTERNATE MATERIAL WILL IN NO WAY BE WARRANTED BY THESE SUBMITTALS.

- 4.2 FRAMES, LIDS AND GRATES DESIGNATED ON THE PLANS FOR STORM SEWER INLETS, MANHOLES AND JUNCTION BOXES SHALL CONFORM TO THE FOLLOWING OR AN APPROVED EQUAL:

CURB INLET	E.J. 7221 TYPE 1 CURB BACK, TYPE M1 GRATE
DEPRESSED CURB INLET	E.J. 7000 WITH M3 GRATE
MANHOLE	E.J. 1020 TYPE M1 OR TYPE A GRATE
YARD INLET	E.J. 6527
JUNCTION BOX	E.J. 1020 TYPE M1 OR TYPE A GRATE

THE WORDS "CITY OF BATAVIA", "STORM" SHALL BE CAST INTO THE LID. ALL STRUCTURES TRIBUTARY TO THE FOX RIVER THE GRATE SHALL BE CAST WITH A FISH AND STATE "DRAINS TO THE RIVER".

- 4.3 MANHOLES TYPE "B": MANHOLES DESIGNATED ON THE PLANS AS TYPE "B" ARE SHALLOW DEPTH MANHOLES WITH A REINFORCED CONCRETE FLAT SLAB TOP. THE THICKNESS OF THE FLAT SLAB TOP TO BE 6 INCHES, MINIMUM. ALL PRECAST CONCRETE MANHOLE SECTIONS SHALL MEET THE REQUIREMENTS OF ASTM C-478.

- 4.4 EXISTING DRAINAGE SYSTEM CLEANING AND REPAIR: WHERE SHOWN ON THE PLANS OR DIRECTED BY THE ENGINEER, EXISTING DRAINAGE STRUCTURES OR SYSTEMS SHALL BE CLEANED OF DEBRIS AND PATCHED AS NECESSARY TO INSURE INTEGRITY.

- 4.5 ALL COMPLETED MAIN LINE STORM SEWERS (NOT LATERALS) SHALL BE INSPECTED USING COLOR CLOSED CIRCUIT TELEVISION CAMERA (CCTV) AND DOCUMENT THE INSPECTION ON A DIGITAL RECORDER. THE CONTRACTOR OR DEVELOPER SHALL PAY TO HAVE THE LINES TELEVIEWED. TELEVIEWING SHALL BE DONE WITH APPROXIMATELY ONE HALF INCH (1/2") CONTINUAL FLOW IN THE SEWER. ALL INSPECTION VIDEO SHALL BE CAPTURED IN EITHER MPEG OR WINDOWS MEDIA VIDEO (.WMV) FILE FORMAT AND SAVED TO PORTABLE HARD DRIVES FOR SUBMITTAL AND REPAIRS COMPLETED, IF NECESSARY, PRIOR TO ACCEPTANCE OF THE SEWERS BY THE CITY. THE FINAL INSPECTION VIDEOS PROVIDED SHALL BECOME THE PROPERTY OF THE CITY. ALL WORK WILL CONFORM TO CURRENT NASSCO PIPELINE ASSESSMENT CERTIFICATION PROGRAM (PACP) CODING CONVENTIONS AND ALL SOFTWARE USED BY THE CONTRACTOR WILL BE PACP COMPLIANT. THIS WORK IS INCLUDED IN THE OVERALL CONTRACT.

- 4.6 FINAL CLEARING: PRIOR TO FINAL INSPECTION AND ACCEPTANCE BY THE CITY, ALL STORM SEWER MAINS AND STRUCTURES SHALL BE CLEANED BY JETTING OR OTHER ACCEPTABLE METHODS TO REMOVE ALL CONSTRUCTION DEBRIS OR SEDIMENT. CONSTRUCTION DEBRIS AND SEDIMENT SHALL BE COLLECTED AND NOT ALLOWED TO BE TRANSPORTED TO DOWNSTREAM SEWERS OR STORMWATER FACILITIES.

- 4.7 POURED INVERTS: ALL INLETS, CATCH BASINS, STORM MANHOLES AND OTHER DRAINAGE STRUCTURES SHALL BE PROVIDED WITH PRECAST CONCRETE INVERTS OR SHALL HAVE POURED IN PLACE CONCRETE INVERTS CONFORMING TO THE SHAPE OF THE PIPE OR AS OTHERWISE SHOWN ON THE PLANS. POURED IN PLACE CONCRETE SHALL BE CLASS "SI" SHAPED AND TOWELED FOR A SMOOTH FINISH.

- 4.8 SUMP PUMP LINES: SUMP PUMP LINES SHALL BE PVC SEWER PIPE CONFORMING TO ASTM D-3034. SPECIFICATIONS TYPE, 4" SDR 26. THE MINIMUM COVER DEPTH SHALL BE 2.5' MINIMUM. ALL STUBS SHALL BE EXTENDED INTO LOT 10' MINIMUM, CAPPED, AND LOCATIONS MARKED WITH 2' X 4' POST PAINTED YELLOW. IF SUMP PUMP LINES ARE INSTALLED TO THE HOUSE PROPER CITY INSPECTIONS ARE REQUIRED.

- 4.9 SUMP PUMP DRAINAGE BOXES: A PRECAST CONCRETE JUNCTION BOX OF THE SIZE AND TYPE SHOWN IN "INLET TYPE A" ON THE PLANS SHALL BE INSTALLED WHERE MULTIPLE SUMP DRAINS FLOW INTO THE RCP STORM SEWER LINE AT A COMMON CONNECTION.

5. 5. SANITARY SEWER CONSTRUCTION

- 5.1 SEWER PIPE AND FITTINGS SHALL CONFORM TO THE FOLLOWING SPECIFICATIONS EXCEPT AS APPROVED BY THE CITY ENGINEER:

- BETWEEN DEPTHS OF SIX FEET (6') AND FOURTEEN FEET (14'), PVC PIPE ASTM D-3034 SDR 26 SHALL BE REQUIRED. (ORD. 97-32, 6-2-1997)
- FOR DEPTHS SHALLOWER THAN SIX FEET (6') OR DEEPER THAN FOURTEEN FEET (14') DUCTILE IRON PIPE, ASTM C151, CLASS 52 WITH PUSH ON JOINTS OR RESTRAINED JOINTS WHERE APPLICABLE, PIPE SHALL BE AS MANUFACTURED BY GRIFFIN PIPE CO., H2SEWER SAFE DUCTILE IRON OR APPROVED EQUAL. ALL DUCTILE IRON SHALL INCLUDE POLY-WRAP. ALL PIPE INSTALLED AT DEPTHS GREATER THAN FOURTEEN FEET (14') SHALL BE EVALUATED FOR THICKNESS BY CONSIDERING THE TRENCH LOAD AND INTERNAL PRESSURE SEPARATELY IN ACCORDANCE WITH ANSI/AWWA C150/A21.5. PRESSURE RATED PIPE, ASTM D-2241, SDR 21 MAY BE SUBSTITUTED FOR BURY DEPTHS FROM FOURTEEN FEET (14'), TO TWENTY FEET (20'). PRESSURE RATED PIPE, ASTM D-2241, (DR) 18, AWWA C-900, MAY BE REQUIRED OR SUBSTITUTED AT DEPTHS GREATER THAN TWENTY FEET (20'). ANY USE OF PLASTIC PIPE AT THESE DEPTHS SHALL BE WITH THE PERMISSION OF (OR REQUIRED BY) THE CITY ENGINEER. (ORD. 85-21,9-3-1985)
- FOR PIPE TWENTY FOUR INCHES (24") AND LARGER, PIPE SHALL BE AS MANUFACTURED BY GRIFFIN PIPE CO., H2SEWER SAFE DUCTILE OR APPROVED EQUAL. ALL DUCTILE IRON SHALL INCLUDE POLY-WRAP. ALL PIPE GREATER THAN TWENTY FOUR INCHES (24") DIA. OR INSTALLED AT DEPTHS GREATER THAN FOURTEEN FEET (14') SHALL BE EVALUATED FOR THICKNESS BY CONSIDERING THE TRENCH LOAD AND INTERNAL PRESSURE SEPARATELY IN ACCORDANCE WITH ANSI/AWWA C150/A21.5. PRESSURE RATED PIPE ASTM D- 2241 OR AWWA C905, MAYBE REQUIRED (OR SUBSTITUTED) ON LARGE DIA. PIPE BY THE CITY ENGINEER.

- 5.2 MANHOLE FRAMES AND LIDS: THE FRAMES AND LIDS SHALL BE OF THE NON-ROCKING AND SELF-SEALING TYPE WITH RUBBER WATERTIGHT GASKET AND SHALL CONFORM TO EAST JORDAN NO 1020 OR AN APPROVED EQUAL. THE LIDS TO BE SOLID WITH CONCEALED PICK HOLE AND WITH THE WORDS "CITY OF BATAVIA" AND "SANITARY SEWER" IN THE CAST IN LID. "INFA-SHIELD", "CANUSA" OR APPROVED EQUAL, CHIMNEY SEALS SHALL BE INSTALLED ON ALL SANITARY SEWER MANHOLES.

- 5.3 SEWER PIPE BEDDING AND COVER: ALL SANITARY SEWER PIPE INCLUDING SERVICE LINES SHALL BE BEDDED AND CRADLED TO THE CENTERLINE OF THE PIPE IN SAND OR FINE GRAVEL. FROM THE CENTERLINE OF THE PIPE TO 12 INCHES OVER THE TOP OF THE PIPE, GRANULAR TRENCH BACKFILL MATERIAL SHALL BE HAND PLACED AND COMPACTED. ALL TO THE DETAILS SHOWN ON THE PLANS, PVC PIPE SHALL BE BEDDED AND CRADLED IN ACCORDANCE WITH ASTM D-2321 (CLASS 1) SPECIFICATIONS. ALL TRENCHES WITHIN STREETS AND FOR SANITARY SEWERS CONSTRUCTED UNDER PROPOSED PAVED AREAS SHALL BE BACKFILLED WITH CA-7 CRUSHED STONE. FLOWABLE FILL IN ACCORDANCE WITH I.D.O.T. SPECIAL PROVISION FOR CONTROLLED LOW-STRENGTH MATERIALS (CLSM) MAY BE REQUIRED UNDER CERTAIN CIRCUMSTANCES AS DIRECTED BY THE DEPT. OF PUBLIC WORKS OR THE CITY ENGINEER. CA-6 CRUSHED STONE TRENCH BACKFILL (95%) COMPACTION @ ONE FOOT INTERVALS ACCORDING TO CITY POLICY) OR OTHER SUITABLE TRENCH BACKFILL MAY BE SUBSTITUTED FOR CA-7 UNDER THE FOLLOWING CONDITIONS: 1) APPROVED BY STREET DEPARTMENT SUPERINTENDENT AND CITY ENGINEER, 2) ON-SITE INSPECTION OF TRENCH BACKFILL DURING CONSTRUCTION.

- 5.4 SANITARY SEWER SERVICES: SANITARY SEWER STUBS INSTALLED FOR HOUSE SERVICE CONNECTIONS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE DETAILS SHOWN ON THE PLANS OR THE STANDARD SPECIFICATIONS. SEWER STUBS SHALL BE EXTENDED TO THE R.O.W. THE EXACT LOCATION SHALL BE DETERMINED IN THE FIELD, AND THE CONSTRUCTED LOCATION ACCURATELY RECORDED AND THE END MARKED WITH A 2'X4' POST PAINTED GREEN. SERVICE LINES SHALL HAVE A MINIMUM SLOPE OF 2.0%.

- 5.5 LEAKAGE TESTING: ALL SANITARY SEWERS SHALL BE TESTED FOR WATERTIGHTNESS BY THE AIR TESTING METHOD SPECIFIED IN THE STANDARD SPECIFICATIONS.

- 5.6 DEFLECTION TESTING: ALL SANITARY SEWER MAIN CONSTRUCTED OF PVC PIPE SHALL BE TESTED FOR DEFLECTION IN ACCORDANCE WITH THE REQUIREMENTS OF THE STANDARD SPECIFICATIONS.

- 5.7 T.V. INSPECTION: PRIOR TO ACCEPTANCE OF THE SANITARY SEWERS BY THE CITY, ALL SANITARY SEWER MAINS SHALL BE INTERNALLY INSPECTED BY TELEVISION CAMERA. THE CITY ENGINEER IS TO BE NOTIFIED PRIOR TO THE INSPECTION. VHS VIDEO TAPES OF THE T.V. INSPECTION SHALL BE RECORDED AND GIVEN TO THE CITY AND THE ENGINEER FOR THEIR RECORDS. CORRECTION OF ANY IRREGULARITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME	= mfortmann
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED	-	_____
DRAWN	-	_____
CHECKED	-	_____
DATE	-	_____

-

-

-

-

-

-

-

BATAVIA

PEACE BRIDGE BIKE RAMP

ILLINOIS

SCALE: NONE

SHEET

2

OF

4

SHEETS

TO STA.

TO STA.

GENERAL NOTES

COUNTY

TOTAL
SHEETS

SHEET
NO.

KANE

63

3

MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CAD - Sheets\DT241108-shs-1gennotes01.dgn



V3 Companies
7325 Jones Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME	= mfortmann
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED	-	_____
DRAWN	-	_____
CHECKED	-	_____
DATE	-	_____

-	_____
-	_____
-	_____
-	_____

-	_____
-	_____
-	_____
-	_____

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

GENERAL NOTES

SCALE: NONE SHEET 3 OF 4 SHEETS STA. TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	4

5.8 VACUUM TESTING: VACUUM TESTING SHALL BE CARRIED OUT IMMEDIATELY AFTER ASSEMBLY AND PRIOR TO BACKFILLING. ALL LIFT HOLES SHOULD BE PLUGGED WITH AN APPROVED NON-SHRINK GROUT, OR RUBBER PLUG. NO GROUT WILL BE PLACED IN THE HORIZONTAL JOINTS BEFORE TESTING. ALL PIPES ENTERING THE MANHOLE SHALL BE PLUGGED, TAKING CARE TO SECURELY BRACE THE PLUGS FROM BEING DRAWN INTO THE MANHOLE. A VACUUM OF TEN (10) INCHES OF MERCURY SHALL BE PLACED ON THE MANHOLE AND THE TIME MEASURED FOR THE VACUUM TO DROP TO NINE (9) INCHES OF MERCURY. THE VACUUM SHALL NOT DROP BELOW NINE (9) INCHES OF MERCURY FOR THE FOLLOWING TIME PERIODS FOR EACH SIZE MANHOLE:

FORTY-EIGHT (48) INCHES DIAMETER	SIXTY (60) SECONDS
SEVENTY-TWO (72) INCHES DIAMETER	NINETY (90) SECONDS

THE VACUUM TESTER SHALL BE MANUFACTURED BY P.A. GLAZIER, INC., WORCESTER, MA. 01613, PHONE (800) 822-6488, OR OTHER TESTING EQUIPMENT MEETING THE SAME STANDARDS, IF APPROVED BY THE CITY DEPARTMENT OF PUBLIC WORKS ALL TESTING SHALL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF P.A. GLAZIER, INC. IF TESTING FAILS THE CONTRACTOR SHALL SEAL ALL LEAKS WITH MATERIAL AND METHODS RECOMMENDED BY P.A. GLAZIER, INC. AND RE-TESTED UNTIL ACCEPTABLE. IT IS RECOMMENDED THAT THIS TESTING BE DONE BEFORE BACKFILLING SO THAT ANY LEAKS CAN BE FOUND AND FIXED EXTERNALLY. THE MANHOLE FRAME AND ADJUSTING RINGS SHALL BE IN PLACE WHEN TESTING.

5.9 MANHOLES: ALL SANITARY SEWER MANHOLES SHALL BE OF PRECAST CONCRETE CONSTRUCTION, AND SHALL HAVE RUBBER GASKETED COUPLINGS FOR ALL INLET AND OUTLET PIPES. INVERTS SHALL BE PRECAST CONCRETE CONFORMING TO THE SIZE AND SHAPE OF THE SHAPE OF THE PIPE OR POURED IN PLACE CLASS "SI" CONCRETE SHAPED AND TROWELED FOR A SMOOTH FINISH CONFORMING TO THE SIZE AND SHAPE OF THE PIPE. MINIMUM SLOPE ON BENCHES SHALL BE ONE INCH PER FOOT. SEWER DROPS ARE TO BE INSTALLED WHERE INLETS TO MANHOLE ARE GREATER THEN TWO (2) FEET ABOVE THE OUTLET INVERT.

5.10 A NON-SHEAR "MISSION" BRAND COUPLING SHALL BE USED WHEN JOINING PIPES MADE OF DISSIMILAR MATERIAL OR WHERE NO "HUB" END EXISTS. PVC TRANSITION FITTINGS SHALL BE USED WHEN JOINING PVC PIPES OF DISSIMILAR MATERIAL SPECIFICATIONS SUCH AS WITH STORM SEWER OR WATER MAIN.

6. SIDEWALK, CURB, AND APRON CONSTRUCTION

6.1 COMBINATION CURB AND GUTTER SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION 606 OF THE LATEST I.D.O.T. STANDARD SPECIFICATIONS (HERETOFORE REFERRED TO AS THE STANDARD SPECIFICATIONS). THE CONCRETE CURB AND GUTTER SHALL BE TYPE B6.12 UNLESS DETAILED OTHERWISE IN THE CONSTRUCTION PLANS. THE CONTRACTOR IS CAUTIONED TO REFER TO THE CONSTRUCTION STANDARDS AND THE PAVEMENT CROSS-SECTION TO DETERMINE THE GUTTER FLAG THICKNESS AND THE AGGREGATE BASE COURSE THICKNESS BENEATH THE CURB AND GUTTER. THE CONCRETE SHALL BE CLASS SI MIX DESIGN. IT SHALL HAVE AN AIR CONTENT OF NOT LESS THAN 5% NOR MORE THAN 7% OF THE VOLUME OF THE CONCRETE. IT SHALL DEVELOP A MINIMUM OF 3,500 PSI COMPRESSIVE STRENGTH AT 14 DAYS. TEST CYLINDERS SHALL BE TAKEN BY THE CONTRACTOR AND THE CERTIFIED COMPRESSION TEST RESULTS SUBMITTED TO THE CITY ENGINEER.

6.2 FOR CURB AND GUTTER CONSTRUCTED OVER UTILITY TRENCHES, TWO (2) EPOXY COATED REINFORCING BARS (NO. 5) SHALL BE PLACED IN THE CURB AND GUTTER, CENTER OVER THE TRENCH. AT EACH EXPANSION JOINT PROVIDE TWO 18" LONG NO. 6 SMOOTH BARS WITH EXPANSION CAPS AND 3/4" PREMOLDED, NON-EXTRUDING JOINT FILLER MEETING THE REQUIREMENTS OF SECTION 1051 OF THE STANDARD SPECIFICATIONS. REFER TO CITY STANDARD DETAIL NO. 7.03 AND 7.04 FOR THE REQUIRED SPACING AND INSTALLATION DETAILS OF EXPANSION JOINTS.

6.3 CONTRACTION JOINTS SHALL BE SAWED AT A MAXIMUM OF TEN FEET (OR 15") SPACING. THE CONTRACTION JOINTS SHALL BE CUT IN THE UPPER 1/3 OF CURBS AND GUTTERS WITHIN 24 HOURS OF PLACEMENT.

6.4 ALL CURB AND GUTTER SHALL BE BROOM FINISHED. FINISHED SURFACES OF ALL NEWLY CONSTRUCTED CURB AND GUTTER SHALL BE COATED WITH CURING COMPOUND ACCORDING TO THE REQUIREMENTS OF SECTION 1022 OF THE STANDARD SPECIFICATIONS AND AS APPROVED BY THE CITY ENGINEER. CURING COMPOUND SHALL BE APPLIED ACCORDING TO THE MANUFACTURER INSTRUCTIONS.

6.5 CURING AND PROTECTION OF ALL EXPOSED CONCRETE SURFACES SHALL BE IN ACCORDANCE WITH ARTICLE 1020.13 OF THE STANDARD SPECIFICATIONS. NO HONEYCOMBING OF THE CURB AND GUTTER WILL BE ACCEPTED.

6.6 BACKFILLING OF CURBS SHALL BE COMPLETED PRIOR TO PLACEMENT OF ROADWAY BASE-COURSE.

6.7 SIDEWALKS SHALL BE FIVE INCHES (5") THICK MINIMUM EXCEPT THRU DRIVEWAYS, WHERE SIX INCHES (6") IS REQUIRED FOR RESIDENTIAL AND 8 INCHES (8") FOR COMMERCIAL DRIVEWAYS. THE WIDTH OF THE SIDEWALK SHALL BE A MINIMUM OF FIVE FEET (5'). THE CONCRETE SHALL BE CLASS SI MIX DESIGN. REFER TO CITY STANDARD DETAIL NO. 7.08 AND 7.09 FOR THE REQUIRED SPACING OF EXPANSION AND CONTRACTION JOINTS.PREFORMED FOAM EXPANSION JOINT FILLER SHALL MEET THE REQUIREMENTS OF SECTION 1051 OF THE STANDARD SPECIFICATIONS. ALL SIDEWALKS SHALL BE BROOM FINISHED.

6.8 ADA SIDEWALK RAMPS SHALL BE INSTALLED AT ALL SIDEWALK/STREET INTERSECTIONS AS SHOWN ON CITY OF BATAVIA SIDEWALK CURB RAMP DETAIL (STANDARD NO. 7.10) OR IN COMPLIANCE WITH THE MOST CURRENT ADA STANDARDS.

6.9 SIDEWALK SHALL NOT BE PLACED UNTIL BUILDING CONSTRUCTION HAS BEEN COMPLETED TO THE POINT THAT CONSTRUCTION TRAFFIC NEED NO LONGER CROSS THE SIDEWALK AREA, OR AS OTHERWISE DIRECTED BY THE ENGINEER.

6.10 CONCRETE DRIVEWAY APRONS SHALL BE POURED IN A SEPARATE POUR FROM ADJACENT SIDEWALK AND CURB. MONOLITHIC POURS ARE NOT ALLOWED WITHOUT PRIOR APPROVAL OF THE CITY OF BATAVIA. NO CONCRETE SHALL BE PLACED UNTIL ALL THE FORMS HAVE BEEN INSPECTED FOR LINE, GRADE, AND SUBGRADE CONDITIONS BY THE CITY OF BATAVIA ENGINEERING INSPECTOR. REFER TO CITY STANDARD DETAIL NO. 7.16 AND 7.17 FOR DETAILED INFORMATION ON COMMERCIAL AND RESIDENTIAL DRIVEWAY APRONS.

7. PAVEMENT CONSTRUCTION

7.1 PROOF ROLL WILL BE REQUIRED WITH THE CITY ENGINEER OR THEIR DESIGNEE PRESENT AFTER PREPARATION OF THE SUBGRADE. PROOF ROLL MUST USE A FULLY LOADED SEMI UNLESS OTHERWISE APPROVED AND WEIGH TICKETS MUST BE PROVIDED.

7.2 THE PROPOSED PAVEMENT SHALL CONSIST OF THE SUB-BASE COURSE, HOT MIX ASPHALT (HMA) BINDER COURSE, AND HMA SURFACE COURSE, OF THE THICKNESS AND MATERIALS AS SPECIFIED ON THE CONSTRUCTION PLANS. PRIME COAT SHALL BE APPLIED TO THE SUB-BASE COURSE AT A RATE OF 0.25 POUNDS PER SQUARE FOOT. ALL PAVEMENT SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", LATEST EDITION.

7.3 AFTER THE INSTALLATION OF THE SUB-BASE COURSE, ALL TRAFFIC SHALL BE KEPT OFF THE BASE UNTIL THE BINDER COURSE IS LAID. AFTER INSTALLATION OF THE BINDER COURSE (AND FOR PUBLIC IMPROVEMENTS AFTER THE BINDER COURSE HAS BEEN IN PLACE AND 80% OF DEVELOPMENT BUILT OUT), AND UPON THE COMPLETION OF INSPECTION OF SAME AND APPROVAL BY THE CITY AND DEVELOPER, THE PAVEMENT SHALL BE CLEANED, PRIMED AND THE SURFACE COURSE LAID. ALL DAMAGED AREAS IN THE BINDER BASE OR BINDER SHALL BE REPAIRED TO THE SATISFACTION OF THE CITY AND DEVELOPER PRIOR TO LAYING THE SURFACE COURSE. THE PAVING CONTRACTOR SHALL PROVIDE WHATEVER EQUIPMENT AND MANPOWER IS NECESSARY, INCLUDING THE USE OF POWER BROOMS, TO PREPARE THE PAVEMENT FOR APPLICATION OF THE SURFACE COURSE. A TACK COAT SHALL BE APPLIED TO THE BINDER AT A RATE OF 0.1 GALLONS PER SQUARE YARD.

7.4 THE BITUMINOUS CONCRETE BINDER COURSE SHALL BE IN ACCORDANCE WITH THE LATEST IDOT DISTRICT ONE HMA - MIX SELECTION TABLE. FOR ROADWAYS WITH LOWER THAN 10,000 ADT THE BINDER COURSE SHALL BE CLASS I, MIXTURE IL19.0, N50. ALL WORK AND MATERIALS SHALL BE PERFORMED IN ACCORDANCE WITH APPLICABLE PROVISIONS OF SECTION 406 OF THE I.D.O.T. STANDARD SPECIFICATIONS. THE MINIMUM THICKNESS OF THE COMPLETED BITUMINOUS BINDER COURSE, AS MEASURED AT ANY POINT ON THE PAVEMENT SURFACE, SHALL BE IN ACCORDANCE WITH THE STANDARD CONSTRUCTION DETAILS SHOWN ON THE ENGINEERING PLANS.

7.5 FOR ROADWAYS IN NEW DEVELOPMENTS, THE BINDER COURSE SHALL BE SUBJECT TO ONE WINTER PERIOD (MINIMUM) OF TRAFFIC AFTER PLACEMENT BEFORE THE CONSTRUCTION OF THE FINAL SURFACE COURSE. PRIOR TO NOVEMBER, BITUMINOUS RAMPS SHALL BE INSTALLED AT RAISED MANHOLES, VAULT, AND INLET CASTING TO FACILITATE SNOW REMOVAL FROM THE STREETS. RAMPS SHALL BE REMOVED PRIOR TO CONSTRUCTION OF THE SURFACE COURSE. PRIOR TO THE CONSTRUCTION OF THE FINAL SURFACE COURSE, CORE BORING SHALL BE MADE, IN THE PRESENCE OF A REPRESENTATIVE OF THE CITY, THROUGH THE EXISTING BINDER COURSE AND AGGREGATE BASE COURSE. THE CORINGS SHALL BE SPACED AS DIRECTED BY THE CITY ENGINEER AND SHALL BE ALTERNATELY STAGGERED ON EACH SIDE OF THE CENTERLINE OF THE PAVEMENT. CORING SHALL BE MEASURED FOR THICKNESS AND RESULTS OF THE CORE BORINGS SHALL BE SUBMITTED TO THE CITY ENGINEER FOR APPROVAL BEFORE PROCEEDING THE FINAL BITUMINOUS COURSE. ANY DEFICIENCIES IN THICKNESS OF BASE AND/OR BINDER SHALL BE CORRECTED BY AN APPROVED THICKNESS OF SURFACE COURSE OR OTHER METHOD FOUND ACCEPTABLE TO THE CITY ENGINEER. ALL CORE BORINGS SHALL BE FILLED AND COMPACTED WITH BITUMINOUS ASPHALT. THE COST OF ALL BORINGS SHALL BE AT THE DEVELOPER'S EXPENSE.

7.6 PRIOR TO CONSTRUCTION OF THE FINAL BITUMINOUS SURFACE COURSE ON PREVIOUSLY CONSTRUCTED BITUMINOUS BINDER COURSE SUBJECT TO EXTENDED TRAFFIC USE, A BITUMINOUS TACK COAT SHALL BE APPLIED TO SAID BITUMINOUS BINDER COURSE SURFACE. THE BITUMINOUS CONCRETE SURFACE COURSE SHALL BE IN ACCORDANCE WITH THE LATEST IDOT DISTRICT ONE HMA - MIX SELECTION TABLE. FOR ROADWAYS WITH LOWER THAN 10,000 ADT THE BITUMINOUS CONCRETE SURFACE COURSE SHALL BE MIX D, IL-9.5 MM N50 CONSTRUCTED ON PREVIOUSLY PLACED BITUMINOUS BINDER COURSE. THE WORK AND MATERIALS SHALL CONFORM TO APPLICABLE PROVISIONS OF SECTION 406 OF THE STANDARD I.D.O.T. SPECIFICATIONS. THE BITUMINOUS MIXTURE SHALL BE SHOWN ON THE PLANS OR SPECIFIED IN THE PROJECT SPECIFICATIONS AND APPROVED BY THE CITY ENGINEER. NO RECYCLED BITUMINOUS MATERIAL WILL BE PERMITTED IN THE FINAL BITUMINOUS SURFACE COURSE MIXTURE UNLESS APPROVED BY THE CITY ENGINEER. THE MINIMUM THICKNESS OF THE FINAL COMPLETED BITUMINOUS SURFACE COURSE, AS MEASURED AT ANY POINT ON THE PAVEMENT SURFACE, SHALL BE IN ACCORDANCE WITH THE CONSTRUCTION DETAILS SHOWN ON THE PLANS.

7.7 THE CONTRACTOR SHALL GUARANTEE THE PAVEMENT FOR ONE YEAR AFTER FINAL ACCEPTANCE AGAINST SETTLEMENT, LOW SPOTS, AND/OR RAVELING OUT OF SURFACE. THE CONTRACTOR SHALL MAKE ANY REPAIRS NECESSARY DURING THE GUARANTEE PERIOD TO MAINTAIN THE FINISHED PAVEMENT IN SATISFACTORY CONDITION. REPAIR SHALL INCLUDE BUT NOT BE LIMITED TO REMOVING DEFECTIVE PAVEMENT AND REPLACING WITH NEW PAVEMENT AS DIRECTED BY THE CITY ENGINEER.

7.8 HMA PATCHES SHALL BE CONSTRUCTED IN ACCORDANCE TO THE SECTION 442 OF THE STANDARD SPECIFICATIONS FOR CLASS D PATCHES. FOR UTILITY TRENCH HMA PATCHES THE CONTRACTOR SHALL SAWCUT THE PAVEMENT AND PATCH AS SHOWN PER THE CITY DETAIL STANDARD NO. 7.15. SAWCUTTING SHALL BE TO FULL DEPTH OF THE MATERIAL BEING REMOVED.

7.9 PAVEMENT MARKINGS SHALL BE THERMOPLASTIC TYPE AND MEETING THE REQUIREMENTS OF ARTICLE 1095.01 OF THE STANDARD SPECIFICATIONS. MARKINGS SHALL BE APPLIED ONLY WHEN THE PAVEMENT TEMPERATURE IS 55 F DEG. OR ABOVE AND NO LATER THAN NOVEMBER 1 OR EARLIER THAN APRIL 15. BEFORE APPLYING THE MARKING MATERIAL, THE PAVEMENT SHALL BE CLEANED ACCORDING TO THE MANUFACTURER, DRY, AND FREE OF DEBRIS. APPLICATION SHALL BE IN ACCORDANCE TO SECTION 780 OF THE STANDARD SPECIFICATIONS.

8. WATER MAIN CONSTRUCTION

8.1 PIPE MATERIAL: ALL WATER MAIN PIPE SHALL BE DUCTILE IRON PIPE, CLASS 52 MINIMUM OR AS SHOWN ON THE PLANS AND SHALL BE CEMENT LINED IN ACCORDANCE WITH AWWA C104. JOINTS SHALL BE PUSH-TYPE UNLESS OTHERWISE SHOWN ON THE PLANS. NO ALTERNATE PIPE MATERIAL, SUCH AS PVC PLASTIC, ETC., SHALL BE CONSIDERED ACCEPTABLE WITHOUT THE WRITTEN CONSENT OF THE CITY ENGINEER, AND ALL PUBLIC BODIES HAVING JURISDICTION. UPON REQUEST, THE CONTRACTOR SHALL PROVIDE THE CITY AND ENGINEER WITH SUPPLIERS' PRODUCT TEST REPORTS, CATALOG INFORMATION, ALTERNATE BIDS OR ANY OTHER INFORMATION THAT THE CITY AND ENGINEER MAY FIND NECESSARY IN CONSIDERING THE ALTERNATE MATERIAL. THE ACCEPTANCE OF THE PROPOSED ALTERNATE WILL IN NO WAY BE WARRANTIED BY THESE SUBMITTALS.

8.2 PIPE FITTINGS: ALL WATER MAIN FITTINGS FOR UNDERGROUND CONSTRUCTION APPLICATIONS SHALL BE DUCTILE IRON PIPE FITTINGS, WITH MECHANICAL JOINTS. FITTINGS AND SPECIALS SHALL BE EITHER CAST IRON OR DUCTILE IRON AND SHALL CONFORM TO AWWA C-153. JOINTS SHALL BE MECHANICAL JOINT IN ACCORDANCE WITH ANSI A21.11 (AWWA C-111 AND AWWA C-600). FITTINGS AND SPECIALS SHALL BE BITUMINOUS (SEAL) COATED ON THE EXTERIOR AND CEMENT-MORTAR LINED ON THE INTERIOR IN ACCORDANCE WITH AWWA C-104. FITTINGS AND SPECIALS SHALL BE FURNISHED AND INSTALLED WITH ACCESSORIES NECESSARY FOR A COMPLETE AND OPERATING INSTALLATION. MEGA-LUG RETAINER GLANDS AND CONCRETE THRUST BLOCKS SHALL BE USED ON ALL OFFSET FITTINGS. REFER TO THE CITY STANDARD NO. 6.10 FOR THRUST BLOCK DETAILS.

8.3 VALVE VAULT FRAMES AND LIDS: FRAMES AND LIDS FOR VALVE VAULTS SHALL CONFORM TO EAST JORDAN CASTING NO. 1020 OR APPROVED EQUAL. THE WORDS "CITY OF BATAVIA" AND "WATER" SHALL BE CAST INTO THE LIDS. REFER TO THE CITY DETAIL STANDARD NO. 6.01 FOR DETAILED INFORMATION ON VALVES AND DETAIL 6.04 FOR DETAILED INFORMATION ON LIDS

8.4 FIRE HYDRANT ASSEMBLY: FIRE HYDRANTS SHALL HAVE A 6-INCH DIAMETER BARREL AND SHALL BE CLOW MEDALLION OR APPROVED EQUAL.THE FIRE HYDRANT ASSEMBLY SHALL CONSIST OF: MAIN LINE TEE, CONNECTING 6-INCH PIPE 6-INCH AUXILIARY GATE VALVE WITH CAST IRON BOX, CONNECTING RODS, AND HYDRANT WITH BREAKAWAY FLANGE AND BRONZE TO BRONZE SEATING, AND ALL OTHER WORK AND MATERIALS FOR A COMPLETED INSTALLATION. ALL BELOW GROUND LEVEL NUTS BOLTS ARE TO BE STAINLESS STEEL. ALL HYDRANTS SHALL BE FACTORY PAINTED MATCHING THE CITY OF BATAVIA COLOR. HYDRANTS SHALL HAVE HYDRANT LOCATORS PER DETAIL. REFER TO THE CITY DETAIL STANDARD NO. 6.03 FOR DETAILED INFORMATION ON THE FIRE HYDRANT ASSEMBLY.

MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CAD - Sheets\241108-shh-gmm0es07.dgn

- 8.5 MINIMUM COVER: ALL WATER MAINS SHALL HAVE A MINIMUM COVER OF 5.5 FEET AND A MAXIMUM OF 10' (UNLESS APPROVED BY THE CITY ENGINEER) MEASURED FROM PROPOSED FINISHED GROUND LINE. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN THIS MINIMUM DEPTH OF COVER.
- 8.6 GATE VALVES: THE CONTRACTOR SHALL FURNISH AND INSTALL RESILIENT WEDGE GATE VALVES CONFORMING TO (AWWA C-515) AND SHALL BE MUELLER WATEROUS, CLOW OR APPROVED EQUAL. VALVES TO BE INSTALLED IN A VALVE VAULT AS SHOWN ON THE PLANS. ALL NUTS AND BOLTS ON VALVE ARE TO BE STAINLESS STEEL. MEG-A-LUGS SHALL BE USED. INTERIOR OF VALVE SHALL BE COATED WITH A RESINOUS OR POLYMERIC COATING CONFORMING TO AWWA C-550. REFER TO THE CITY DETAIL STANDARD NO. 6.01 FOR DETAILED INFORMATION ON VALVES.
- 8.7 THRUST RESTRAINT: REINFORCED CONCRETE BLOCKS AND "MEGA-LUG" JOINT RESTRAINTS SHALL BE USED FOR THRUST RESTRAINT ON ALL FITTINGS. USE OF PRECAST THRUST BLOCKS SHALL BE LIMITED TO FIRE HYDRANT INSTALLATIONS (AS NOTED ON THE TYPICAL HYDRANT DETAIL DRAWING) AND FOR PIPE DIAMETERS SMALLER THAN 12-INCH. AS NOTED ON THE TYPICAL DETAIL DRAWINGS. REFER TO THE CITY DETAIL STANDARDS NO. 6.09 AND 6.10 FOR DETAILED INFORMATION ON THRUST BLOCKS AND RESTRAINED JOINTS.
- 8.8 POLYETHYLENE ENCASEMENT TUBING: THE CONTRACTOR SHALL FURNISH AND INSTALL POLYETHYLENE ENCASEMENT TUBING FOR ALL DUCTILE IRON PIPE. POLYETHYLENE ENCASEMENT TUBING SHALL BE FURNISHED AND INSTALLED IN ACCORDANCE WITH ANSI A21.5 (AWWA C-105), SHALL BE CLASS "C" POLYETHYLENE MATERIAL, AND SHALL BE INSTALLED EITHER BY "METHOD A" OR "METHOD B" AS LISTED IN ANSI A21.5. THE POLYETHYLENE ENCASEMENT TUBING SHALL BE BLUE IN COLOR UNLESS OTHERWISE DIRECTED BY THE ENGINEER. SECURE THE TUBING ALONG THE LENGTH OF THE WATERMAIN AT EVERY 3FT ALONG THE PIPE BARREL AND AT JOINTS AS NOTED. NOTE THAT WHEN LIFTING THE POLYETHYLENE ENCASED PIPE WITH A BACKHOE, USE FABRIC TYPE "SLING" OR PADDED CABLE TO PROTECT THE POLYETHYLENE. CAREFUL ATTENTION SHALL BE TAKEN WHEN MOUNTING TABBING MACHINES TO PROTECT THE TUBING FOR SERVICE CONNECTIONS. FOLLOW THE RECOMMENDED GUIDELINES FOR SERVICE TAPS IN THE ANSI STANDARD.
- 8.9 SERVICE PIPE AND FITTINGS: WATER SERVICE PIPE INSTALLED FOR HOUSE SERVICES SHALL BE MINIMUM 1-INCH DIAMETER COPPER PIPE, TYPE "K" CONFORMING TO LATEST REQUIREMENTS OF THE ILLINOIS PLUMBING CODE. FITTINGS SHALL BE BRONZE AND OF THE COMPRESSION TYPE. COPPER PIPE SHALL BE ONE PIECE FROM THE TAP TO THE CURB BOX.
- 8.10 CORPORATION AND CURB STOPS: WATER SERVICE STOPS SHALL BE OF BRASS, AND OF THE TYPE THAT IS STANDARD WITH THE CITY DETAIL 6.02 ALL CORP AND CURB STOPS SHALL BE STAMPED WITH "NL".
- 8.11 TAPPING VALVE AND SLEEVE: TAPPING VALVES AND SLEEVES SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS OF THE SIZE SHOWN ON THE PLANS. TAPPING VALVES SHALL CONFORM TO AWWA SPECIFICATION C-515, RESILIENT WEDGE GATE VALVES. TAPPING VALVES AND SLEEVES SHALL BE INSTALLED IN PRECAST CONCRETE VAULTS OF THE SIZE AND TYPE SHOWN ON THE PLAN. ALL TAPPING TEES SHALL BE STAINLESS STEEL. REFER TO THE CITY DETAIL STANDARD NO. 6.07 FOR DETAILED INFORMATION ON PRESSURE CONNECTIONS.
- 8.12 SHOP DRAWINGS SHALL BE SUBMITTED FOR ALL WATERMAIN AND APPURTENANCES TO BE PROVIDED AND APPROVED BY THE CITY ENGINEER OR THEIR REPRESENTATIVE PRIOR TO DELIVERY OF MATERIALS TO THE CONSTRUCTION SITE. SUBMITTALS WILL INCLUDE CATALOGUE DATA, WEIGHTS, ASSEMBLY DRAWINGS, COATINGS INFORMATION, AFFIDAVITS OF COMPLIANCE, AND RECORDS OF THE TESTING REQUIREMENTS AS SET FORTH IN THE APPLICABLE AWWA STANDARD FOR THE MATERIAL BEING PROVIDED.
- 8.13 LEAKAGE TESTING AND DISINFECTING: ALL WATER MAINS SHALL BE TESTED FOR LEAKAGE UNDER PRESSURE AND BE DISINFECTED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS AND TO THE SATISFACTION OF THE CITY OF BATAVIA WATER DEPARTMENT. A CITY REPRESENTATIVE SHALL BE PRESENT DURING TESTING.

9. RESTORATION AND LANDSCAPING

- 9.1 ALL EXCAVATED MATERIALS FOR CURBS OR WALKS IS TO BE REMOVED FROM SITE. THIS SPOIL MAY NOT TO BE USED AS BACKFILL.
- 9.2 CUT EDGE OF EXCAVATION AWAY TO ALLOW FOR PROPER COMPACTION.

- 9.3 BACKFILL ALL OVER-DUG OR EXCAVATED AREAS WITH PULVERIZED TOPSOIL, EITHER MANUALLY OR MECHANICALLY. (SOURCE TO BE APPROVED BY CITY ENGINEER OR ENGINEER'S REPRESENTATIVE)
- 9.4 COMPACT PULVERIZED TOPSOIL IN 4" TO 6" LIFTS TO MINIMIZE SETTLEMENT UNLESS OTHERWISE NOTED BY THE ENGINEER.
- 9.5 MANUALLY FEATHER PULVERIZED TOPSOIL INTO EXISTING GRADES OR NO GREATER THAN 4:1, APPROXIMATELY 2' TO 4' FEET IN FRONT OF AND BEHIND NEW CURBS, WALKS OR BOTH SIDE OF EXCAVATION FOR PUBLIC IMPROVEMENTS OR AS DIRECTED BY CITY ENGINEER OR THEIR DESIGNEE IN ORDER TO CREATE A SMOOTH, CONSISTENT AND MAINTAINABLE SURFACE. (NOTE: ON LARGER PROJECTS THIS MAY BE DONE MECHANICALLY. IN ALL CASES WHERE WORK IS ADJACENT TO EXISTING TURF, FINISH WORK MUST BE MANUALLY RAKED.)
- 9.6 SEED BLENDS (PLEASE PROVIDE TAG FROM BAG TO CITY REPRESENTATIVE):
A) LOW SALT IMPACT AREAS:
50% EQUAL QUANTITIES OF 2 VARIETIES OF IMPROVED KENTUCKY BLUE GRASS (98/85)
50% EQUAL QUANTITIES OF 2 VARIETIES OF TURF TYPE PERENNIAL RYE GRASS (98/90)
B) HIGH SALT IMPACT AREAS (I.E. RIGHT OF WAY / PARKWAY):
USE CLASS 1A SALT TOLERANT "I.D.O.T." BLEND WITH 1/2 RATE OF LOW SALT IMPACT AREA BLEND
- 9.7 SEED TO BE INSTALLED AT THE RATE LISTED IN SECTION 250 OF THE IDOT SPEC BOOK. EITHER MECHANICALLY OR MANUALLY. SEED TO BE RAKED IN OR LIGHTLY COVERED IN A METHOD APPROVED BY CITY ENGINEER OR ENGINEER'S DESIGNEE FROM APRIL 1 TO JUNE 15 AND AUGUST 1 TO NOVEMBER 1
- 9.8 WITHIN 24 HRS. SEEDED AREAS TO BE COVERED PER THE IDOT SPEC 251 UNLESS THE SLOPE IS GREATER THAN 3:1, WHICH IT MUST BE COVERED THE SAME DAY. BLANKET TO USE BIODEGRADABLE STAPLES. THE LONGEVITY OF THE EROSION CONTROL BLANKET PRODUCT TAKE INTO CONSIDERATION THE SITE CONDITIONS AND REQUIRED DEGREE OF STABILIZATION. FOR RESIDENTIAL PARKWAY AREAS OR AS DIRECTED BY THE CITY ENGINEER, EROSION CONTROL BLANKET SHALL BE "ULTRA-SHORT TERM" SUCH THAT THE BLANKET AND NETTING WILL DECOMPOSE WITHIN 3 MONTHS.
- 9.9 IMMEDIATELY UPON COMPLETION OF STRAW PLACEMENT A LIGHT COVERING OF ADHESIVE TREATED HYDROMULCH TO BE INSTALLED TO HOLD STRAW IN PLACE.
- 9.10 ALL MATERIALS, WORK METHOD, EQUIPMENT AND SCHEDULING OF WORK TO BE APPROVED BY CITY ENGINEER OR THEIR DESIGNEE PRIOR TO COMMENCEMENT OF LANDSCAPE RESTORATION WORK.

10. EROSION AND SEDIMENT CONTROL CONSTRUCTION

- 10.1 UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL MEASURES WILL BE CONSTRUCTED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS IN THE LATEST EDITION OF THE ILLINOIS URBAN MANUAL.
- 10.2 THE KANE-DUPAGE SOIL AND WATER CONSERVATION DISTRICT (KDSWCD) MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITIES, AND ONE WEEK PRIOR TO THE FINAL INSPECTION.
- 10.3 A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- 10.4 PRIOR TO COMMENCING LAND-DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING BUT NOT LIMITED TO, ADDITIONAL PHASES OF DEVELOPMENT AND OFF-SITE BORROW OR WASTE AREAS) A SUPPLEMENTARY EROSION CONTROL PLAN SHALL BE SUBMITTED TO THE OWNER FOR REVIEW BY THE KDSWCD.
- 10.5 THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE

KDSWCD.

- 10.6 DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO SEDIMENT BASINS OR SILT TRAPS. DEWATERING DIRECTLY INTO FIELD TILES OR STORMWATER STRUCTURES IS PROHIBITED. THE CONTRACTOR IS RESPONSIBLE FOR PREPARING AND SUBMITTING A DEWATERING PLAN FOR APPROVAL TO THE OWNER AND KDSWCD PRIOR TO STARTING ANY DEWATERING OPERATIONS.
- 10.7 ANY DEWATERING OPERATIONS SHALL FOLLOW ILLINOIS URBAN MANUAL PRACTICE STANDARD 813-DEWATERING.
- 10.8 IT IS THE RESPONSIBILITY OF THE LANDOWNER AND/OR GENERAL CONTRACTOR TO INFORM ANY SUB-CONTRACTOR(S) WHO MAY PERFORM WORK ON THIS PROJECT, OF THE REQUIREMENTS OF IMPLEMENTING AND MAINTAINING THESE EROSION CONTROL PLANS AND THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT REQUIREMENTS SET FORTH BY THE ILLINOIS EPA.
- 10.9 ALL AREAS OF THE CONSTRUCTION SITE THAT HAVE NOT BEEN FINALLY STABILIZED, STRUCTURAL CONTROL MEASURES, AND LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE MUST BE INSPECTED AT LEAST ONCE EVERY SEVEN CALENDAR DAYS OR ONCE EVERY 14 CALANDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM THAT IS 0.25 INCHES OR GREATER OR EQUIVALENT SNOWFALL.
- 10.10 IN AREAS WHERE WORK IS COMPLETE, PERMANENT STABILIZATION SHALL OCCUR WITHIN 7 DAYS OF COMPLETION. IN AREAS WHERE WORK HAS TEMPORARILY CEASED FOR 14 DAYS OR MORE, TEMPORARY STABILIZATION SHALL OCCUR BY THE 14TH DAY AFTER WORK HAS CEASED.
- 10.11 THE DEVELOPER IS RESPONSIBLE FOR SUPPLYING THE CITY OF BATAVIA WITH WEEKLY SOIL EROSION REPORTS.
- 10.12 DUST CONTROL: PROVISIONS SHALL BE MADE TO HAVE THE PUBLIC STREETS SWEEPED WITH A MECHANICAL SWEEPER ON A WEEKLY BASIS, UNLESS REQUIRED DAILY BY THE CITY ENGINEER OR THEIR DESIGNEE. IN ADDITION, THE SITE DUST SHALL BE KEPT TO A MINIMUM BY SPRAYING THE SITE DOWN DAILY WITH WATER TO BE PROVIDED BY THE CONTRACTOR. A METER FOR THE WATER MUST BE OBTAINED FROM THE WATER DIVISION AT PUBLIC WORKS.

- 10.13 CONCRETE WASHOUT SHALL NOT BE LOCATED IN A FLOOD-PRONE AREA OR A DESIGNATED BUFFER PROTECTING WATERS OF THE UNITED STATES OR ISOLATED WATERS. STOCKPILING OF MATERIAL IS NOT ALLOWED ON-SITE.
- 10.14 IF POSSIBLE, ANY WORK IN THE WATERWAY SHOULD BE TIMED TO TAKE PLACE DURING LOW OR NO-FLOW CONDITIONS. LOW FLOW CONDITIONS ARE FLOW AT OR BELOW THE NORMAL WATER ELEVATION.
- 10.15 WHEN OUTLET WORK IS BEING CONDUCTED, DISTURBED AREAS SHOULD BE STABILIZED AT THE END OF EACH WORK DAY.

11. CONSTRUCTION SEQUENCE

- A. INSTALLATION OF ALL EROSION CONTROL MEASURES:
1. PIPE AND INLET PROTECTION
2. PERIMETER EROSION BARRIER
3. SILT CURTAIN
- B. INSTALLATION OF PROPOSED STORM SEWER AND OUTFALL
- C. CONSTRUCTION OF PROPOSED BIKE RAMP
- D. STABILIZATION AND SEEDING OF VEGETATED AREAS
- E. REMOVAL OF REMAINING EROSION CONTROL ITEMS

HOT-MIX ASPHALT REQUIREMENTS

MIXTURE TYPE	VOIDS
FULL-DEPTH PARKING LOT PAVEMENT	
HMA SURFACE COURSE, IL-9.5, MIX "D", N50, 1.5"	4% @ 50 GYR
HMA BINDER COURSE, IL-19.0, N50, 2.5"	4% @ 50 GYR

NOTES

1. THE UNIT WEIGHT USED TO CALCULATE ALL HMA MIXTURE QUANTITIES IS 112 LBS/SQYD/IN.
2. FOR USE OF RECYCLED MATERIALS SEE IDOT DISTRICT SPECIAL PROVISION FOR "RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES".
3. THE "AC TYPE" FOR POLYMERIZED HMA MIXES SHALL BE "SBS/SBR PG 76-22" AND FOR NON-POLYMERIZED HMA THE "AC TYPE" SHALL BE "PG 64-22" UNLESS MODIFIED BY THE SPECIAL PROVISION.



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann	DESIGNED - _____	- _____	- _____
	DRAWN - _____	- _____	- _____
PLOT SCALE =	CHECKED - _____	- _____	- _____
PLOT DATE = 4/25/2025	DATE - _____	- _____	- _____

DESIGNED - _____	- _____	- _____
DRAWN - _____	- _____	- _____
CHECKED - _____	- _____	- _____
DATE - _____	- _____	- _____

DESIGNED - _____	- _____	- _____
DRAWN - _____	- _____	- _____
CHECKED - _____	- _____	- _____
DATE - _____	- _____	- _____

DESIGNED - _____	- _____	- _____
DRAWN - _____	- _____	- _____
CHECKED - _____	- _____	- _____
DATE - _____	- _____	- _____

PEACE BRIDGE BIKE RAMP

ILLINOIS

GENERAL NOTES

SCALE: NONE

SHEET

4

OF

4

SHEETS

STA.

TO STA.

COUNTY

TOTAL
SHEETS

SHEET
NO.

KANE

63

5

MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CA00_Sheets\DT241108-shit-LS-0007.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME	= mfortmann
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED	-	_____
DRAWN	-	_____
CHECKED	-	_____
DATE	-	_____

-	_____
-	_____
-	_____
-	_____

-	_____
-	_____
-	_____
-	_____

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

SUMMARY OF QUANTITIES

SCALE: NONE SHEET 1 OF 4 SHEETS STA. TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	6

SPECIAL PROVISION	CODE NO.	ITEM	UNIT	TOTAL QUANTITY
	20200100	EARTH EXCAVATION	CU YD	50
	20200200	ROCK EXCAVATION	CU YD	450
	20800150	TRENCH BACKFILL	CU YD	380
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	344
	21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	7
	25000210	SEEDING, CLASS 2A	ACRE	0.012
	25100630	EROSION CONTROL BLANKET	SQ YD	59
	28000400	PERIMETER EROSION BARRIER	FOOT	131
	28000510	INLET FILTERS	EACH	1
	28100109	STONE RIPRAP, CLASS A5	SQ YD	39
	28200200	FILTER FABRIC	SQ YD	5
	30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	50
	31101180	SUBBASE GRANULAR MATERIAL, TYPE B 2"	SQ YD	588
	31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	31
	35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	109
	35300060	PORTLAND CEMENT CONCRETE BASE COURSE, 4"	SQ YD	31
	40602978	HOT-MIX ASPHALT BINDER COURSE, IL- 9.5, N50	TON	15
	40604060	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	TON	9
	42001300	PROTECTIVE COAT	SQ YD	399

MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CADD_Sheets\DT241108-shit-LSO022.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME	= mfortmann
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED	-	_____
DRAWN	-	_____
CHECKED	-	_____
DATE	-	_____

-	_____
-	_____
-	_____
-	_____

-	_____
-	_____
-	_____
-	_____

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

SUMMARY OF QUANTITIES

SCALE: NONE	SHEET	2	OF	4	SHEETS	STA.	TO STA.
-------------	-------	---	----	---	--------	------	---------

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	7

SPECIAL PROVISION	CODE NO.	ITEM	UNIT	TOTAL QUANTITY
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2,202
	42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	3,094
	44000100	PAVEMENT REMOVAL	SQ YD	217
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	19
	44000600	SIDEWALK REMOVAL	SQ FT	1,620
	50102400	CONCRETE REMOVAL	CU YD	2
	50200100	STRUCTURE EXCAVATION	CU YD	2,722
	50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	8
	50300225	CONCRETE STRUCTURES	CU YD	0.42
	50300254	RUBBED FINISH	SQ FT	2,705
	50300285	FORM LINER TEXTURED SURFACE	SQ FT	628
	50500505	STUD SHEAR CONNECTORS	EACH	284
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	17,800
	50901720	BICYCLE RAILING (RAILING A)	FOOT	26
	52200105	FURNISHING SOLDIER PILES (W SECTION)	FOOT	520
	52200200	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	607
	52200205	DRILLING AND SETTING SOLDIER PILES (IN ROCK)	CU FT	785
	52200250	Untreated Timber Lagging	SQ FT	1,963
	52200900	CONCRETE STRUCTURES (RETAINING WALL)	CU YD	124

MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CADD_Sheets\241108-shit-LSC003.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME	= mfortmann
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED -	_____	-	_____	-	_____
DRAWN -	_____	-	_____	-	_____
CHECKED -	_____	-	_____	-	_____
DATE -	_____	-	_____	-	_____

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

SCALE: NONE

SHEET 3 OF 4 SHEETS

STA. TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	8

SPECIAL PROVISION	CODE NO.	ITEM	UNIT	TOTAL QUANTITY
	54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1
	542C1053	PIPE CULVERTS, CLASS C, TYPE 2 8"	FOOT	11
	542C1893	PIPE CULVERTS, CLASS C, TYPE 3 8"	FOOT	7
	550B0430	STORM SEWERS, CLASS B, TYPE 2 30"	FOOT	50
	550B0730	STORM SEWERS, CLASS B, TYPE 3 30"	FOOT	131
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	274
	60146304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	362
	60203805	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1
	60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1
	60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	10
	67100100	MOBILIZATION	L SUM	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
	72000100	SIGN PANEL - TYPE 1	SQ FT	17
	73000100	WOOD SIGN SUPPORT	FOOT	6
	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	16
	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	535
	78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	90
*	X0300019	REMOVE AND REINSTALL PARKING BLOCKS	EACH	1

EXISTING LEGEND


- (A) PORTLAND CEMENT CONCRETE PAVEMENT
- (B) RETAINING WALL
- (C) HOT-MIX ASPHALT PARKING LOT PAVEMENT
- (D) EXISTING GROUND
- (E) BRICK PAVERS
- (F) EXISTING RAILING
- (G) EXISTING BEDROCK (SEE GEOTECHNICAL REPORT)

PROPOSED LEGEND


- (1) PORTLAND CEMENT CONCRETE SIDEWALK, 5"
- (2) COMPACTED AGGREGATE SUBBASE, CA-6, 2"
- (3) HMA SURFACE COURSE, IL-9.5, MIX "D", N50, 1.5"
- (4) HMA BINDER COURSE, IL-19.0, N50, 2.5"
- (5) AGGREGATE BASE COURSE, TYPE B, 6"
- (6) PROPOSED RETAINING WALL
- (7) PROPOSED RAILING
- (8) PORTLAND CEMENT CONCRETE SIDEWALK, 6"
- (9) BRICK PAVERS
- (10) SAND CUSHION, 1"
- (11) PORTLAND CEMENT CONCRETE BASE COURSE, 4"
- (12) COMPACTED AGGREGATE SUBBASE, CA-6, 4"
- (13) WOVEN GEOTECHNICAL FABRIC (FOLD UP AT EDGES PLACED AT JOINT AND OVER DRAIN HOLES) - TYPE AND THICKNESS PER MANUFACTURES RECOMMENDATIONS
- (14) 2" DRAIN HOLES, 2' O/C, AT LOW POINTS AND BACK OF CURB (FILL WITH PEA GRAVEL)
- (15) SEEDING, CLASS 2A TOPSOIL EXCAVATION AND PLACEMENT, 4"
- (16) AGGREGATE SUBGRADE IMPROVEMENT AT LOCATIONS DETERMINED BY THE ENGINEER
- (17) 30" REINFORCED CONCRETE PIPE STORM SEWER
- (18) TRENCH BACKFILL (SEE UTILITY TRENCH SECTION DETAIL)

NOTES

- ALL TYPICAL SECTION VIEWS FACING EAST.
- SEE GENERAL NOTES FOR HOT-MIX ASPHALT REQUIREMENTS.




PEDESTRIAN BRICK PAVER AREA
AT RIVER STREET - TYPICAL SECTION




EXISTING TYPICAL SECTION
PEACE BRIDGE RAMP

STA 10+25.00 TO STA 10+90.46
(STA 11+53.11 TO STA 12+18.09)




EXISTING TYPICAL SECTION
PEACE BRIDGE RAMP

STA 10+90.46 TO STA 11+53.11




EXISTING TYPICAL SECTION
PEACE BRIDGE RAMP

STA 12+18.09 TO STA 12+33.36




EXISTING TYPICAL SECTION
PEACE BRIDGE RAMP

STA 12+33.36 TO STA 12+91.08
*STAIRS DOWN FROM STA 12+53.48 TO STA 12+80.24
**PEACE BRIDGE RAMP BEGINS STA 12+53.48




PROPOSED TYPICAL SECTION
PEACE BRIDGE RAMP

STA 10+25.00 TO STA 10+99.08
(STA 11+44.01 TO STA 12+18.09)
*STA 11+44.01 TO STA 11+50.05
**STA 12+17.85 TO STA 12+18.09




PROPOSED TYPICAL SECTION
PEACE BRIDGE RAMP

STA 10+99.08 TO STA 11+44.01
*STA 11+34.44 TO STA 11+44.01



PROPOSED TYPICAL SECTION
PEACE BRIDGE RAMP

STA 12+18.09 TO STA 12+33.36



PROPOSED TYPICAL SECTION
PEACE BRIDGE RAMP

STA 12+33.36 TO STA 12+91.08
*STAIRS DOWN FROM STA 12+53.48 TO STA 12+80.24
**PEACE BRIDGE RAMP BEGINS STA 12+53.48

MODEL: Default
FILE NAME: N:\2024\2410\Drawings\Main\CA-DD_Sheets\01241108-eth\typical01.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

TYPICAL SECTIONS

SCALE: NONE SHEET 1 OF 1 SHEETS STA. 10+00.00 TO STA. 12+91.08

COUNTY TOTAL SHEETS SHEET NO.
KANE 63 10

NST NASHnal SOIL TESTING							BOREHOLE LOG				Number B-1				
23856 W. Andrew Rd, Unit 103, Plainfield							Client		V3 Companies				Plate 3		
							Location		Ramp to Existing Pedestrian Bridge-111 N. River St., Batavia, IL-60510						
							Job Number		2024-1301-14G						
							Drill Rig Type		Geoprobe 7822						
							Sampler Type		Split Spoon (SS)						
							Boring Location		See Plate 2 (1888430.990N, 991544.883 E)						
							Boring Elevation (ft)		660.00				Date: 11/20/2024		
Sample #	Sampling Method	Qp (tsf)	Sample Recovery (in)	Moisture Content (%)	Driving Resistance Blows/ft (N)	Depth (ft)	Sample Depth	Graphic	Soil Description				Elevation (ft)		
						0.5		TS SP-GP	4 inches of Top Soil				659.50		
						1.0			Gray Sandy Gravel (SP-GP)				659.00		
						1.5			Medium Dense-Weathered Bedrock				658.50		
1	SS	N/A	2.0	NA	25.0	2.0							658.00		
						2.5							657.50		
						3.0						657.00			
						3.5		Auger Refusal at 3.5' - Bedrock				656.50			
									End of Boring at 3.5'						
									Water Level While Drilling : None						
									Water Level After Drilling : None						
									Cave In Depth : None						

NST NASHnal SOIL TESTING							BOREHOLE LOG				Number B-2				
23856 W. Andrew Rd, Unit 103, Plainfield							Client		V3 Companies				Plate 4		
							Location		Ramp to Existing Pedestrian Bridge-111 N. River St., Batavia, IL-60510						
							Job Number		2024-1301-14G						
							Drill Rig Type		Geoprobe 7822						
							Sampler Type		Split Spoon (SS)						
							Boring Location		See Plate 2 (1888425.999N, 991649.798 E)						
							Boring Elevation (ft)		669.00				Date: 11/20/2024		
Sample #	Sampling Method	Qp (tsf)	Sample Recovery (in)	Moisture Content (%)	Driving Resistance Blows/Ft (N)	Depth (ft)	Sample Depth	Graphic	Soil Description				Elevation (ft)		
						0.5		TS	3 inches of Top Soil				668.50		
						1.0			Dark Brown Topsoil Mix Fill (FILL)				668.00		
						1.5			Traces Gravel and Rock-Loose				667.50		
1	SS	N/A	18.0	25.1	7.0	2.0			FILL					667.00	
						2.5								666.50	
						3.0						666.00			
					50/4*	3.5			Auger Refusal at 3.5' - Bedrock				665.50		
									End of Boring at 3.5'						
									Water Level While Drilling : None						
									Water Level After Drilling : None						
									Cave In Depth : None						

NST NASHnal SOIL TESTING							BOREHOLE LOG				Number B-3			
23856 W. Andrew Rd, Unit 103, Plainfield							Client		V3 Companies				Plate 5	
							Location		Ramp to Existing Pedestrian Bridge-111 N. River St., Batavia, IL-60510					
							Job Number		2024-1301-14G					
							Drill Rig Type		Geoprobe 7822					
							Sampler Type		Split Spoon (SS)					
							Boring Location		See Plate 2 (1888417.531N, 991573.058 E)					
							Boring Elevation (ft)		664.00				Date: 11/20/2024	
Sample #	Sampling Method	Qp (tsf)	Sample Recovery (in)	Moisture Content (%)	Driving Resistance Blows/ft (N)	Depth (ft)	Sample Depth	Graphic	Soil Description				Elevation (ft)	
						0.5		TS	4 inches of Top Soil				663.50	
						1.0			Dark Brown Topsoil mix Fill (FILL)				663.00	
						1.5			Traces Gravel and Rock-Loose				662.50	
1	SS	N/A	12.0	27.4	7.0	2.0							662.00	
						2.5							661.50	
						3.0		FILL					661.00	
						3.5							660.50	
						4.0							660.00	
2	SS	N/A	6.0	24.8	9.0	4.5							659.50	
						5.0							659.00	
						5.5		ROCK					658.50	
						6.0							658.00	
						6.5			Light Brown Weathered Rock (Rock)				657.50	
3	SS	N/A	2.0	4.8	50/3"	7.0			Weatherd Rock-Very Dense				657.00	
						7.5			Auger Refusal at 7.5' - Bedrock				656.50	
End of Boring at 7.5'														
Water Level While Drilling : None														
Water Level After Drilling : None														
Cave In Depth : None														
Note: Soil group symbol and group name are determined based on visual classification. Plasticity index and liquid limit were estimated using ASTM D2488 due to insufficient material availability														

ROCK DEPTH AND ROCK QUALITY DETERMINATION										
BORING	NORTHING	EASTING	CORE RECOVERY	ROCK QUALITY DESIGNATION INDEX (RQD)	SAMPLE	DISTANCE FROM TOP OF ROCK	DISTANCE FROM SURFACE	COMPRESSIVE STRENGTH	SHEAR STRENGTH (ESTIMATE)	COMMENTS
B-1	1888435.051	991570.302	78%	LESS THAN 25% (VERY POOR)	A	3 FT	16 FT	3630 PSI	1820 PSI	TOP OF THE HIGHLY WEATHERED ROCK WAS ENCOUNTERED AT 7 FEET BELOW SURFACE AND ROCK CORE STARTED AT 13 FEET. A 10-FEET LONG CORE WAS RETRIEVED BETWEEN 13 AND 23 FEET.
					B	9 FT	22 FT	4300 PSI	2150 PSI	
B-2	1888439.846	991638.739	98%	LESS THAN 25% (VERY POOR)	A	3 FT	15 FT	5110 PSI	2560 PSI	TOP OF THE HIGHLY WEATHERED ROCK WAS ENCOUNTERED AT 7 FEET BELOW SURFACE AND ROCK CORE STARTED AT 12 FEET. A 10-FEET LONG CORE WAS RETRIEVED BETWEEN 12 AND 22 FEET.
					B	9 FT	21 FT	5790 PSI	2900 PSI	

MODEL: Default
FILE NAME: R2024241108Drawings\Map\0_CADD_Sheets\DT241108-shr-sch-bw-11p01.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

SCALE: NONE

SHEET

1

OF

1

SHEETS

STA.

TO STA.

SOIL BORING LOGS

COUNTY

TOTAL SHEETS

SHEET NO.

KANE


63

11


BENCHMARK POINTS				
B.M. #	NORTHING	EASTING	ELEVATION	DESCRIPTION
101	1889034.66	990854.64	PUBLISHED = 670.53 MEASURED = 670.477	ALUMINUM ROD WITH 6 INCH LID, 37.30 FEET WEST OF NORTHWEST BOLT OF LIGHT BASE, 9.65 FEET EAST OF EAST FACE OF BRICK WALK, AND 4.44 FEET NORTH OF CUT CROSS IN CONCRETE CURB.
10001	1888696.854	991641.996	681.292	SW BONNET BOLT OF HYDRANT WEST OF RIVER ST & SPRING ST
10002	1887989.877	991689.744	681.613	S TAG BOLT OF HYDRANT NW OF RIVER ST & WILSON ST

CONTROL POINTS						
C.P. #	NORTHING	EASTING	STATION	OFFSET	ELEVATION	DESCRIPTION
100	1888443.204	991551.549	12+33.16	5.75' RT	669.23	FOUND CUT CROSS IN TOP OF CURB
101	1888424.241	991568.772	10+25.80	10.63' LT	670.02	FOUND CUT CROSS IN TOP OF WALL
103	1888467.885	991695.152	11+34.44	50.58' RT	675.40	SET CUT CROSS IN TOP OF CURB
108	1888271.684	991478.734	14+53.61	0.69' LT	658.47	FOUND CUT CROSS
109	1888413.531	991499.889	13+10.36	7.68' LT	658.54	SET CUT CROSS

PEACE BRIDGE RAMP ALIGNMENT POINTS			
	NORTHING	EASTING	STATION
POT	1888411.842	991543.752	10+00.00
POT	1888419.359	991652.918	11+09.42
POT	1888444.247	991650.434	11+34.44
POT	1888433.631	991496.260	12+88.97
POT	1888409.257	991487.921	13+14.74
POT	1888389.990	991489.320	13+34.05
POT	1888379.160	991488.120	13+44.95



NOTE:
ELEVATIONS SHOWN REFER TO NAVD88.
COORDINATES SHOWN HEREON ARE ILLINOIS STATE PLANE, EAST ZONE, NAD83(2011) GRID .



MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CA00_Sheets\241108-sh1-A7B01.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

ALIGNMENT, TIES AND BENCHMARKS



SCALE: 1"=20'

SHEET 1 OF 1 SHEETS

STA. 10+00.00


TO STA. 13+43.82

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	12




 <div>V3 Companies 7325 Janes Avenue Woodridge, IL 60517 630.724.9200 phone 630.724.9202 fax www.v3co.com</div>	USER NAME = mfortmann	DESIGNED - _____	- _____	- _____	PEACE BRIDGE BIKE RAMP	EXISTING CONDITION & REMOVAL PLAN	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE =	DRAWN - _____	- _____	- _____			KANE	63	13
	PLOT DATE = 4/25/2025	CHECKED - _____	- _____	- _____			CONTRACT NO. xxxxxx		
		DATE - _____	- _____	- _____					
BATAVIA					ILLINOIS	SCALE: 1"=10'	SHEET 1 OF 1 SHEETS	STA. 10+00.00 TO STA. 13+43.82	

NOTES: (1) SEE SHEETS 40 THROUGH 42 FOR PROPOSED LIGHTING PLANS AND ELECTRICAL DETAILS.
(2) SEE SHEETS 20 THROUGH 34 FOR STRUCTURAL WALL AND RAILING DETAILS.



PAVING LEGEND

	PORTLAND CEMENT CONCRETE SIDEWALK, 6" COMPACTED AGGREGATE SUBBASE, CA-6, 2"		REMOVE AND REPLACE BRICK PAVERS PORTLAND CEMENT CONCRETE BASE, 4" COMPACTED AGGREGATE SUBBASE, CA-6, 4"
	PORTLAND CEMENT CONCRETE SIDEWALK, 5" (HIGH EARLY STRENGTH CONCRETE) COMPACTED AGGREGATE SUBBASE, CA-6, 2"		
	HMA SURFACE COURSE, IL-9.5, MIX "D", N50, 1.5" HMA BINDER COURSE, IL-19.0, N50, 2.5" AGGREGATE BASE COURSE, TYPE B, 6"		



MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CA-6D_Sheets\241108-sh1-2P01.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com


USER NAME = mfortmann
DRAWN =
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -	
DRAWN -	
CHECKED -	
DATE -	

PEACE BRIDGE
BIKE RAMP
BATAVIA
ILLINOIS

SCALE: SEE ABOVE
SHEET 1 OF 1 SHEETS
STA. 10+00.00 TO STA. 13+43.82

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	14
CONTRACT NO. xxxxxx		



LEVEL LANDING

(X.XX%)

EXISTING SLOPE /

(XXX.XX)

EXISTING ELEVATION

X.XX%

GRADING SLOPE

M.E.

MATCH EXISTING

NOTE: SEE GRADING PLAN SHEETS 2 & 3 FOR FINISHED PATH, TOP OF WALL, AND FINISHED GROUND GRADES.

RR-4 STONE RIP RAP
SEE PIPE OUTLET TO CHANNEL
DETAIL ON CONSTRUCTION DETAILS
SHEET 61 FOR SIZE AND DIMENSION

FOX RIVER

LIMITS OF ORDINARY
HIGH WATER MARK


EXISTING PEDESTRIAN
WALKWAY BRIDGE

10-YR FLOODPLAIN
BOUNDARY LINE
100-YR FLOODPLAIN
BOUNDARY LINE
FLOODWAY
BOUNDARY LINE

HMA PAVEMENT

RIVER STREET

PERMEABLE
PAVERS



MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CA00_Sheets\241108-sh1-CA001.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -	-	-	-
DRAWN -	-	-	-
CHECKED -	-	-	-
DATE -	-	-	-

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

SCALE: 1"=10'
SHEET 1 OF 3 SHEETS
STA. 10+00.00 TO STA. 13+43.82

GRADING PLAN

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	16

MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CADD_Sheets\241108-sh1-A0A02.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME	= mfortmann
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED -	_____	-	_____	-	_____
DRAWN -	_____	-	_____	-	_____
CHECKED -	_____	-	_____	-	_____
DATE -	_____	-	_____	-	_____

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

GRADING PLAN

SCALE: 1"=10' SHEET 2 OF 3 SHEETS STA. 10+00.00 TO STA. 13+43.82

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	17

PEACE BRIDGE RAMP ADA RAMP ELEVATION TABLE				
POINT:	STATION	OFFSET	TYPE:	ELEVATION
A	10+26.09	10.00 LT	T/W	669.33
			F/P	668.83
B	10+25.00	0.00	T/W	669.29
			F/P	668.78
			F/G	668.79
C	10+30.00	0.00	T/W	669.29
			F/P	668.53
			F/G	668.88
D	10+30.00	10.00 LT	T/W	669.12
			F/P	668.56
E	10+30.00	11.00 LT	T/W	669.12
			F/P	661.63
F	10+30.00	25.00 LT	T/W	671.93
			F/P	661.64
			F/G	670.15
G	10+50.00	0.00	T/W	669.29
			F/P	667.54
			F/G	669.17
H	10+50.00	10.00 LT	T/W	668.07
			F/P	667.54
I	10+50.00	11.00 LT	T/W	668.07
			F/P	662.62
J	10+50.00	25.00 LT	T/W	673.55
			F/P	662.64
			F/G	671.75
K	10+59.08	0.00	T/W	670.16
			F/P	667.09
			F/G	669.66
L	10+59.08	10.00 LT	T/W	667.59
			F/P	667.09
M	10+64.08	0.00	T/W	670.67
			F/P	667.01
			F/G	669.94
N	10+64.08	10.00 LT	T/W	667.51
			F/P	667.01
O	10+81.58	0.00	T/W	672.46
			F/P	666.14
			F/G	671.22
P	10+81.58	10.00 LT	T/W	666.57
			F/P	666.07

PEACE BRIDGE RAMP ADA RAMP ELEVATION TABLE				
POINT:	STATION	OFFSET	TYPE:	ELEVATION
Q	10+99.08	0.00	T/W	674.24
			F/P	665.27
			F/G	673.08
R	10+99.08	10.00 LT	T/W	665.62
			F/P	665.12
S	11+00.00	0.00	T/W	674.34
			F/P	665.28
			F/G	673.18
T	11+00.00	25.00 LT	T/W	676.87
			F/P	664.91
			F/G	675.16
U	11+09.42	0.00	T/W	675.40
			F/P	665.42
			F/G	674.26
V	11+19.43	0.00	T/W	675.40
			F/P	665.27
			F/G	674.93
W	11+34.41	0.00	T/W	675.40
			F/P	665.05
			F/G	675.21
X	11+34.44	0.00	T/W	676.87
			F/P	665.05
			F/G	675.19
Y	11+44.01	0.00	T/W	676.87
			F/P	664.90
			F/G	675.15
Z	11+20.74	10.00 LT	T/W	665.62
			F/P	665.11
AA	11+50.00	0.00	T/W	676.87
			F/P	664.60
			F/G	675.14
BB	11+50.00	14.00 LT	T/W	665.94
			F/P	664.77
CC	11+50.00	15.00 LT	T/W	665.94
			F/P	665.43
DD	11+50.00	25.00 LT	T/W	673.63
			F/P	665.57
			F/G	672.43
EE	11+52.06	0.00	T/W	676.87
			F/P	664.50
			F/G	675.13

GRADING LEGEND / ABBREVIATIONS

LEVEL LANDING

X.XX%



GRADING SLOPE

(X.XX%)
(XXX.XX)

EXISTING SLOPE /
EXISTING ELEVATION

M.E. MATCH EXISTING

NOTE: SEE GRADING PLAN SHEET 1 FOR LOCATION OF FINISHED PATH AND TOP OF WALL GRADES.



MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CA00_Sheets\DT241108-sh1-ADA03.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME	= mfortmann
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED -	_____	-	_____	-	_____
DRAWN -	_____	-	_____	-	_____
CHECKED -	_____	-	_____	-	_____
DATE -	_____	-	_____	-	_____

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

SCALE: 1"=10'

SHEET 3 OF 3 SHEETS

STA. 10+00.00 TO STA. 13+43.82

GRADING PLAN

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	18



PEACE BRIDGE RAMP ADA RAMP ELEVATION TABLE				
POINT:	STATION	OFFSET	TYPE:	ELEVATION
FF	11+64.01	0.00	T/W	675.90
			F/P	663.91
			F/G	674.19
GG	11+64.01	14.00 LT	T/W	666.70
			F/P	664.01
HH	11+84.01	0.00	T/W	674.28
			F/P	662.91
			F/G	672.47
II	11+84.01	14.00 LT	T/W	667.59
			F/P	662.91
JJ	11+89.01	0.00	T/W	673.88
			F/P	662.84
			F/G	672.08
KK	11+89.01	14.00 LT	T/W	667.85
			F/P	662.84
LL	12+00.00	0.00	T/W	672.99
			F/P	662.29
			F/G	671.20
MM	12+00.00	14.00 LT	T/W	668.43
			F/P	662.28
NN	12+00.00	15.00 LT	T/W	668.43
			F/P	667.89
OO	12+00.00	25.00 LT	T/W	669.29
			F/P	667.88
			F/G	669.08
PP	12+09.01	0.00	T/W	672.26
			F/P	661.84
			F/G	670.48
QQ	12+09.01	14.00 LT	T/W	668.91
			F/P	661.84
RR	12+29.01	0.00	T/W	670.64
			F/P	660.84
			F/G	668.99
SS	12+29.01	14.26 LT	T/W	(668.62±)
			F/P	660.84
TT	12+31.84	0.00	T/W	670.41
			F/P	660.80
			F/G	668.92
UU	12+34.01	0.00	T/W	669.97
			F/P	660.77
			F/G	669.16

PEACE BRIDGE RAMP ADA RAMP ELEVATION TABLE				
POINT:	STATION	OFFSET	TYPE:	ELEVATION
VV	12+34.01	14.37 LT	T/W	(668.57±)
WW	12+50.00	0.00	F/P	660.77
			T/W	666.71
			F/P	660.10
XX	12+50.00	14.40 LT	F/G	665.61
			T/W	(670.04±)
YY	12+54.01	0.00	F/P	660.02
			T/W	665.89
			F/G	664.95
ZZ	12+54.01	14.41 LT	T/W	(668.86±)
			F/P	659.85
AAA	12+80.00	0.00	T/W	660.58
			F/P	658.84
			F/G	660.30
BBB	12+80.00	14.12 LT	T/W	(659.24±)
			F/P	658.63
CCC	12+83.32	0.00	T/W	659.90
			F/P	658.70
			F/G	659.41
DDD	12+83.32	14.09 LT	T/W	(658.98±)
			F/P	(658.49±)
EEE	12+88.97	0.00	T/W	658.62
FFF	13+04.26	0.00	F/P	658.62
			T/W	658.42
GGG	13+12.26	0.00	T/W	(658.32±)
			F/P	(658.32±)
HHH	10+50.53	0.00	T/W	669.29
			F/P	667.52
			F/G	669.19

GRADING LEGEND / ABBREVIATIONS


	LEVEL LANDING	(X.XX%) EXISTING SLOPE /	(XXX.XX) EXISTING ELEVATION
	GRADING SLOPE	M.E.	MATCH EXISTING

NOTE: SEE GRADING PLAN SHEET 1 FOR LOCATION OF FINISHED PATH AND TOP OF WALL GRADES.



LEGEND

LEVEL LANDING



MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CADD_Sheets\241108-sh1-joint.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME	= mfortmann
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED -	_____	-	_____	-	_____
DRAWN -	_____	-	_____	-	_____
CHECKED -	_____	-	_____	-	_____
DATE -	_____	-	_____	-	_____

BATAVIA



PEACE BRIDGE
BIKE RAMP

ILLINOIS

SCALE: 1"=10' SHEET 1 OF 1 SHEETS STA. 10+00.00 TO STA. 13+43.82

JOINTING PLAN

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	19



INDEX OF SHEETS

S1 - General Plan and Notes
 S2 - General Notes
 S3 - Structural Removal and Replacement I
 S3A - Structural Removal and Replacement II
 S4 - South Wall Plan and Elevation
 S5 - South Wall Reinforcement Detail
 S6 - East End Wall Plan and Elevation
 S7 - North Wall Plan and Elevation I
 S8 - North Wall Plan and Elevation II
 S9 - North Wall Reinforcement Detail
 S10 - West End Wall Plan and Elevation
 S11 - Center Wall Plan and Elevation I
 S12 - Center Wall Plan and Elevation II
 S13 - Cross Sections
 S14 - Soldier Pile Wall Details I
 S15 - Soldier Pile Wall Details II
 S16 - Center Wall Details
 S17 - Railing Details

NOTES:

1. Station and offsets are called out along the front face of walls.
2. See Drainage and Utility plan for additional storm sewer and trench drain details.
3. See civil plans for light fixture locations attached to front face of walls.

DESIGN SPECIFICATIONS

2020 AASHTO LRFD Bridge Design Specifications, 9th Edition

DESIGN STRESSES

FIELD UNITS

$f'_c = 3,500$ psi
 $f_y = 60,000$ psi (Reinforcement)
 $f_y = 50,000$ psi (Piles)

CONSTRUCTION SPECIFICATIONS

Illinois Department of Transportation Supplemental Specifications and Recurring Special Provisions Adopted Jan. 1, 2024

Illinois Department of Transportation Standard Specifications For Road and Bridge Construction Adopted Jan. 1, 2022

MODEL: SheetS1
 FILE NAME: N:\2024\24110\Drawings\Main\Structures\CADD_Sheets\24110\Sheet-General Plan.dgn



V3 Companies
 7325 Janes Avenue
 Woodridge, IL 60517
 630.724.9200 phone
 630.724.9202 fax
 www.v3co.com

USER NAME = mfortmann
 PLOT SCALE =
 PLOT DATE = 4/25/2025

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

-
 -
 -
 -

-
 -
 -
 -

BATAVIA

PEACE BRIDGE BIKE RAMP

ILLINOIS

SCALE:

SHEET

GENERAL PLAN AND NOTES

S1 OF

S17 SHEETS

STA.

TO STA.

COUNTY

KANE

TOTAL SHEETS

63

SHEET NO.

20

CAST-IN-PLACE CONCRETE CONSTRUCTION

1.

ALL CAST IN PLACE CONCRETE WORK AND REINFORCING STEEL WORK SHALL BE IN ACCORDANCE WITH SECTIONS 503 AND 508 OF THE IDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, JANUARY 1, 2022 AND SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS EXCEPT AS MODIFIED BY THE CONTRACT PLANS OR CONTRACT SPECIFICATIONS. IN THE EVENT OF A DISCREPANCY, THE CONTRACT PLANS OR CONTRACT SPECIFICATIONS SHALL GOVERN.
2.

ALL EXPOSED CONCRETE EDGES SHALL HAVE A ¾" x 45° CHAMFER, EXCEPT WHERE SHOWN OTHERWISE. CHAMFER ON VERTICAL EDGES SHALL BE CONTINUED A MINIMUM OF ONE FOOT BELOW FINISHED GROUND LEVELS.
3.

ALL EXPOSED SURFACES OF NEW CAST IN PLACE CONCRETE CONSTRUCTION ON THE FRONT FACE OF EACH WALL SHALL BE GIVEN A RUBBED FINISH AND SEALED WITH PROTECTIVE COST. FOR CONCRETE SURFACES EXTENDING BELOW GRADE, THE RUBBED FINISH SHALL EXTEND 1'-0" BELOW THE PROPOSED FINISH GRADE. AT THE FRONT FACE OF WALL. SEE SHEET S13 FOR RUBBED FINISHED LOCATIONS.
4.

ALL EXPOSED SURFACES OF NEW CAST IN PLACE CONCRETE CONSTRUCTION ON THE BACK FACE OF EACH WALL SHALL BE FORMED USING A FORM LINER. ADDITIONALLY, THE FRONT FACE OF THE WEST WALL SHALL BE FORMED USING A FORM LINER. ALL EXPOSED SURFACES SHALL BE SEALED WITH PROTECTIVE COAT. FOR CONCRETE SURFACES EXTENDING BELOW GRADE, THE FORM LINER FINISH SHALL EXTEND 1'-0" BELOW THE PROPOSED FINISH GRADE AT THE BACK FACE OF WALL. SEE SHEET S13 FOR FORM LINER LOCATIONS.
5.

ALL CONSTRUCTION JOINTS SHALL BE BONDED ACCORDING TO ARTICLE 503.09 OF THE IDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, JANUARY 1, 2022 AND RECURRING SPECIAL PROVISIONS.
6.

THE CONCRETE WILL BE STAINED WITH A COLOR OR SANDSTONE AS DETAILED IN THE SPECIFICATIONS. AN ANTI-GRAFFITI COATING SHALL BE APPLIED TO ALL EXPOSED CONCRETE SURFACES.

CONSTRUCTION

1.

CONTRACTOR SHALL NOT SCALE DIMENSIONS FROM THE CONTRACT PLANS FOR CONSTRUCTION PURPOSES.
2.

NO CONSTRUCTION JOINTS EXCEPT THOSE SHOWN ON THE PLANS, WILL BE ALLOWED UNLESS APPROVED BY THE ENGINEER.
3.

NO CONCRETE CUTTING WILL BE PERMITTED UNTIL THE REMOVAL LIMITS HAVE BEEN OUTLINED BY THE CONTRACTOR AND APPROVED BY THE ENGINEER.
4.

THE CONTRACTOR SHALL USE CARE WHEN EXCAVATING AROUND EXISTING FOUNDATIONS. ANY DAMAGE TO THE EXISTING STRUCTURE AND/OR SUPPORTING FOUNDATION SHALL BE REPAIRED OR REPLACED AT THE CONTRACTOR'S EXPENSE AT NO ADDITIONAL COST TO THE CLIENT.

REINFORCEMENT BARS

1.

REINFORCEMENT BARS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M-31 (ASTM A706), GRADE 60, DEFORMED BARS.
2.

REINFORCEMENT BAR BENDING DETAILS SHALL BE IN ACCORDANCE WITH THE LATEST "MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE STRUCTURES", ACI 315.
3.

COVER FROM THE FACE OF CONCRETE TO FACE OF REINFORCEMENT BARS SHALL BE 3" FOR SURFACES FORMED AGAINST EARTH AND 2" FOR ALL OTHER SURFACES UNLESS OTHERWISE SHOWN.
4.

REINFORCEMENT BAR BENDING DIMENSIONS ARE OUT TO OUT.
5.

ALL REINFORCEMENT BARS SHALL BE EPOXY COATED UNLESS OTHERWISE NOTED.
6.

MINIMUM BAR LAPS FOR EPOXY COATED REINFORCEMENT; #4 BAR = 1'-8", #5 BAR = 2'-1"

RETAINING WALL CONSTRUCTION:

1.

ALL RETAINING WALL WORK SHALL BE IN ACCORDANCE WITH SECTION 522 OF THE IDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION , JANUARY 1, 2022 AND SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS EXCEPT AS MODIFIED AS BY THE CONTRACT PLANS OR CONTRACT SPECIFICATIONS. IN THE EVENT OF A DISCREPANCY, THE CONTRACT PLANS OR CONTRACT SPECIFICATIONS SHALL GOVERN.
2.

ALL STRUCTURAL STEEL SHALL BE ASTM A572 GRADE 50.
3.

SOLDIER PILES SHALL BE CLEANED AND GIVEN ONE SHOP COAT OF INORGANIC ZINC RICH PRIMER. COST INCLUDED WITH FURNISHING SOLDIER PILES (W SECTION).

GENERAL NOTES TO CONTRACTOR:

1.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY DIMENSIONS, ELEVATIONS AND DETAILS IN THE FIELD AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO BIDDING, ORDERING OF MATERIALS AND/OR STARTING CONSTRUCTION. SUCH VARIATION WILL NOT BE CAUSE FOR ADDITIONAL COMPENSATION OR A CHANGE IN THE SCOPE OF WORK.
2.

ANY DISCREPANCIES, CONFLICTS, OR AMBIGUITIES ON THE DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER. FAILURE TO DO SO WILL NOT RELIEVE THE CONTRACTOR OF ADDITIONAL COSTS REGARDING THE ABOVE ITEMS.
3.

THE CONTRACTOR SHALL PROTECT THE PUBLIC, TRAFFIC, EXISTING UTILITIES, EXISTING STRUCTURES AND ABUTTING PROPERTY DURING THE CONSTRUCTION. FAILURE TO DO SO WILL NOT RELIEVE THE CONTRACTOR FROM THE EXPENSE OF THE REPAIR AND/OR THE REPLACEMENT OF THESE ITEMS.
4.

ALL DRILLED SOLDIER PILES SHALL BE EMBEDDED A MINIMUM OF 5 FEET INTO SOLID BEDROCK. ALL SPREAD FOOTINGS SHALL BE EMBEDDED A MINIMUM OF 6 INCHES INTO SOLID BEDROCK. PRIOR TO CONSTRUCTION THE BEDROCK CONDITIONS SHALL BE VERIFIED WITH A ROCK CORE.
5.

CONSTRUCTION ACTIVITIES SHALL NOT EXCEED THE ASSUMED SURCHARGE OF 250 PSF.
6.

ANY WORK SPECIFIED BUT NOT ADDRESSED BY THE CONTRACT PLANS OR CONTRACT SPECIFICATIONS SHALL BE CONSTRUCTED ACCORDING TO THE IDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, JANUARY 1, 2022 AND SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS.
7.

FORM LINER SHALL BE SYMONS COLONIAL DRY STACK AS SPECIFIED BY THE CITY OF BATAVIA. THE FORM LINER SHALL HAVE RECESSES NO GREATER THAN 1⅜" DEEP AND SHALL MAINTAIN A MINIMUM CONCRETE COVER OF 1½" AT RECESSED LOCATIONS.
8.

ANY STORAGE OF CONSTRUCTION EQUIPMENT AND MATERIAL BEHIND WALL IS NOT ALLOWED.
9.

IF CONDITIONS ARE ENCOUNTERED THAT REQUIRE A COFFERDAM FOR CONSTRUCTION, THE CONTRACTOR, WITH WRITTEN PERMISSION OF THE ENGINEER, WILL BE PERMITTED TO CONSTRUCT A COFFERDAM IN ACCORDANCE WITH SECTION 502.06 OF THE IDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.
10.

WORK IN THE WATERWAY SHOULD BE TIMED TO TAKE PLACE DURING LOW OR NO-FLOW CONDITIONS. LOW FLOW CONDITIONS ARE FLOW AT OR BELOW THE NORMAL WATER ELEVATIONS.
11.

IF PRESENT, WATER SHALL BE ISOLATED FROM THE IN-STREAM WORK AREA USING A COFFERDAM CONSTRUCTED OF NONERODIBLE MATERIALS (STEEL SHEETS, AQUA BARRIERS, RIP RAP AND GEOTEXTILE LINER, ETC.). EARTHEN COFFERDAMS ARE NOT PERMISSIBLE.
12.

ALL ANCHOR BOLTS, NUTS, WASHERS, ETC. SHALL BE GALVANIZED STEEL UNLESS OTHERWISE NOTED AND SHALL BE IN ACCORDANCE WITH REQUIREMENTS OF ASTM A-153.

TOTAL BILL OF MATERIALS

ITEM	UNIT	TOTAL
Concrete Removal	Cu. Yd.	2.4
Structure Excavation	Cu. Yd.	2,722.1
Concrete Structures	Cu. Yd.	0.4
Concrete Structures (Retaining Wall)	Cu. Yd.	123.6
Form Liner Textured Surface	Sq. Ft.	628.3
Protective Coat	Sq. Yd.	398.7
Stud Shear Connectors	Each	284
Reinforcement Bars, Epoxy Coated	Pound	18,060
Furnishing Soldier Piles (HP Section)	Foot	520
Drilling and Setting Soldier Piles (In Soil)	Cu. Ft.	607.3
Drilling and Setting Soldier Piles (In Rock)	Cu. Ft.	785.4
Untreated Timber Lagging	Sq. Ft.	1,962.8
Geocomposite Wall Drain	Sq. Yd.	273.7
Pipe Underdrains For Structures 4"	Foot	362
Railing Type A	Foot	23.5
Railing Type C	Foot	335.5
Rock Excavation for Structures	Cu. Yd.	7.5
Rubbed Finish	Sq. Ft.	2,704.7
Steel Handrail	Foot	282.6

LIST OF ABBREVIATIONS AND SYMBOLS

⊕	CENTERLINE
∅	DIAMETER
±	APPROXIMATELY
©	CONSTRUCTION JOINT
PROP.	PROPOSED
E.F.	EACH FACE
TYP.	TYPICAL
STA.	STATION
OFF.	OFFSET
ELEV.	ELEVATION
CONST.	CONSTRUCTION
JT.	JOINT
CTS.	CENTERS
CL.	CLEAR COVER
MIN.	MINIMUM
FT.	FEET
LT.	LEFT
RT.	RIGHT
CLSM	CONTROLLED LOW STRENGTH MATERIAL
F/G	FINISHED GRADE
FTG.	FOOTING
F.F.	FRONT FACE
B.F.	BACK FACE
UNO	UNLESS NOTED OTHERWISE

MODEL: Default
FILE NAME: N:\2024\241108\Drawings\MainStructures\CADD_Sheets\01\241108-cast-General Notes.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann

PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED - _____
DRAWN - _____
CHECKED - _____
DATE - _____

- _____
- _____
- _____
- _____

- _____
- _____
- _____
- _____

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

SCALE:

SHEET

S2

OF

S17

SHEETS

STA.

TO STA.

GENERAL NOTES

COUNTY


TOTAL
SHEETS

SHEET
NO.

KANE

63

21



PLAN
(Showing removal of existing north and west wall)

LEGEND




Concrete Removal




Proposed Concrete

Notes:

Concrete removal shall be according to Article 501.05 of the IDOT Standard Specification for Road and Bridge Construction.
Existing reinforcement bars extending into the removal area shall be cut 2" below the proposed finished grade of path. Reinforcement to remain shall be blast cleaned to gray metal and straightened.
See sheet S3A for Bill of Materials.



SECTION A-A
(Showing removal)



SECTION A-A
(Showing concrete replacement)

* See grading plan for additional grading information.

** Cut and bend to fit.

MODEL: Sheet-S3
FILE NAME: N:\2024\241108\Drawings\Main\Structures\CADD_Sheets\241108-sh-1-Removal & Replacement.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -			
DRAWN -			
CHECKED -			
DATE -			

BATAVIA


**PEACE BRIDGE
BIKE RAMP**

ILLINOIS

STRUCTURAL REMOVAL AND REPLACEMENT

SCALE: SHEET S3 OF S17 SHEETS STA. TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	22



PLAN
(Showing partial removal of existing wall)


BILL OF MATERIAL

Bar	No.	Size	Length	Shape
h10(E)	2	#4	17'-10"	—
h11(E)	2	#4	9'-5"	—
Reinforcement Bars, Epoxy Coated			Lbs.	40
Concrete Removal			Cu. Yd.	2.4
Concrete Structures			Cu. Yd.	0.4

LEGEND




Concrete Removal




Proposed Concrete


Notes:
Concrete removal shall be according to Article 501.05 of the IDOT Standard Specification for Road and Bridge Construction.
Existing reinforcement bars extending into the removal area shall be cut 2" below the proposed top of concrete. Reinforcement to remain shall be blast cleaned to gray metal and straightened.



SECTION C-C
(Showing concrete replacement)



SECTION B-B
(Showing removal)



SECTION B-B
(Showing concrete replacement)

MODEL: SheetS3A
FILE NAME: N:\2024\241108\Drawings\Main\Structures\CADD_Sheets\DT241108-sh-Removal & Replacement-2.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

BATAVIA


PEACE BRIDGE
BIKE RAMP

ILLINOIS


STRUCTURAL REMOVAL AND REPLACEMENT II

SCALE: SHEET S3A OF S17 SHEETS STA. TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	23



Notes:
 See sheet 5 for reinforcement detail at railing posts.
 See sheet 8 for reinforcement detail at lighting fixtures.
 See sheet S14 for typical soldier pile wall section.
 See sheet 17 for railing post spacing.



MODEL: Sheet-S4
 FILE NAME: N:\2024\241108\Drawings\Main\Structures\CADD_Sheets\DT241108-s4-South Wall.dgn



V3 Companies
 7325 Janes Avenue
 Woodridge, IL 60517
 630.724.9200 phone
 630.724.9202 fax
 www.v3co.com

USER NAME = mfortmann
 PLOT SCALE =
 PLOT DATE = 4/25/2025

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

-
 -
 -
 -

-
 -
 -
 -

BATAVIA


**PEACE BRIDGE
 BIKE RAMP**

ILLINOIS

SOUTH WALL PLAN AND ELEVATION

SCALE: SHEET S4 OF S17 SHEETS STA. TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	24



ELEVATION
(Showing reinforcement)


* Cut to fit

MINIMUM BAR LAP
#4 Bar = 1'-8"
#5 Bar = 2'-1"

SUPERSTRUCTURE
BILL OF MATERIAL

Bar	No.	Size	Length	Shape
a(E)	16	#5	1'-6"	—
d(E)	28	#4	2'-2"	□
h(E)	20	#5	43'-1"	—
h1(E)	24	#5	26'-2"	—
v(E)	48	#5	3'-4"	—
v1(E)	60	#5	7'-6"	—
v2(E)	60	#5	11'-4"	—
Reinforcement Bars, Epoxy Coated			Lbs.	2,960
Concrete Structures (Retaining Wall)			Cu. Yds.	20.3

Bars indicated thus 3 x 2-#5 etc. indicates
3 lines of bars with 2 lengths per line.



Notes:
See sheet 5 for reinforcement detail at railing posts.
See sheet 8 for reinforcement detail at lighting fixtures.
See sheet S14 for typical soldier pile wall section.
See sheet 17 for railing post spacing.

MODEL: SheetS5
FILE NAME: N:\2024\241108\Drawings\MainStructures\CADD_Sheets\DT241108-sf-South Wall.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

BATAVIA

**PEACE BRIDGE
BIKE RAMP**

ILLINOIS

SOUTH WALL REINFORCEMENT DETAIL

SCALE: SHEET S5 OF S17 SHEETS STA. TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	25


MODEL: SheetS6
FILE NAME: N:\2024\241108\Drawings\MainStructures\CADD_Sheets\01241108-eh-East End Wall.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com


USER NAME = mfortmann	DESIGNED -	-	-
	DRAWN -	-	-
PLOT SCALE =	CHECKED -	-	-
PLOT DATE = 4/25/2025	DATE -	-	-

PEACE BRIDGE BIKE RAMP		EAST END WALL PLAN AND ELEVATION		COUNTY	TOTAL SHEETS	SHEET NO.
ILLINOIS		SCALE:		KANE	63	26
		SHEET S6 OF S17 SHEETS		STA. TO STA.		




ELEVATION
(Looking West)

Notes:
See sheet S5 for reinforcement detail at railing posts.
See sheet S8 for reinforcement detail at light fixtures.
See sheet S14 for typical soldier pile wall section.
See sheet S17 for railing post spacing.




PLAN




CORNER DETAIL


(Showing corner between the East and South wall,
corner between East and North wall similar)



BAR c1(E)



BAR c(E)



ELEVATION
(Showing reinforcement)


* Cut to fit

BILL OF MATERIAL


Bar	No.	Size	Length	Shape
a(E)	4	#5	1'-6"	—
c(E)	25	#5	6'-2"	└
c(E)	25	#5	3'-0"	└
d(E)	10	#4	2'-2"	└
h2(E)	26	#5	26'-7"	—
v3(E)	56	#5	12'-0"	—
Reinforcement Bars, Epoxy Coated			Lbs.	1,680
Concrete Structures (Retaining Wall)			Cu. Yds.	12.0

MINIMUM BAR LAP

#5 bar = 2'-1"



Notes:
See sheet S5 for reinforcement detail at railing posts.
See sheet S8 for reinforcement detail at light fixtures.
See sheet S14 for typical soldier pile wall section.
See sheet S17 for railing post spacing.
See Drainage and Utility Plan sheet for additional storm sewer information.



MODEL: SheetS7
FILE NAME: N:\2024\241108\Drawings\Main\Structures\CADD_Sheets\01241108-sh-North Wall.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

BATAVIA

PEACE BRIDGE
BIKE RAMP


ILLINOIS

NORTH WALL PLAN AND ELEVATION I


SCALE:

SHEET S7 OF S17 SHEETS STA. TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	27




*Note:
Move reinforcement in concrete face
to clear opening for storm pipe.*




LIGHT FIXTURE DETAIL

Note:
Cut or move longitudinal and vertical reinforcement in concrete face to clear light fixture.



ELECTRICAL CONDUIT DETAIL

Notes:
See sheet S5 for reinforcement detail at railing posts.
See sheet S8 for reinforcement detail at light fixtures.
See sheet S14 for typical soldier pile wall section.
See sheet S17 for railing post spacing.
See Drainage and Utility Plan sheet for additional storm sewer information.
See civil plans for light fixture locations.



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = infortmann	DESIGNED - _____	- _____	- _____
	DRAWN - _____	- _____	- _____
PLOT SCALE =	CHECKED - _____	- _____	- _____
PLOT DATE = 4/25/2025	DATE - _____	- _____	- _____


BATAVIA

PEACE BRIDGE BIKE RAMP

ILLINOIS

SCALE:	SHEET S8 OF S17 SHEETS	STA.	TO STA.
--------	------------------------	------	---------


COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	28



ELEVATION
(Showing reinforcement)

MINIMUM BAR LAP
#5 bar = 2'-1"

* Cut to fit



ELEVATION
(Showing reinforcement)

SUPERSTRUCTURE
BILL OF MATERIAL

Bar	No.	Size	Length	Shape
a(E)	36	#5	1'-6"	—
d(E)	50	#4	2'-2"	□
h3(E)	84	#5	31'-4"	—
h4(E)	40	#5	32'-1"	—
h5(E)	8	#5	33'-9"	—
v2(E)	62	#5	11'-4"	—
v4(E)	124	#5	13'-5"	—
v5(E)	62	#5	12'-3"	—
v6(E)	62	#5	7'-4"	—
v7(E)	14	#5	2'-7"	—
Reinforcement Bars, Epoxy Coated			Lbs.	8,270
Concrete Structures (Retaining Wall)			Cu. Yds.	91.2

Bars indicated thus 1 x 2-#4 etc. indicates 1 line of bars with 2 lengths per line.

Notes:
See sheet S5 for reinforcement detail at railing posts.
See sheet S8 for reinforcement detail at light fixtures.
See sheet S14 for typical soldier pile wall section.
See sheet S17 for railing post spacing.

MODEL: SheetS9
FILE NAME: N:\2024\24110\Drawings\Main\Structures\CADD_Sheets\DT241108-sh-North_Wall.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -	—	-	—	-	—
DRAWN -	—	-	—	-	—
CHECKED -	—	-	—	-	—
DATE -	—	-	—	-	—

BATAVIA

PEACE BRIDGE
BIKE RAMP


ILLINOIS

NORTH WALL REINFORCEMENT DETAIL


SCALE: SHEET S9 OF S17 SHEETS STA. TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	29


MODEL: SheetS10
FILE NAME: N:\2024\241108\Drawings\Main\Structures\CADD_Sheets\01241108-4th West End Wall.dgn



ELEVATION
(Looking East)




BAR n1(E)



SECTION C-C


** Field drill and epoxy grout in place according to Section 584 of the Standard Specifications.



PLAN

BILL OF MATERIALS				
Bar d(E)	No.	Size	Length	Shape
	16	#4	2'-2"	⌐
h6(E)	10	#5	25'-0"	—
n1(E)	20	#5	5'-9"	⌐
t1(E)	40	#5	3'-8"	—
v8(E)	29	#5	4'-5"	—
w5(E)	8	#5	22'-7"	—
w6(E)	2	#5	9'-6"	—
Reinforcement Bars, Epoxy Coated			Lbs.	900
Concrete Structures (Retaining Wall)			Cu. Yd.	7.3
Rock Excavation for Structures			Cu. Yd.	1.4

Notes:
See sheet S5 for reinforcement detail at railing posts.
See sheet S8 for reinforcement detail at light fixtures.
See sheet S17 for railing post spacing.



SECTION B-B



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann	DESIGNED -	-	-
PLOT SCALE =	DRAWN -	-	-
PLOT DATE = 4/25/2025	CHECKED -	-	-
	DATE -	-	-

**PEACE BRIDGE
BIKE RAMP**



ILLINOIS

WEST END WALL PLAN AND ELEVATION

SCALE: SHEET S10 OF S17 SHEETS STA. TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	30

MODEL: SheetS11
FILE NAME: N:\2024\241108\Drawings\Main\Structures\CADD_Sheets\DT241108-41-Center Wall.dgn



Notes:
See sheet S5 for reinforcement detail at railing posts.
See sheet S16 for center wall details and bill of materials.
See sheet S17 for railing post spacing.



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

BATAVIA

**PEACE BRIDGE
BIKE RAMP**


ILLINOIS

CENTER WALL PLAN AND ELEVATION I

SCALE:


SHEET S11 OF S17 SHEETS STA. TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	31



ELEVATION
(Looking North)

Notes:
See sheet S5 for reinforcement detail at railing posts.
See Sheet S16 for center wall details and bill of materials.
See sheet S17 for railing post spacing.



PLAN

MIN. BAR LAPS
#4 Bars = 1'-8"
#5 Bars = 2'-1"

* Cut to fit

MODEL: SheetS12
FILE NAME: N:\2024\241108\Drawings\Main\Structures\CADD_Sheets\DT241108-sh-Center Wall.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS


CENTER WALL PLAN AND ELEVATION II

SCALE: SHEET S12 OF S17 SHEETS STA. TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	32

PILE LAYOUT

Pile	Station at Working Point	Top of Pile Elevation	Bottom of Wall Elevation	Section	Auger Diameter	Pile Tip Elevation	Pile Length
P-01	10+27.20	667.83	666.68	HP14X89	2'-6"	651.50	16.33'
P-02	10+36.20	667.98	666.25	HP14X89	2'-6"	651.50	16.48'
P-03	10+45.20	668.11	665.82	HP14X89	2'-6"	651.50	16.60'
P-04	10+54.20	668.40	665.38	HP14X89	2'-6"	651.50	16.90'
P-05	10+63.20	668.89	665.09	HP14X89	2'-6"	651.50	17.39'
P-06	10+72.20	669.38	664.69	HP14X89	2'-6"	651.50	17.88'
P-07	10+81.20	670.18	664.26	HP14X89	2'-6"	651.50	18.68'
P-08	10+90.20	671.10	663.83	HP14X89	2'-6"	651.50	19.60'
P-09	10+99.20	672.09	663.40	HP14X89	2'-6"	651.50	20.59'
P-10	11+08.20	673.06	663.54	HP14X89	2'-6"	651.50	21.56'
P-11	11+11.39	673.65	663.53	HP14X89	2'-6"	651.50	22.15'
P-12	11+18.56	673.90	663.42	HP14X89	2'-6"	651.50	22.40'
P-13	11+25.23	674.14	663.32	HP14X89	2'-6"	651.50	22.64'
P-14	11+32.41	674.21	663.28	HP14X89	2'-6"	651.50	22.71'
P-15	11+36.44	674.18	663.15	HP14X89	2'-6"	658.15	16.02
P-16	11+45.44	674.15	662.96	HP14X89	2'-6"	657.96	16.19
P-17	11+54.44	674.07	662.53	HP14X89	2'-6"	657.53	16.54
P-18	11+63.44	673.35	662.10	HP14X89	2'-6"	657.10	16.25
P-19	11+72.44	672.53	661.67	HP14X89	2'-6"	656.67	15.86
P-20	11+81.44	671.73	661.24	HP14X89	2'-6"	656.24	15.49
P-21	11+90.44	671.05	660.97	HP14X89	2'-6"	655.83	15.21
P-22	11+99.44	670.35	660.54	HP14X89	2'-6"	655.06	15.29
P-23	12+08.44	669.61	660.11	HP14X89	2'-6"	654.28	15.33
P-24	12+17.44	668.89	659.68	HP14X89	2'-6"	653.50	15.39
P-25	12+26.44	668.22	659.25	HP14X89	2'-6"	652.73	15.50
P-26	12+35.44	666.63	658.99	HP14X89	2'-6"	651.95	14.68
P-27	12+44.44	664.63	658.56	HP14X89	2'-6"	650.51	13.13
P-28	12+53.44	663.66	658.12	HP14X89	2'-6"	650.51	12.16
P-29	12+62.44	663.16	657.69	HP14X89	2'-6"	650.51	11.66
P-30	12+71.44	660.81	657.26	HP14X89	2'-6"	650.51	9.31
P-31	12+80.44	659.35	656.83	HP14X89	2'-6"	650.51	7.85
P-32	12+87.44	657.30	656.64	HP14X89	2'-6"	650.51	5.80



CROSS SECTION
Elevations vary and are shown
for Sta. 10+59.08 only

NOTES:

See pipe underdrain detail on sheet S14.

BILL OF MATERIAL


Item	Unit	Quantity
Steel Handrail	Foot	282.6

HANDRAIL DETAIL

(Handrail to be painted same color
& using same process as railing)

NOTES:

*Space reinforcement to miss anchor rods.
All railings, splices, anchor devices, and bent plates shall be painted using one coat of zinc rich primer and two coats of black acrylic enamel paint. The exact color shall be submitted to the Engineer for approval prior to painting any railing elements.
Handrail brackets shall be spaced no more than 10 feet on center.*



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann	DESIGNED - _____	- _____ <small>DATE: DAY - MONTH - YEAR</small>	- _____
	DRAWN - _____	- _____ <small>DATE: DAY - MONTH - YEAR</small>	- _____
PLOT SCALE =	CHECKED - _____	- _____ <small>DATE: DAY - MONTH - YEAR</small>	- _____
PLOT DATE = 4/25/2025	DATE _____	- _____ <small>DATE: DAY - MONTH - YEAR</small>	- _____

BATAVIA

PEACE BRIDGE
BIKE RAMP


ILLINOIS

SCALE:	SHEET S13 OF S17 SHEETS	STA.	TO STA.
--------	-------------------------	------	---------


CROSS SECTION

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	33


MODEL: SheetS14
FILE NAME: N:\2024\241108\Drawings\MainStructures\CADD_Sheets\DT241108-sh-Soldier Pile Details.dgn




TYPICAL SOLDIER PILE WALL CROSS SECTION




SHEAR STUD CONNECTION DETAIL (STUDS)
Note: Use a minimum of 4 studs per pile



EXPANSION JOINT



AT SOLDIER PILES




BETWEEN SOLDIER PILES


UNDERDRAIN DETAIL

**Included in the cost of Pipe Underdrain for Structure

Note:
Drain to daylight at river or tie into storm sewer.



SECTION B-B



CONSTRUCTION JOINT

GENERAL NOTES:

1. Structure Excavation is measured 2'-0" from the front face of wall to back of the soldier pile timber lagging
2. The Contractor is responsible for the design and performance of the lagging system. For Wood Lagging, using no less than 3" nominal rough-sawn thickness and timber with a minimum allowable bending stress of 1000 psi, until the correct facing is installed. The Contractor shall utilize Steel Lagging if Wood Lagging capacity is not sufficient especially where the pile spacings exceed 7'-6". The Contractor shall submit design calculations and details prepared by an Illinois Licensed Structural Engineer for approval by the Engineer.
3. The geocomposite wall drain shall be placed behind the lagging with the previous side toward the soil according to Section 591 of the Standard Specifications and shall be centered between the piles. The drain shall be installed in stages as the excavation proceeds downward making sure that drain splices as well as the top side edges are covered as required to protect the drain. Thickness shall not be greater than 1 1/2".
4. See Sheet S13 for Table of Soldier Pile Data.



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann	DESIGNED -	-	-
	DRAWN -	-	-
PLOT SCALE =	CHECKED -	-	-
PLOT DATE = 4/25/2025	DATE -	-	-

PEACE BRIDGE
BIKE RAMP


BATAVIA

ILLINOIS

SOLDIER PILE WALL DETAILS I


SCALE:	SHEET S14 OF S17 SHEETS	STA.	TO STA.
--------	-------------------------	------	---------

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	34




STEEL PILE TABLE


Designation	Depth d	Flange width bf	Web and Flange thickness t	Encasement diameter A
HP 14x89	13 7/8"	14 3/4"	5/8"	30"



ELEVATION




ISOMETRIC VIEW



DETAIL "B"


WELDED COMMERCIAL SPLICE




ISOMETRIC VIEW

WELDED COMMERCIAL SPLICE ALTERNATE

- * Interrupt welds 1/4" from end of web and/or each flange.
- ** Remove portions of backup plates that extend outside the flanges.
- *** Weld size per pile shoe manufacturer (5/16" min.).




ELEVATION




SECTION A-A

INDIVIDUAL PILE
CONCRETE ENCASEMENT
(when specified)




ELEVATION



END VIEW

Designation	F	Ft	Fw	W	Wt	Ww
HP 14x89	12 1/2"	3/4"	1 1/16"	7 3/4"	5/8"	1/2"



DETAIL D

WELDED PLATE FIELD SPLICE

Note:
The steel H-piles shall be according to
AASHTO M270 Grade 50.

MODEL: Sheets15
FILE NAME: N:\2024\241108\Drawings\Main\Structures\CADD_Sheets\241108-41-Solder_Pile_Details.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

BATAVIA


PEACE BRIDGE
BIKE RAMP

ILLINOIS

SOLDIER PILE WALL DETAILS II



SCALE: SHEET S15 OF S17 SHEETS STA. TO STA.

COUNTY TOTAL SHEETS SHEET NO.
KANE 63 35





MINIMUM BAR LAP

#4 BAR = 1'-8"
#5 BAR = 2'-1"



CONSTRUCTION JOINT DETAIL



PIPE UNDERDRAIN DETAIL

*Included in the cost of Pipe Underdrain for Structure


Note:
Drain to daylight at river or tie into storm sewer.

RETAINING WALL BILL OF MATERIALS

Bar	No.	Size	Length	Shape
d(E)	24	#4	2'-2"	□
h7(E)	20	#5	20'-7"	—
h8(E)	16	#5	26'-1"	—
h9(E)	12	#5	29'-7"	—
n(E)	73	#5	4'-7"	└
t(E)	196	#5	4'-2"	—
v(E)	14	#5	3'-4"	—
v6(E)	50	#5	7'-4"	—
v9(E)	42	#5	9'-7"	—
v10(E)	42	#5	5'-3"	—
w(E)	20	#5	21'-7"	—
w1(E)	10	#5	25'-0"	—
w2(E)	10	#5	6'-7"	—
w3(E)	15	#5	4'-1"	└
w4(E)	15	#5	7'-10"	└
Reinforcement Bars, Epoxy Coated			Lbs.	4,210
Concrete Structures (Retaining Wall)			Cu. Yds.	22.8
Rock Excavation for Structures			Cu. Yd.	6.1


Notes:
The spread footing shall be embedded a minimum of 6 inches into solid bedrock. If bedrock is not encountered within the first 4 feet below grade then the bottom of spread footing shall be placed at a minimum of 4 feet below grade.






Notes:
 The Contractor shall design, detail, furnish and install railings on top of the new switchback walls. The new railings shall match the existing railing as shown in the elevations and sections provided. Place reinforcement bars to miss anchor rod locations. The post base plate shall be fastened to the top of walls snug tight and given an additional 1/8" turn. All HSS tubing used for the Handrail shall be CVN tested according to Article 1006.34(b) of the Standard Specifications. All railings, posts, splices, anchor devices, and bent plates shall be painted using one coat of zinc rich primer and two coats of black acrylic enamel paint. The exact color shall be submitted to the Engineer for approval prior to painting any railing elements. Railings to match existing railings A and C from Batavia Park District Enhancement Project (Job No. C91-576-93) plans dated February 3, 1998.


RAILING PLAN



RAILING A SECTION




RAILING A ELEVATION



RAILING C SECTION

RAILING C ELEVATION



BASE PLATE

BILL OF MATERIAL

Item	Unit	Quantity
Railing Type A	Foot	23.5
Railing Type C	Foot	335.5

3/4" Ø Holes in Base Plate for drilling and setting 5/8" Ø anchor rods according to Article 509.06 of Standard Specifications. Embedment shall be according to the Manufacturer's Specifications. (4 galvanized bolts per plate, painted.)

MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CA00_Signs\241108-shs-01.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

PEACE BRIDGE
BIKE RAMP

ILLINOIS

SCALE: 1"=10'

PAVEMENT MARKING & SIGNAGE PLAN

SHEET 1 OF 1 SHEETS

STA. 10+00.00

TO STA. 13+38.00

COUNTY


TOTAL
SHEETS

SHEET
NO.

KANE

63

39



CIRCUIT DESIGNATION IDENTIFICATION

LIGHTING CIRCUIT DESIGNATION
POLE NO. ON GIVEN CIRCUIT

X-X
STA XXX+XX.XX; XX.XX' O/S

LEGEND

- EXISTING ELECTRICAL CONDUIT
- PROPOSED ELECTRICAL CONDUIT AND CABLE
(SEE CONDUIT AND CABLE LEGEND)
- PROPOSED 24" X 24" COMPOSITE CONCRETE
HANDHOLE
- PROPOSED WALL LUMINAIRE
(SEE FIXTURE SCHEDULE)

NOTE:

1. INTERCEPT EXISTING CONDUIT IN HANDHOLE.
CONNECT PROPOSED FEEDERS FOR RAMP LIGHTING
TO EXISTING FEEDERS. MAINTAIN CONNECTION TO
EXISTING DECORATIVE LIGHT.
2. ROUTE CONDUIT UNDER PROPOSED PCC FROM
PROPOSED HANDHOLE TO EDGE OF WALL. SEE WALL
LUMINAIRE MOUNTING AND CONDUIT ROUTING DETAIL.

CONDUIT AND CABLE LEGEND

- 2-1C NO. 10, 1/C NO. 10 GROUND, (XLP-TYPE USE),
1" DIA. RIGID GALVANIZED STEEL CONDUIT

LOAD TABLE

CIRCUIT	AMPS	WATTS
A	0.87	104
TOTAL	0.87	104

LOAD TABULATION IS BASED ON THE FOLLOWING

8W HSL 13 STEP LIGHT SERIES LUMINAIRE: 0.067A AT 120V

LIGHTING FIXTURE SCHEDULE

SYMBOL	DESCRIPTION	QUANTITY	LLF	COLOR	MOUNTING	CONFIG.	CATALOG NO. & NOTES
SL-1	HYDREL, HSL STEP LIGHT 13, 9" NOMINAL LENGTH 8W, 120V, TYPE IV DISTRIBUTION	13	0.90	3000K	*3'-6" MOUNTING HEIGHT	1 FIXTURE	HSL13-9INCH-LED-30K-MVOLT-L-MIN5-BRB

*EXCEPT FOR LIGHTS 1 AND 2 SINCE WALL HEIGHT IS LESS
THAN 3'-6". MOUNT THESE LIGHTS 3" FROM TOP OF WALL.



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED - AM
DRAWN - AM
CHECKED - MGS
DATE

-
-
-
-

-
-
-
-

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

PEDESTRIAN RAMP LIGHTING PLAN

SCALE: 1"=10'


SHEET 1 OF 1 SHEETS

STA. 10+00.00 TO STA. 13+43.82

COUNTY TOTAL SHEETS SHEET NO.
KANE 63 40

1. THE LIGHT POLE LOCATIONS ON THIS PLAN SHOW THE RECOMMENDED PLACEMENT. ADJUSTMENTS TO THESE LOCATION MAY BE REQUIRED TO ACCOMMODATE SITE CONDITIONS AND SHALL BE APPROVED BY THE CITY AND ENGINEER.
2. LOCATION OF LIGHTING CABLE SHOWN ON THE PLAN IS DIAGRAMMATIC ONLY.
3. ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR FURNISHING ALL NECESSARY MATERIALS AND MAKING ALL FINAL CONNECTIONS OF THE LIGHTING SYSTEM FOR A COMPLETE INSTALLATION TO THE PROPOSED JUNCTION BOX.
4. ALL LIGHTING WORK SHALL CONFORM TO THE CITY OF BATAVIA STANDARDS AND SPECIFICATIONS, THE LATEST EDITION OF IDOT STANDARD SPECIFICATIONS BOOK, AND THE LATEST EDITION OF THE STANDARD SPECIFICATIONS FOR STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINAIRES AND TRAFFIC SIGNALS.
5. PRIOR TO ANY EQUIPMENT ORDER, THE CONTRACTOR SHALL SUBMIT EQUIPMENT SPECIFICATIONS, CATALOG CUT SHEETS, AND DESIGN DATA FOR ALL MATERIAL PROPOSED FOR THE PROJECT TO THE ENGINEER AND OWNER FOR REVIEW & APPROVAL.
6. ALL ELECTRICAL WORK SHALL CONFORM TO THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (N.E.C.) AND ANY APPLICABLE LOCAL CODES.
7. ALL EXCESS DIRT AND DEBRIS EXCAVATED FOR POLE FOUNDATIONS SHALL BE REMOVED BY THE CONTRACTOR.
8. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL EXISTING STREETS, DRIVEWAYS, SIDEWALKS, AND PARKING LOTS AT ALL TIMES TO THE EXTENT POSSIBLE DURING THE CONSTRUCTION OPERATION.
9. THE COST OF THE CABLE SHALL INCLUDE ELBOWS, SWEEPS, CONNECTING HARDWARE, MOUNTING HARDWARE, TRENCHING AND BACKFILL AS INDICATED IN THE PLANS. THE COST OF THE CONDUIT SHALL ALSO INCLUDE THE COST OF RESTORING CUT PAVEMENT, SIDEWALKS, SOD, ETC., TO ITS ORIGINAL CONDITION. SOD SHALL BE REPLACED IN LIKE KIND OF THE ADJACENT SURROUNDINGS.
10. THE CONDUCTOR SIZES SHOWN ON THE PLANS ARE BASED ON A 120/240 VOLT SINGLE-PHASE SERVICE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING SERVICE WITH THE CONSTRUCTION MANAGER. IF SERVICE IS DIFFERENT, THE CONTRACTOR SHALL PROVIDE ADEQUATE NUMBER AND SIZE CONDUCTORS AND CONDUITS.
11. THE CONTRACTOR SHALL PUSH OR DIRECTIONALLY BORE ALL CONDUIT UNDER EXISTING PAVEMENT.
12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE ESTABLISHMENT OF FINISHED GRADE.
13. THE LIGHTING SYSTEM WILL BE MAINTAINED BY CITY UPON FINAL ACCEPTANCE.

LIGHTING GENERAL NOTES



ELECTRICAL CABLES SPLICE DETAIL

HYDREL

MODEL: _____
NOTES: _____
FILE: _____

HSL13
Static White and Static Color
Step Light 13

HIGHLIGHTS

- Integral Driver
- Long throw distribution
- Standard 0-10V dimming option
- Die-cast housing with solid aluminum, brass, or stainless steel faceplate
- Wet location listed
- Back Box provided by Hydrel or by others
- Suitable for concrete pour if BB option is chosen or Steel City back box is used

5 YEAR WARRANTY

LED

BAA

SABA

DIMENSIONS

12INCH

15.00" 0.50" 2.125" face view

Exposed terminals for the luminaire only

Integral driver

LED module with concealed optics

Wet location listed

Steel City HBCD or equivalent (See Notes)

CROSS SECTION

6INCH

11.00" 0.50" 2.125" face view

Exposed terminals for the luminaire only

Integral driver

LED module with concealed optics

Wet location listed

Steel City HBCD or equivalent (See Notes)

CROSS SECTION

3INCH

8.87" 0.50" 2.125" face view

Exposed terminals for the luminaire only

Integral driver

LED module with concealed optics

Wet location listed

Steel City HBCD or equivalent (See Notes)

CROSS SECTION

LUMEN PACKAGES

Distribution	Output Lumens	Input Watts	Lumens/Watt
3K/30	47	3	29
6K/30	79	5	36
9K/30	299	8	37
12K/30	366	11	37

Performance data based upon 30K LED HBCB

HYDREL

HSL13 STEP LIGHT | 2

ORDERING INFORMATION

EXAMPLE: HSL13 3INCH LED 27K MVOLT L MINS BRB

Series*	Length*	Source*	Color Temperature*	Voltage*	Distribution*
HSL13 Step Light 13	3INCH 3" Nominal Length 4INCH 4" Nominal Length 6INCH 6" Nominal Length 9INCH 9" Nominal Length 12INCH 12" Nominal Length	LED	27K 2700K 30K 3000K 35K 3500K 40K 4000K 50K 5000K	AMBLW Amber Limited Wavelength 590nm BLU Blue GRN Green RED Red CYN Cyan RDO Red Orange	MVOLT Multivolt 120V thru 277V L Long Throw

Dimming Options

OPTION	REMARK
BB Back Box	Back Box
BRB Brushed Brass	Brushed Brass
BRP Brushed Brass Paint	Brushed Brass Paint
BRSS Brushed Stainless Steel	Brushed Stainless Steel
LRPS Light Bronze Paint (see note)	Light Bronze Paint (see note)
PSR Polished Brass	Polished Brass
PSS Polished Stainless Steel	Polished Stainless Steel
SGS Same Glass Black	Same Glass Black
SGW Same Glass White	Same Glass White
CF Custom Finish	Custom Finish
RALTR RALTR Finish	RALTR Finish

Note: * is a required field

PERFORMANCE DATA

Expected Life: Static White LED: L70 @ 60,000 hours
Static Color LED: L70 @ 60,000 hours

Lumen Multiplier Table for CCT

CCT	Multiplier
27K	0.963
30K	1.000
35K	1.078
40K	1.163
50K	1.333
AMBLW	0.338
RDO	0.407
GREEN	0.902
BLUE	0.364

HYDREL

HSL13 STEP LIGHT | 3

WIRING

Read all instructions before installation. Do not make live connections!

NON-DIMMING INSTALLATIONS (For non-dimming, cap off the grey and purple wires separately)

Connect STEP WHITE wire to power NEUTRAL.
Connect STEP BLACK wire to power HOT.
Connect STEP GREEN wire to power GROUND.

DIMMING INSTALLATIONS

The integral dimming driver is designed to the 0-10V/EC dimming specification 60929 and is compatible with common 0-10V dimmers and dimming systems. Do NOT connect line voltage to dimming input wires.
Connect STEP WHITE wire to power NEUTRAL.
Connect STEP BLACK wire to power HOT.
Connect STEP VIOLET wire to POSITIVE INPUT of Dimming Control.
Connect STEP GREY or PINK wire to NEGATIVE INPUT of Dimming Control.

LIGHTING SPECIFICATIONS SHEETS

PEACE BRIDGE
BIKE RAMP

ELECTRICAL DETAILS

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	41

ILLINOIS SCALE: NONE SHEET 1 OF 2 SHEETS STA. TO STA.

BATAVIA


MODEL: Default
FILE NAME: N:\2024\24108\Drawings\Mech\CA\DD_Specs\DD1241108-att\hsl13detail01.dgn

V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com


USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED - AM
DRAWN - AM
CHECKED - MGS
DATE -

-
-
-
-



WALL LUMINAIRE MOUNTING AND CONDUIT ROUTING DETAIL



LIGHTING CONDUIT TRENCH BACKFILL DETAIL

MODEL: Default
FILE NAME: N:\2024\24108\Drawings\Main\CA-6_Specs\DT24108-entg\detail01.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED - AM
DRAWN - AM
CHECKED - MGS
DATE -

-
-
-
-

-
-
-
-

BATAVIA


PEACE BRIDGE
BIKE RAMP

ILLINOIS

ELECTRICAL DETAILS

SCALE: NONE SHEET 2 OF 2 SHEETS STA. TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	42



MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CA00_Sheets\241108-sh1-detour01.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-

-

-

-

-

-

-

-

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

SCALE: 1"=50'

PEDESTRIAN DETOUR PLAN

SHEET 1 OF 1 SHEETS STA. TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	43

MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CA00_Sheets\241108-sh-MOT1.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9200 fax
www.v3co.com

USER NAME	= mfortmann
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED -	---	-	---	-	---
DRAWN -	---	-	---	-	---
CHECKED -	---	-	---	-	---
DATE -	---	-	---	-	---

BATAVIA

PEACE BRIDGE BIKE RAMP

ILLINOIS

SCALE: 1"=10'

SHEET 1

OF

1


SHEETS

STA. 10+00.00


TO STA. 13+38.00

STAGING PLAN

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	44



MODEL: P:\R\PeaceBridgeRamp - 10+30.00 (Sheet)
FILE NAME: N:\2024\100\Drawings\Main\Design\10+30+XS.dgn



(FACING EAST) **STA 10+30.00**



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

BATAVIA

**PEACE BRIDGE
BIKE RAMP**


ILLINOIS

CROSS SECTIONS

SCALE: SHEET 1 OF 8 SHEETS STA. 10+30.00 TO STA. 10+30.00

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	45
CONTRACT NO. xxxxxx		

MODEL: P:\RL\PeaceBridgeRamp - 10+50.00 (Sheet)
FILE NAME: N:\2024\24100\Drawings\Main\Design\241108-XS.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

BATAVIA

**PEACE BRIDGE
BIKE RAMP**


ILLINOIS

CROSS SECTIONS

SCALE: SHEET 2 OF 8 SHEETS STA. 10+50.00 TO STA. 10+50.00

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	46
CONTRACT NO. xxxxxx		

MODEL: P:\R\PeaceBridgeRamp - 11+00.00 (Sheet)
FILE NAME: N:\2024\1100\Drawings\Main\Design\11+00-AS.dgn



(FACING EAST) **STA 11+00.00**



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME	= mfortmann
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED -	_____	-	_____	-	_____
DRAWN -	_____	-	_____	-	_____
CHECKED -	_____	-	_____	-	_____
DATE -	_____	-	_____	-	_____

BATAVIA

**PEACE BRIDGE
BIKE RAMP**


ILLINOIS

CROSS SECTIONS

SCALE: SHEET 3 OF 8 SHEETS STA. 11+00.00 TO STA. 11+00.00

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	47
CONTRACT NO. xxxxxx		

Model: P:\PeaceBridgeRamp - 11-03-27 (Sheet)
FILENAME: N:\2024\1100\Drawings\Main\Design\11-03-27.dgn



(FACING EAST) **STA 11+03.87**



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME	= mfortmann
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED -	---	-	---	-	---
DRAWN -	---	-	---	-	---
CHECKED -	---	-	---	-	---
DATE -	---	-	---	-	---

BATAVIA

**PEACE BRIDGE
BIKE RAMP**

ILLINOIS

SCALE:

SHEET

4

OF

8


SHEETS

STA. 11+03.87

TO STA. 11+03.87

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	48
CONTRACT NO. xxxxxx		

MODEL: P:\RL\PeaceBridgeRamp - 11+50.00 (Sheet)
FILE NAME: N:\2024\1100\Drawings\Main\Design\11+50.XS.dgn



(FACING WEST) **STA 11+50.00**



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

BATAVIA

**PEACE BRIDGE
BIKE RAMP**


ILLINOIS

CROSS SECTIONS

SCALE: SHEET 5 OF 8 SHEETS STA. 11+50.00 TO STA. 11+50.00

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	49
CONTRACT NO. xxxxxx		

MODEL: P:\R\PeaceBridgeRamp - 12+00.00 (Sheet)
FILE NAME: N:\2024\24100\Drawings\Main\Design\241108-XS.dgn



(FACING WEST) **STA 12+00.00**



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME	= mfortmann
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED -	_____	-	_____	-	_____
DRAWN -	_____	-	_____	-	_____
CHECKED -	_____	-	_____	-	_____
DATE -	_____	-	_____	-	_____

BATAVIA

**PEACE BRIDGE
BIKE RAMP**


ILLINOIS

CROSS SECTIONS

SCALE: SHEET 6 OF 8 SHEETS STA. 12+00.00 TO STA. 12+00.00

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	50
CONTRACT NO. xxxxxx		

MODEL: P:\RL\PeaceBridgeRamp - 12+50.00 (Sheet)
FILE NAME: N:\2024\10\Drawings\Main\Design\12+50.XS.dgn



(FACING WEST) **STA 12+50.00**



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME	= mfortmann
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED -	_____	-	_____	-	_____
DRAWN -	_____	-	_____	-	_____
CHECKED -	_____	-	_____	-	_____
DATE -	_____	-	_____	-	_____

BATAVIA

**PEACE BRIDGE
BIKE RAMP**


ILLINOIS

CROSS SECTIONS

SCALE: SHEET 7 OF 8 SHEETS STA. 12+50.00 TO STA. 12+50.00

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	51
CONTRACT NO. xxxxxx		

MODEL: P:\RL\PeaceBridgeRamp - 12+80.00 (Sheet)
FILE NAME: N:\2024\24100\Drawings\Main\Design\241108-XS.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME	= mfortmann
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED -	_____	-	_____	-	_____
DRAWN -	_____	-	_____	-	_____
CHECKED -	_____	-	_____	-	_____
DATE -	_____	-	_____	-	_____

BATAVIA


**PEACE BRIDGE
BIKE RAMP**

ILLINOIS

CROSS SECTIONS

SCALE:	SHEET 8 OF 8 SHEETS	STA. 12+80.00	TO STA. 12+80.00
--------	---------------------	---------------	------------------



COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	52
CONTRACT NO. xxxxxx		




FLEXSTORM Inlet Filter Specifications		
WOVEN Geotextile Sediment Bag Specs (2 ft ³ vol)		
Material Property	Test Method	Value (ave)
Grab Tensile	ASTMD 4632	255 x 275
Puncture Strength	ASTMD 4833	135 lbs
Trapezoidal Tear	ASTMD 4533	75 lbs
UV Resistance	ASTMD 4355	90%
App Open Size (AOS)	ASTMD 4751	20 sieve
Permittivity	ASTMD 4491	1.5 / sec
Water Flow Rate	ASTMD 4491	200 gpm/sqft
Sediment Removal Efficiency (8% mix)	ASTMD 7351	82%

INSTALLATION:

1. REMOVE GRATE
2. DROP FLEXSTORM INLET FILTER ONTO LOAD BEARING LIP OF CASTING OR CONCRETE STRUCTURE
3. REPLACE GRATE



WORK APP	ALL PRODUCTS MANUFACTURED BY INLET & SIPE PROTECTION, INC DISTRIBUTED BY ADS WWW.INLETFILTERS.COM (866) 287-8655 PH (630) 355-3477 FX INFO@INLETFILTERS.COM
CHECKED	
QA	
ENG	
APPROVED	
DATE	DATE MD
C	FLEXSTORM SPECS
SCALE	SHEET 1 OF 1



SHEET: 1 OF 1
DATE: 1/1/16

INLET FILTER

STANDARD NO. 4.13



SHEET: 1 OF 1
DATE: 1/1/16

INLET FILTER MAINTENANCE

STANDARD NO. 4.14

1. IDENTIFY YOUR FRAME STYLE, SIZE, AND MATERIAL			
STYLE		FRAME STYLE AND SIZE	Frame P/N
ROUND		Small Round / Up to 20.0" dia grates (4" dim)	62SRD
		Medium Round (20.3" - 26.0" dia grates (4" up to 25" dia openings) (B))	62MRD
		Large Round (26.3" - 32.0" dia grates (4" up to 30" dia openings) (B))	62LRD
RECT. / SQUARE		XL Round (32" dia - 36" dia grates (4" up to 37" dia openings) (B))	62XLRD
		Small Rect / Square (up to 16" (B) x 16" (D) openings or 96" perimeter)	62SRSQ
		Med Rect / Square (up to 24" (B) x 24" (D) openings or 96" perimeter)	62MSRSQ
SQUARE INLETS		Large Rect / Square (up to 36" (B) x 24" (D) openings or 120" perimeter)	62LRSQ
		XL Rect / Square (side by side 2 set to fit up to 48" (B) x 36" (D) openings)	62XLRSQ
		Small Rect / Square (ref rect sizing; shipped with Magnetic Curb Flaps)	62SRSQC
W/LOPEAST		Med Rect / Square (ref rect sizing; shipped with Magnetic Curb Flaps)	62MSRSQC
		Large Rect / Square (ref rect sizing; shipped with Magnetic Curb Flaps)	62LRSQC
		XL Rect / Square (ref rect sizing; shipped with Magnetic Curb Flaps)	62XLRSQC
WALLMOUNT		12" diameter Nyloplast castings (Stainless Steel Framing standard)	6212NV
		15" diameter Nyloplast castings (Stainless Steel Framing standard)	6215NV
		18" diameter Nyloplast castings (Stainless Steel Framing standard)	6218NV
		24" diameter Nyloplast castings (Stainless Steel Framing standard)	6224NV
		30" diameter Nyloplast castings (Stainless Steel Framing standard)	6230NV
Open Throat Gutters - Curb Opening Size			
	Up to 4" (2 Filters and Mounting Hardware)		62NMW1
	Between 4" and 8" (2 Filters and Mounting Hardware)		62NMW2
	Between 8" and 12" (3 Filters and Mounting Hardware)		62NMW3
	Between 12" and 16" (4 Filters and Mounting Hardware)		62NMW4
UPGRADED FRAMING MATERIAL OPTIONS (STANDARD IS ZINC PLATED)			SUFFIX
CHROME PLATED FRAMING FOR HIGH SALT EXPOSURE			-CH
STAINLESS STEEL FRAMING FOR HIGH SALT AND/OR CHEMICAL EXPOSURE			-SS



STRUCTURE ID#/LOCATION:

[illegible]

2. SELECT YOUR FILTER BAG PART NUMBER				
FLEXFORM FILTER BAGS	(22" depth) STD Bag P/N	(13" depth) Short Bag P/N	Clean Water flow Rate (GPM/Sq Ft)	Mn A.O.S. (US LBS)
FX: Standard Woven Bag	FXD	FX-S	200	40
FXC: Woven w/ MyCelx	FXP	FXP-S	200	40
FXD: Woven w/ Oil Boom	FXD	FXD-S	200	40
PC: Post Construction Bag	PC	PC-S	137	140
PC+: PC Bag w/ MyCelx	PCP	PCP-S	137	140
LL: Litter and Leaf Bag	LL	LL-S	High	3.5
IL: IDOT Non-Woven Bag	IL	IL-S	145	70

3. CREATE YOUR FLEXSTORM INLET FILTER PART NUMBER

		-	
Frame P/N from Step 1.	Filter Bag P/N from Step 2.		Framing Material

Nominal Bag Size	Solids Storage (Cu Ft)	Filtered Flow Rate at 50% Max			% PC Oil Retent	
		RT (Woven)	PC (Post Cast)	IM (Non Woven)	Retent (Oz)	Retent (Oz)
Small	1.6	1.2	0.8	0.9	66	155
Medium	2.1	1.8	1.2	1.3	96	185
Large	3.8	2.2	1.5	1.6	120	209
XL	4.2	3.6	2.4	2.6	192	330

* PC filter bag at 50% max adsorption capacity



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann	DESIGNED - _____	- _____	- _____
	DRAWN - _____	- _____	- _____
PLOT SCALE =	CHECKED - _____	- _____	- _____
PLOT DATE = 4/25/2025	DATE - _____	- _____	- _____

BATAVIA

PEACE BRIDGE BIKE RAMP

ILLINOIS


SCALE: NONE

SHEET	1	OF	11	SHEETS	STA.
-------	---	----	----	--------	------

CONSTRUCTION DETAILS

TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	53



NOTE:

1. MINIMUM STORM STRUCTURE DIAMETER IS 48". THE INSIDE DIAMETER SHALL BE DETERMINED BASED ON THE SIZE AND ORIENTATION OF THE STORM SEWERS ENTERING THE MANHOLE. REFER TO THE APPROVED PLANS FOR THE REQUIRED STORM MANHOLE DIAMETERS. TYPICALLY, A 4' DIA. MANHOLE IS REQUIRED FOR STORM SEWER SIZES 8" THRU 18", 5' DIA. MANHOLE FOR 21" THRU 42", AND 6 DIA. MANHOLE FOR 48" AND ABOVE.





CITY OF BATAVIA
PUBLIC WORKS DEPARTMENT
SHEET: 1 OF 1
DATE: 1/1/16

STORM SEWER MANHOLE - TYPE "A" OR TYPE "B"

STANDARD NO. 4.02

EAST JORDAN #1020 (OR APPROVED EQUAL) FRAME AND LID WITH CONCEALED PICKHOLES. LID SHALL HAVE THE WORDS "CITY OF BATAVIA", "STORM". CASTINGS FOR CURB INLETS AND CATCH BASINS IN THE CURB LINE SHALL BE E.J. #7221 (OR APPROVED EQUAL)



1-1/2 LETTERS
(RECESSED FLUSH)
HEAVY DUTY
MATERIAL ASTM A48 CL 35
COVER WT 125 LBS



CITY OF BATAVIA
PUBLIC WORKS DEPARTMENT
SHEET: 1 OF 1
DATE: 1/1/16

STORM MANHOLE LID DETAIL

STANDARD NO. 4.05

MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CAD_Sheets\241108-shh-4-01.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann	DESIGNED -	-	-
	DRAWN -	-	-
PLOT SCALE =	CHECKED -	-	-
PLOT DATE = 4/25/2025	DATE -	-	-

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

SCALE: NONE


SHEET 2 OF 11 SHEETS STA. TO STA.

CONSTRUCTION DETAILS

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	54

PIPE DIA.	APPROX. WT. (lbs)	WALL	A	B	C	D	E	G	R	SLOPE
12"	530	2"	4"	2'-0"	4'-0 ⁷ / ₈ "	6'-0 ⁷ / ₈ "	2'-0"	2"	9"	3:1
15"	740	2 ¹ / ₄ "	6"	2'-3"	3'-10"	6'-1"	2'-6"	2 ¹ / ₄ "	11"	3:1
18"	990	2 ¹ / ₂ "	9"	2'-3"	3'-10"	6'-1"	3'-0"	2 ¹ / ₂ "	12"	3:1
21"	1280	2 ³ / ₄ "	9"	2'-11"	3'-2"	6'-1"	3'-6"	2 ³ / ₄ "	13"	3:1
24"	1520	3"	9 ¹ / ₂ "	3'-7 ¹ / ₂ "	2'-6"	6'-1 ¹ / ₂ "	4'-0"	3"	14"	3:1
27"	1930	3 ¹ / ₄ "	10 ¹ / ₂ "	4'-0"	2'-1 ¹ / ₂ "	6'-1 ¹ / ₂ "	4'-6"	3 ¹ / ₄ "	14 ¹ / ₂ "	3:1
30"	2190	3 ¹ / ₂ "	12"	4'-6"	1'-7 ³ / ₄ "	6'-1 ³ / ₄ "	5'-0"	3 ¹ / ₂ "	15"	3:1
33"	3200	3 ³ / ₄ "	13 ¹ / ₂ "	4'-10 ¹ / ₂ "	3'-3 ¹ / ₄ "	8'-1 ³ / ₄ "	5'-6"	3 ³ / ₄ "	17 ¹ / ₂ "	3:1
36"	4100	4"	15"	5'-3"	2'-10 ³ / ₄ "	8'-1 ³ / ₄ "	6'-0"	4"	20"	3:1
42"	5380	4 ¹ / ₂ "	1'-9"	5'-3"	2'-11"	8'-2"	6'-6"	4 ¹ / ₂ "	22"	3:1
48"	6550	5"	2'-0"	6'-0"	2'-2"	8'-2"	7'-0"	5"	22"	3:1
54"	8240	5 ¹ / ₂ "	2'-3"	5'-5"	2'-11"	8'-4"	7'-6"	5 ¹ / ₂ "	24"	2.4:1
60"	8730	6"	2'-11"	5'-0"	3'-3"	8'-3"	8'-0"	5"	*	2:1
66"	10710	6 ¹ / ₂ "	2'-6"	6'-0"	2'-3"	8'-3"	8'-6"	5 ¹ / ₂ "	*	2:1
72"	12520	7"	3'-0"	6'-6"	1'-9"	8'-3"	9'-0"	6"	*	1.86:1
78"	14770	7 ¹ / ₂ "	3'-0"	7'-6"	1'-9"	9'-3"	9'-6"	6 ¹ / ₂ "	*	1.82:1
84"	18160	8"	3'-0"	7'-6 ¹ / ₂ "	1'-9"	9'-3 ¹ / ₂ "	10'-0"	6 ¹ / ₂ "	*	1.5:1

* RADIUS AS FURNISHED BY MANUFACTURER



NOTES:

- TRASH GRATES REQUIRED ON ALL FLARED END SECTIONS.
- PRECAST CONCRETE FLARED END SECTIONS SHALL CONFORM TO APPLICABLE REQUIREMENTS OF AASHTO M-170 CLASS III, WALL B REINFORCED CONCRETE PIPE.
- PRECAST CONCRETE FLARED END SECTION FOR PIPE DIAMETER REQUIRED SHALL BE AS INDICATED ON DETAIL PLAN FOR EACH INDIVIDUAL INSTALLATION.
- THE END BLOCK SHALL BE PLACED PRIOR TO THE INSTALLATION OF THE FLARED END SECTION. THE END BLOCK SHALL BE BACKFILLED IN ACCORDANCE WITH ARTICLE 502.10 OF THE IDOT STANDARD SPECIFICATIONS (LATEST EDITION), COST INCIDENTAL TO END SECTION.
- FLARED END SECTION SHALL BE AFFIXED TO THE FIRST PIPE SECTION USING 2" X 2" X 1/4" THK. GALVANIZED STRAPS FASTENED TO THE PIPE WITH GALV. ANCHORS AND 5/8" BOLTS.




CITY OF BATAVIA
PUBLIC WORKS DEPARTMENT

SHEET: 1 OF 1
DATE: 1/1/16

FLARED END SECTION A

STANDARD NO. 4.03



NOTES:

- TRENCH BACKFILL MATERIALS UNDER PAVED AREAS OR WITHIN THE ZONE OF INFLUENCE (3' FROM EDGE OF PAVEMENT) SHALL CONSIST OF THE FOLLOWING:
 - CA-6 PLACED IN 6" LAYERS COMPACTED TO 95% PROCTOR DENSITY (OR CONTROLLED LOW STRENGTH MATERIAL IDOT MIX 1 WITH PRIOR APPROVAL BY CITY ENGINEER);
 - MAXIMUM DEPTH FOR PAYMENT OF TRENCH BACKFILL MATERIAL SHALL BE FROM 12" ABOVE TOP OF PIPE TO TOP OF SUBGRADE;
 - MAXIMUM WIDTH FOR PAYMENT SHALL BE 18" PLUS PIPE O.D. (FOR TRENCHES <5') AND 36" PLUS PIPE O.D. (FOR TRENCHES >5').
- BACKFILL MATERIALS IN NON-PAVED AREAS OUTSIDE THE ZONE OF INFLUENCE (3' PAST EDGE OF PAVEMENT) SHALL CONSIST OF INORGANIC EXCAVATED MATERIALS COMPACTED PLACED IN 9" LIFTS COMPACTED TO 90% STANDARD PROCTOR DENSITY, A MINIMUM OF 6" OF TOPSOIL SHALL BE RESPREAD TO MATCH EXISTING GRADE.
- ALL MATERIALS SHALL BE PROPERLY COMPACTED PER SPECIFICATIONS (INUNDATION OR WATER JETTING ONLY ALLOWED WITH PRIOR APPROVAL OF THE CITY ENGINEER).
- ALL TRENCH EXCAVATIONS SHALL MEET OSHA REQUIREMENTS.
- BEDDING MATERIAL FOR PVC PIPE INSTALLATION SHALL COMPLY WITH ASTM D-2321.



CITY OF BATAVIA
PUBLIC WORKS DEPARTMENT

SHEET: 1 OF 1
DATE: 9/3/19

UTILITY TRENCH SECTION

STANDARD NO. 5.08



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

SCALE: NONE

SHEET 3

OF 11


SHEETS

CONSTRUCTION DETAILS


STA.

TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	55



SIDEWALK SECTION



SIDEWALK SECTION

NOTES:

1. CONCRETE SHALL BE IDOT CLASS SI.
2. MINIMUM SIDEWALK THICKNESS SHALL BE 5".
3. SIDEWALK THICKNESS ACROSS DRIVEWAYS SHALL BE AT A MINIMUM 6" FOR RESIDENTIAL DRIVEWAYS AND 8" FOR COMMERCIAL DRIVEWAYS.
4. MAXIMUM LONGITUDINAL SLOPE SHALL NOT EXCEED 5% (20:1). FOR ANY SLOPE IN EXCESS OF 5%, ALL REQUIREMENTS OF THE ILLINOIS ACCESSIBILITY CODE (LATEST EDITION) SHALL BE MET.
5. MINIMUM TRANSVERSE SLOPE SHALL BE 1.0% (1:100). MAXIMUM TRANSVERSE SLOPE SHALL BE 2.0% (1:50).
6. A MINIMUM 2" AGGREGATE SUBBASE (CA-6) SHALL BE PROVIDED. (4" THROUGH COMMERCIAL DRIVEWAYS).
7. AGGREGATE SUBBASE SHALL BE MECHANICALLY COMPACTED.
8. ALL SIDEWALKS SHALL BE PROMPTLY BACKFILLED AND PROTECTED FROM DAMAGE.
9. SIDEWALK CONSTRUCTION SHALL FOLLOW APPLICABLE IDOT STANDARDS.
10. SIDEWALKS SHALL FOLLOW CURRENT ADA GUIDELINES.





CITY OF BATAVIA
PUBLIC WORKS DEPARTMENT

SHEET: 1 OF 1
DATE: 1/1/16

SIDEWALK

STANDARD NO. 7.08



NOTES:

1. ALL AGGREGATE SUB-BASE SHALL BE MECHANICALLY COMPACTED.
2. SIDEWALK THICKNESS AT CURB RAMPS, THRU DRIVEWAYS, AND CARRIAGE WALKS SHALL BE A MINIMUM OF 6" PCC ON 2" AGGREGATE SUB BASE.
3. SIDEWALK CONSTRUCTION SHALL FOLLOW APPLICABLE IDOT STANDARDS.
4. SIDEWALKS SHALL FOLLOW CURRENT ADA GUIDELINES.
5. THE WIDTH OF PUBLIC SIDEWALKS FOR ALL TYPES OF ZONING SHALL NOT BE LESS THAN 5'.
6. MINIMUM SIDEWALK WIDTH IS 10 FEET WITH GRASS PARKWAY.
7. EXPANSION JOINTS SHALL BE PLACED AT THE END OF EACH POUR.



CITY OF BATAVIA
PUBLIC WORKS DEPARTMENT

SHEET: 1 OF 1
DATE: 1/1/16

SIDEWALK CONSTRUCTION

STANDARD NO. 7.09



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

SCALE: NONE

SHEET 4

OF

11


SHEETS

STA.

TO STA.

CONSTRUCTION DETAILS

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	56



NOTES:

- 3/4" PREFORMED BITUMINOUS EXPANSION JOINT WITH TWO (2) NUMBER 6 COATED SMOOTH DOWEL BARS (3/4" DIA. X 18") WITH GREASE CAPS SHALL BE PLACED EVERY 150', 5' EITHER SIDE OF DRAINAGE STRUCTURES, P.C.'S, RADIUS POINTS AND BACK OF CUL-DE-SACS. WHEN EXPANSION JOINTS ARE CONSTRUCTED ADJACENT TO EXISTING CURB & GUTTER THE EXISTING CURB SHALL BE DRILLED AND TWO (2) NUMBER 6 EPOXY COATED SMOOTH DOWEL BARS (3/4" X 18") GROUTED IN PLACE. GREASE CAPS SHALL BE PLACED ON THE SIDE OF THE NEW CURB AND GUTTER SHALL HAVE A PINCHED STOP THAT WILL PROVIDE A MINIMUM 1" EXPANSION.
- TOOLED CONTROL JOINTS OR SAWCUTS SHALL BE MADE EVERY 15' AND AT LEAST (1) CONTROL JOINT PROVIDED AT ADA CURB RAMPS PER CITY STANDARD DETAIL NO. 7.10.
- SAWCUTS SHALL BE MADE WITHIN TWENTY-FOUR (24) HOURS AND SEALED WITH A CITY APPROVED JOINT SEALANT. JOINTS SHALL BE CLEAN AND DRY PRIOR TO APPLICATION OF SEALANT.
- FOR CURB AND GUTTER CONSTRUCTED OVER UTILITY TRENCHES, TWO (2) EPOXY COATED REINFORCING BARS (NO. 5) SHALL BE PLACED IN THE CURB AND GUTTER, CENTERED OVER THE TRENCH.




**CITY OF BATAVIA
PUBLIC WORKS DEPARTMENT**

SHEET: 1 OF 1
DATE: 11/8/18

B6.12 BARRIER CURB & GUTTER

STANDARD NO. 7.04



NOTES:

- THE COMPLETE REPAIR OF PAVEMENTS ADJACENT TO THE REPLACEMENT CONCRETE CURB AND GUTTER IS INCLUDED IN THE COST OF THE NEW CURB AND GUTTER.
- CLASS SI CONCRETE SHALL BE POURED SEPARATELY FROM THE CURB ONCE THE FORM BOARDS HAVE BEEN REMOVED.



**CITY OF BATAVIA
PUBLIC WORKS DEPARTMENT**

SHEET: 1 OF 1
DATE: 1/1/16

CURB REPLACEMENT

STANDARD NO. 7.07

MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CAD - Sheets\B6.12 Barrier Curb & Gutter.dwg



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME	= mfortmann
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED	-	_____
DRAWN	-	_____
CHECKED	-	_____
DATE	-	_____

	-	_____
	-	_____
	-	_____
	-	_____

	-	_____
	-	_____
	-	_____
	-	_____

	-	_____
	-	_____
	-	_____
	-	_____

	-	_____
	-	_____
	-	_____
	-	_____

	-	_____
	-	_____
	-	_____
	-	_____

	-	_____
	-	_____
	-	_____
	-	_____

	-	_____
	-	_____
	-	_____
	-	_____

	-	_____
	-	_____
	-	_____
	-	_____

**PEACE BRIDGE
BIKE RAMP**

ILLINOIS

SCALE: NONE

SHEET 5

OF 11

SHEETS

STA.

TO STA.

CONSTRUCTION DETAILS

COUNTY


KANE

TOTAL SHEETS

63

SHEET NO.

57



ISOMETRIC VIEW

NOTES:

1. ALL AGGREGATE SUB-BASE SHALL BE MECHANICALLY COMPACTED.
2. SIDEWALK THICKNESS AT CURB RAMPS SHALL BE A MINIMUM OF 6" PCC ON 2" AGGREGATE SUB BASE.
3. SIDEWALK CONSTRUCTION SHALL FOLLOW APPLICABLE IDOT STANDARDS.
4. SIDEWALKS SHALL FOLLOW CURRENT ADA GUIDELINES.
5. PROVIDE AT LEAST ONE (1) TOOLED OR SAWCUT CONTROL JOINT IN THE CURB. JOINT SHALL BE INLINE WITH SIDEWALK EDGE.
6. DETECTABLE WARNING TILE COLOR SHALL BE "BRICK RED" OR AS APPROVED BY THE CITY OF BATAVIA.

APPLICABLE IDOT STANDARD DETAILS OR LATEST REVISION THEREOF:

424001-07	PERPENDICULAR CURB RAMPS FOR SIDEWALKS
424006-01	DIAGONAL CURB RAMPS FOR SIDEWALKS
424011-01	CORNER PARALLEL CURB RAMPS FOR SIDEWALKS
424016-01	MID-BLOCK CURB RAMPS FOR SIDEWALKS
424021-01	DEPRESSED CORNER FOR SIDEWALKS
424026-01	ENTRANCE/ALLEY PEDESTRIAN CROSSINGS
424031-01	MEDIAN PEDESTRIAN CROSSINGS
606001-05	CONCRETE CURB TYPE B AND COMB CONCRETE CURB AND GUTTER

APPROVED ADA DETECTABLE WARNING TILES:

1. ADA SOLUTIONS - CAST IN PLACE REPLACEABLE
2. ARMOR TILE - CAST IN PLACE
3. DETECTILE - SLIMTEK II
4. TUFTILE - POLYMER WET-SET




CITY OF BATAVIA
PUBLIC WORKS DEPARTMENT

SHEET: 1 OF 1
DATE: 8/18/20

CURB RAMPS

STANDARD NO. 7.10



CITY OF BATAVIA
PUBLIC WORKS DEPARTMENT

SHEET: 1 OF 4
DATE: 1/12/21

ACCESSIBLE PARKING SPACE MARKINGS

STANDARD NO. 7.12



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

SCALE: NONE

SHEET 6

OF

11 SHEETS

STA.

TO STA.

CONSTRUCTION DETAILS

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	58

MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CAAD_Sheet\241108-shl-std-01.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

-
-
-
-

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

SCALE: NONE

SHEET 7

OF



11 SHEETS

STA.


TO STA.

CONSTRUCTION DETAILS


COUNTY TOTAL SHEETS SHEET NO.
KANE 63 59



FLOATING SILT CURTAIN - TYPICAL LAYOUT



TYPICAL COMPONENTS / ANCHORAGE SYSTEM



TYPICAL PLAN VIEW


Maximum flow for waterbody shall be less than 5fps.
Isolated work area shall not exceed more than 1/3 stream width.
Silt curtain shall be placed parallel to stream flow.

REFERENCE
Project _____
Designed _____ Date _____
Checked _____ Date _____
Approved _____ Date _____




STANDARD DWG. NO.
IUM-617A
SHEET 1 OF 1
DATE 1-06-2012

FLOATING SILT CURTAIN - PANEL CONNECTORS



SEWN SEAM



GROMMETED HOLES WITH ROPE LACING

REFERENCE
Project _____
Designed _____ Date _____
Checked _____ Date _____
Approved _____ Date _____



STANDARD DWG. NO.
IUM-617B
SHEET 1 OF 1
DATE 1-6-2012

MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CAD - Sheets\241108-shs-01.dgn



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
DESIGNED - _____
DRAWN - _____
CHECKED - _____
DATE - _____
PLOT SCALE = _____
PLOT DATE = 4/25/2025

DESIGNED - _____
DRAWN - _____
CHECKED - _____
DATE - _____

PEACE BRIDGE
BIKE RAMP


CONSTRUCTION DETAILS

ILLINOIS SCALE: NONE SHEET 8 OF 11 SHEETS STA. TO STA.

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	60

PIPE OUTLET TO CHANNEL

Pipe Outlet To Well-Defined Channel



NOTES:



1. The filter fabric shall meet the requirements in material specification 592 GEOTEXTILE Table 1 or 2, Class I, II or III.
2. The rock riprap shall meet the IDOT requirements for the following gradation RR4.
3. The riprap shall be placed according to construction specification 61 LOOSE ROCK RIPRAP. The rock may be equipment placed.

REFERENCE	
Project	_____
Designed	_____ Date _____
Checked	_____ Date _____
Approved	_____ Date _____




STANDARD DWG. NO.	IL-611
SHEET 1 OF 1	
DATE	8-18-94


AUTOCAD2006




DETAIL 1




DETAIL 2



DETAIL 3



STAPLE DETAIL



PUSH PIN DETAIL

NOTES:

1. Staples shall be placed in a diamond pattern at 2 per s.y. for stiched blankets. Non-stiched shall use 4 staples per s.y. of material. This equates to 200 staples with stiched blanket and 400 staples with non-stiched blanket per 100 s.y. of material.
2. Staple or push pin lengths shall be selected based on soil type and conditions. (minimum staple length is 6")
3. Erosion control material shall be placed in contact with the soil over a prepared seedbed.
4. All anchor slots shall be stapled at approximately 12" intervals.

Sheet 1 of 1	File No. 11M-530	Drawn by	Designed	Date
			Drawn B. JOHNSON	11/08
			Checked	
			Approved	
EROSION CONTROL BLANKET INSTALLATION DETAILS				

MODEL: Default
FILE NAME: N:\2024\241108\Drawings\Main\CAD - Sheets\241108-sh1.dwg



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME	= mfortmann
DESIGNED	- _____
DRAWN	- _____
CHECKED	- _____
DATE	- _____
PLOT SCALE	=
PLOT DATE	= 4/25/2025

DESIGNED	- _____	- _____	- _____
DRAWN	- _____	- _____	- _____
CHECKED	- _____	- _____	- _____
DATE	- _____	- _____	- _____

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS


SCALE: NONE SHEET 9 OF 11 SHEETS STA. TO STA.

CONSTRUCTION DETAILS

COUNTY	TOTAL SHEETS	SHEET NO.
KANE	63	61


ROLLED EROSION CONTROL PRODUCTS

STAKING PATTERN GUIDE



- NOTES:
- 1. OVERLAP MINIMUM IS THE DIAMETER OF THE ROLL.
 - 2. 4' SPACING FOR WATTLES.
 - 3. 2' SPACING FOR ROLLED EXCELSIOR.
 - 4. OR SPACE ACCORDING TO MANUFACTURER'S SPECIFICATIONS.

STAKE DETAIL




- NOTES:
- 1. DRAWINGS ARE NOT TO SCALE.
 - 2. ENDS OF WATTLES OR ROLLED EXCELSIOR SHALL BE TURNED AT LEAST 6" UPSLOPE.
 - 3. RECOMMENDED STAKES ARE 1 1/8" WIDE x 1 1/8" THICK x 30" LONG.
 - 4. STAKES SHALL NOT EXTEND ABOVE THE STRAW WATTLE MORE THAN 2".
 - 5. SPACING: THE TOE OF THE UPSTREAM DITCH CHECK SHALL CREATE A HORIZONTAL LINE WITH THE TOP OF THE DOWNSTREAM DITCH CHECK.

REFERENCE
Project _____
Designed _____ Date _____
Checked _____ Date _____
Approved _____ Date _____



STANDARD DWG. NO.
IUM-514
SHEET 1 OF 1
DATE 08-2-2019

SUMP PIT PLAN




- NOTES:
- 1. Pit dimensions are optional.
 - 2. The standpipe will be constructed by perforating a 12"-24" diameter corrugated metal or PVC pipe.
 - 3. A base of 2" aggregate will be placed in the pit to a minimum depth of 12". After installing the standpipe, the pit surrounding the standpipe will then be backfilled with 2" aggregate.
 - 4. The standpipe will extend 12" to 18" above the lip of the pit.
 - 5. If discharge will be pumped directly to a storm drainage system, the standpipe will be wrapped with filter fabric before installation.
 - 6. If desired, 1/4"-1/2" hardware cloth may be placed around the standpipe prior to attaching the filter fabric. This will increase the rate of water seepage into the pipe.

REFERENCE
Project _____
Designed _____ Date _____
Checked _____ Date _____
Approved _____ Date _____



STANDARD DWG. NO.
IL-650
SHEET 1 OF 1
DATE 8-11-94



EXAMPLE OF PORTABLE CONCRETE WASHOUT CONTAINER

PURPOSE:

TEMPORARY CONCRETE WASHOUT FACILITIES ARE USED TO CONTAIN CONCRETE LIQUIDS WHEN THE CHUTES OF CONCRETE TRUCKS ARE RINSED OUT AFTER DELIVERY OF CONCRETE TO THE CONSTRUCTION SITE. THESE WASHOUT FACILITIES FUNCTION TO CONSOLIDATE SOLIDS FOR DISPOSAL AND PREVENT RUNOFF LIQUIDS ASSOCIATED WITH CONCRETE. FAILURE TO COMPLY WITH APPROPRIATE WASHOUT LOCATION REQUIREMENTS WILL RESULT IN MONETARY DEFICIENCY DEDUCTION AGAINST THE CONTRACTOR.


IMPLEMENTATION:

- TEMPORARY CONCRETE WASHOUT FACILITIES ARE TO BE IN PLACE BEFORE ANY DELIVERY OF CONCRETE TO THE CONSTRUCTION SITE.
- TEMPORARY CONCRETE WASHOUT FACILITIES ARE TO BE LOCATED AT LEAST 50 FEET FROM STORM DRAIN INLETS, OPEN DRAINAGE FACILITIES, OR WATER BODIES. EACH FACILITY IS TO BE LOCATED AWAY FROM CONSTRUCTION TRAFFIC OR ACCESS AREAS TO PREVENT DISTURBANCE OR TRACKING.
- A SIGN IS TO BE INSTALLED ADJACENT TO EACH TEMPORARY CONCRETE WASHOUT FACILITY TO INFORM CONCRETE EQUIPMENT OPERATORS OF THE DESIGNATED WASHOUT FACILITY.

INSPECTION/MAINTENANCE/REMOVAL:

- TEMPORARY CONCRETE WASHOUT FACILITIES ARE TO BE INSPECTED DURING WEEKLY EROSION AND SEDIMENT CONTROL INSPECTION, AFTER A STORM EVENT OF 1/2" OR GREATER AND AT THE END OF ANY DAY WHEN CONCRETE HAS BEEN POURED ON THE CONSTRUCTION SITE. THE INSPECTOR IS TO ENSURE THAT THERE ARE NO LEAKS, NO SPILLS AND THAT THE FACILITIES CAPACITY HAS NOT YET BEEN COMPROMISED.
- ANY OVERFLOWING OF THE WASHOUT FACILITY ONTO THE GROUND MUST BE CLEANED UP AND REMOVED WITHIN 24 HOURS OF DISCOVERY.
- IF A RAIN OR SNOW EVENT IS FORECASTED, A NON-COLLAPSING, NON-WATER COLLECTING COVER SHALL BE PLACED OVER THE WASHOUT FACILITY AND SECURED TO PREVENT ACCUMULATION AND OVERFLOW OF PRECIPITATION.
- CONTENTS OF EACH CONCRETE WASHOUT FACILITY ARE NOT TO EXCEED 75% OF ITS DESIGNED CAPACITY. IF THE CONTENTS REACH 75% CAPACITY, DISCONTINUE POURING CONCRETE INTO THE FACILITY UNTIL IT HAS BEEN CLEANED OUT.
- ALLOW SLURRY TO EVAPORATE OR REMOVE FROM THE SITE IN A SAFE MANNER (IE. VACUUM TRUCK). ALL HARDENED MATERIAL CAN THEN BE REMOVED AND DISPOSED OF PROPERLY.
- IF A LINED BASIN IS USED, IMMEDIATELY REPLACE THE LINER IF IT BECOMES DAMAGED.
- REMOVE TEMPORARY CONCRETE WASHOUT FACILITIES WHEN THEY ARE NO LONGER NEEDED AND RESTORE THE DISTURBED AREAS TO THEIR ORIGINAL CONDITION.
- NOT THE LOCATIONS OF TEMPORARY CONCRETE WASHOUT FACILITIES AND CHANGES TO THESE FACILITIES ON THE SWPPP.

PORTABLE CONCRETE WASHOUT CONTAINER



NOTE: FILTER BAG SHALL BE PLACED ON A WELL VEGETATED GRASSY AREA OR SURROUNDED BY PERIMETER SEDIMENT PROTECTION.
DEWATERING PLAN TO BE PREPARED BY CONTRACTOR AND APPROVED PRIOR TO CONSTRUCTION.

LOW VOLUME FILTER BAGS SHALL BE MADE FROM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE FOLLOWING STANDARDS:

A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME 1/2 FULL OF SEDIMENT. SPARE BAGS SHALL BE AVAILABLE ON SITE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED.

NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. HOWEVER, IF NECESSARY TO CAPTURE ANY REMAINING SEDIMENT WITHIN THE RUNOFF AND GIVEN THE SITE SPECIFIC CONDITIONS A COMPOST BERM, COMPOST FILTER SOCK OR WATTLE SHALL BE INSTALLED BELOW BAGS LOCATED WITHIN 100 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE.

THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE.

THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR 1/2 THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED.

FILTER BAGS SHALL BE INSPECTED AT LEAST ONCE DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY AND SHALL NOT RESUME UNTIL A REMEDIAL SOLUTION IS ESTABLISHED AND THE PROBLEM IS CORRECTED.

SEDIMENT FILTRATION BAGS SHALL BE RAISED ABOVE THE SUPPORTING GROUND ON A SURFACE, OR MATERIAL, THAT ALLOWS WATER TO FLOW OUT OF THE BOTTOM OF THE BAG AT THE RESPECTIVE DESIGN DISCHARGE RATE FOR THE SEDIMENT FILTER BAG SELECTED.

DEWATERING FILTER BAG DETAIL



V3 Companies
7325 Janes Avenue
Woodridge, IL 60517
630.724.9200 phone
630.724.9202 fax
www.v3co.com

USER NAME = mfortmann
PLOT SCALE =
PLOT DATE = 4/25/2025

DESIGNED -
DRAWN -
CHECKED -
DATE -

-
-
-
-

-
-
-
-

BATAVIA

PEACE BRIDGE
BIKE RAMP

ILLINOIS

SCALE: NONE

SHEET 10 OF 11 SHEETS

STA.

TO STA.

CONSTRUCTION DETAILS

COUNTY TOTAL SHEETS SHEET NO.
KANE 63 62

