

VILLAGE OF SOUTH HOLLAND, ILLINOIS

THORN DITCH FLOOD MITIGATION PROJECT

LEGEND





INDEX OF SHEETS

- **COVER SHEET**
- 2. SUMMARY OF QUANTITIES & NOTES
- 3. TYPICAL CROSS SECTIONS
- ALIGNMENT, TIES & BENCHMARKS
- **EXISTING CONDITIONS & REMOVALS**
- 11.-12. GRADING PLAN
- 13.-19. PLAN & PROFILE
- 20.-24. LANDSCAPING & EROSION CONTROL
- STORM WATER POLLUTION PREVENTION
- PEDESTRIAN BRIDGE STRUCTURE PLANS
- 37.-63. CULVERT DETAILS
- 64.-69. CONSTRUCTION DETAILS
- 70.-71. DETOUR PLAN





- INDICATES PROPOSED IMPROVEMENT





PROJECT NO. 23-R0646

SUMMARY OF QUANTITIES

NO.	ITEM DESCRIPTION	UNIT	QUANTITY
1	MOBILIZATION	LSUM	1
2	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	617
3	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	986
4	TREE TRUNK PROTECTION	EACH	20
5	EARTH EXCAVATION	CU YD	38,800
6	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	50
7	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	50
8	EXPLORATION TRENCH 84" DEPTH	FOOT	90
9	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,420
10	PAVEMENT REMOVAL	SQ YD	610
11	COMBINATION CURB AND GUTTER REMOVAL	FOOT	350
12	SIDEWALK REMOVAL	SQ FT	1,580
13	REMOVAL OF EXISTING STRUCTURES	L SUM	1
14	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1
15	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1
16	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1
17	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1
18	PRECAST CONCRETE BOX CULVERTS 7' X 7'	FOOT	856
19	PRECAST CONCRETE BOX CULVERTS 10' X 7'	FOOT	184
20	STRUCTURE EXCAVATION	CU YD	4,329
21	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	1,709
22	CONCRETE STRUCTURES	CU YD	25
23	GRANULAR BACKFILL FOR STRUCTURES	CU YD	8
24	CONCRETE SEALER	SQFT	332
25	REINFORCEMENT BARS, EPOXY COATED	POUND	2,320
26	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	3
27	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	1
28	BOX CULVERT END SECTIONS, CULVERT NO. 3	EACH	4
29	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	31
	STORM SEWERS, CLASS A, TYPE 2 18"		
30		FOOT	41 397
32	STORM SEWERS, CLASS A, TYPE 1 24" STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	150
	PIPE UNDERDRAINS, TYPE 1, 4"		
33	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	FOOT	486
35	MANHOLES, TYPE A, 4-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH EACH	2
36	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2
37	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	1
38	PRECAST REINFORCED CONCRETE ELARED END SECTIONS 12"	EACH	1
39	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1
40	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1
41	STORM SEWER REMOVAL 6"	FOOT	5
42	STORM SEWER REMOVAL 6"	FOOT	15
43	STORM SEWER REMOVAL 6 STORM SEWER REMOVAL 33"	FOOT	68
43			
44	REMOVING MANHOLES REMOVING CATCH BASINS	EACH EACH	1 4
46	REMOVING INLETS	EACH	6
		EACH	
47	VALVE BOXES TO BE ADJUSTED		1
48	MANHOLES TO BE ADJUSTED	EACH	1
49	ADJUSTING WATER MAIN 6" 20" DIAMETER STEEL SLEEVE, 0.344" WALL THICKNESS, OPEN CUT	FOOT	150
50	INSTALLATION	FOOT	130
51	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	350
52	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	160
53	AGGREGATE BASE COURSE, TYPE B 5"	SQ YD	100
54	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	640
55	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	1,710
56	BITUMINOUS MATERIALS (PRIME COAT)	POUND	1,330
57	BITUMINOUS MATERIALS (TACK COAT)	POUND	270
58	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	140
59	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	TON	70
60	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	5,872
61	SEEDING, CLASS 2A	ACRE	2.8
62	SEEDING, MESIC PRAIRIE	ACRE	1.05

63 SE	EEDING, SEDGE MEADOW MIX	ACRE	1
64 ER	ROSION CONTROL BLANKET	SQ YD	24,200
65 PE	ERENNIAL PLANTS, WETLAND EMERGENT	ACRE	0.34
66 TE	EMPORARY EROSION CONTROL SEEDING	POUND	280
67 TE	EMPORARY DITCH CHECKS	FOOT	240
68 PE	RIMETER EROSION BARRIER	FOOT	5,030
69 IN	ILET FILTERS	EACH	19
70 TE	EMPORARY EROSION CONTROL BLANKET	SQ YD	13,170
71 ST	TONE RIPRAP, CLASS A3	SQ YD	10
72 ST	ONE RIPRAP, CLASS A4	SQ YD	30
73 ST	TONE RIPRAP, CLASS A5	SQ YD	1,260
74 FIL	LTER FABRIC	SQ YD	1,300
75 PII	LLAR RELOCATION	EACH	6
76 CC	ONNECTION TO EXISTING SEWER	EACH	5
77 BI	AXIAL GEOGRID	SQ YD	1,607
78 TR	RENCH BACKFILL	CU YD	137
79 PO	DROUS GRANULAR EMBANKMENT	CU YD	4,606
80 PC	DROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	589
81 PL	LUG EXISTING STORM SEWERS	EACH	1
82 FE	ENCE REMOVAL AND REINSTALLATION	FOOT	480
83 W	OOD FENCE	FOOT	85
84 ME	EMBRANE WATERPROOFING SYSTEM FOR BURIED STRUCTURES	SQ YD	1,296
85 CL	LEANOUTS	EACH	1
86 W	ATER MAIN LINE STOP 6"	EACH	5
87 SA	ANITARY SEWER MAIN LINE REPAIR 10"	FOOT	25
	ANITARY SEWER MAIN LINE REPAIR 8"	FOOT	32
	ANITARY SEWER POINT REPAIRS, 10"	LF	40
	URED-IN-PLACE PIPE LINER, 10"	FOOT	187
	UT PROTRUDING TAPS	EACH	1
	ERVICE LATERALS TO BE REINSTATED	EACH	2
	YE TESTING OF PROPERTIES	EACH	1
94 MA	ANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR	EACH	1
os PF	ATE ATE APPENDED MANHOLE/CATCH BASIN CONNECTION OVER EXISTING STORM	EACH	2
SE	EWER RAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
	HANGEABLE MESSAGE SIGN	CAL DA	500
	TORM SEWER BACKFLOW PREVENTER, 18"	EACH	1
	ELICAL PIER	EACH	172
100 TF	REE, ACER SACCHARUM (SUGAR MAPLE), 3" CALIPER, BALLED AND	FACH	14
404 TF	JRLAPPED REE, ULMUS CARPINIFOLIA NEW HORIZON (NEW HORIZON SMOOTHLEAF	EACH	14
EL	.M), 3" CALIPER, BALLED AND BURLAPPED REE, QUERCUS RUBRA (RED OAK), 3" CALIPER, BALLED AND BURLAPPED	EACH	14
	TABILIZED CONSTRUCTION ENTRANCE	SQ YD	280
	OCK FILL	CU YD	1,110
	AYGROUND EQUIPMENT REMOVAL	LSUM	1
	RECAST CONCRETE RISER, T1F, OL	EACH	10
	DND AERATING FOUNTAIN EMOVE EXISTING OUTLET	EACH EACH	3
	ONTRACT EXTRA WORK	UNIT	150.000
		L SUM	150,000
-	EMOVAL AND RELOCATION OF EXISTING PEDESTRIAN BRIDGE		
	OOD DECKING SPECIAL	SQ FT	210
	EDESTRIAN TRUSS SUPERSTRUCTURE	SQ FT	210
	LECTRIC SERVICE INSTALLATION	EACH	3
114 EL	ECTRIC UTILITY SERVICE CONNECTION	L SUM	1

GENERAL NOTES

- THESE CONSTRUCTION PLANS AND SUBSEQUENT DETAILS ARE TO BE CONSIDERED AS PART OF THE CONTRACT DOCUMENTS. INCIDENTAL ITEMS OR ACCESSORIES NECESSARY TO COMPLETE THIS WORK MAY NOT BE SPECIFICALLY NOTED BUT ARE TO BE CONSIDERED A PART OF THE CONTRACT.
- THE ROBINSON ENGINEERING, LTD. FIELD OFFICE (708-331-6700), THE VILLAGE OF SOUTH HOLLAND PUBLIC WORKS (708-339-2323) AND THE MWRD LOCAL SEWER SYSTEMS SECTION OFFICE (708-588-4055) SHALL BE NOTIFIED AT LEAST TWO (2) WORKING DAYS PRIOR TO START OF CONSTRUCTION.
- 3. THE WORK TO BE PERFORMED UNDER THIS CONTRACT SHALL INCLUDE ALL THE NECESSARY LABOR, EQUIPMENT AND MATERIALS REQUIRED TO FURNISH AND INSTALL PROPOSED WATER MAIN AND ALL OTHER APPURTENANCES AS SHOWN ON THE PLANS AND AS DESCRIBED IN THESE SPECIFICATIONS.
- 4. EXCEPT WHERE MODIFIED BY THE CONTRACT DOCUMENTS, ALL WORK PROPOSED HEREIN SHALL BE IN ACCORDANCE WITH THE FOLLOWING SPECIFICATIONS. WHICH ARE HEREBY MADE A PART HEREOF:
 - A. "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION IN ILLINOIS". AS PREPARED BY IDOT. LATEST EDITION.
 - B. VILLAGE ORDINANCES.
 - C. "STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS". LATEST EDITION.
- 5. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR PROVIDING SAFE AND HEALTHFUL WORKING CONDITIONS THROUGHOUT THE CONSTRUCTION OF THE PROPOSED IMPROVEMENTS. THE CONTRACTOR MUST, THEREFORE, BE FAMILIAR WITH AND ADHERE TO THE MINIMUM SAFETY STANDARDS AS SET FORTH IN PUBLIC LAW 91–596 ADMINISTERED BY THE DEPARTMENT OF LABOR OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION AND AS FURTHER DEFINED IN PART 1926 OF TILE 29 CODE OF THE FEDERAL REGULATIONS ENTITLED "SAFETY AND HEALTH REGULATIONS FOR
- 6. ALL UTILITY COMPANIES SHALL BE CONTACTED AND THEIR FACILITIES SHALL BE LOCATED PRIOR TO ANY WORK IN ANY EASEMENT, RIGHT—OF—WAY, OR SUSPECTED UTILITY LOCATION. REPAIR OF ANY DAMAGE TO EXISTING FACILITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. UTILITY LOCATIONS SHOWN HEREIN ARE FOR GRAPHIC ILLUSTRATION ONLY AND ARE NOT TO BE RELIED UPON.
- 7. PRIOR TO COMMENCEMENT OF CONSTRUCTION, THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS AFFECTING THEIR WORK WITH THE ACTUAL CONDITIONS AT THE JOB SITE. IF THERE ARE ANY DISCREPANCIES FROM WHAT IS SHOWN ON THE CONSTRUCTION PLANS, HE MUST IMMEDIATELY REPORT SAME TO THE ENGINEER BEFORE DOING ANY WORK, OTHERWISE THE CONTRACTOR ASSUMES FULL RESPONSIBILITY. IN THE EVENT OF DISAGREEMENT BETWEEN THE CONSTRUCTION PLANS, STANDARD SPECIFICATIONS AND/OR SPECIAL DETAILS, THE CONTRACTOR SHALL SECURE WRITTEN INSTRUCTIONS FROM THE ENGINEER PRIOR TO PROCEEDING WITH ANY PART OF THE WORK AFFECTED BY OMISSIONS OR DISCREPANCIES, FAILING TO SECURE SUCH INSTRUCTION, THE CONTRACTOR WILL BE CONSIDERED TO HAVE PROCEEDED AT HIS OWN RISK AND EXPENSE. IN THE EVENT OF ANY DOUBT OR QUESTION ARISING WITH RESPECT TO THE TRUE MEANING OF THE CONSTRUCTION PLANS OR SPECIFICATIONS, THE DECISION OF THE ENGINEER SHALL BE FINAL AND CONCLUSIVE.


- ALL WORK PERFORMED UNDER THIS CONTRACT SHALL BE GUARANTEED AGAINST ALL DEFECTS IN MATERIALS AND WORKMANSHIP OF WHATEVER NATURE BY THE CONTRACTOR AND HIS SURETY FOR A PERIOD OF 12 MONTHS FROM THE DATE OF FINAL WRITTEN ACCEPTANCE OF THE WORK BY THE VILLAGE AND OTHER APPLICABLE GOVERNMENTAL AGENCIES.
- THE CONTRACTOR SHALL INFORM THE ENGINEER AND THE VILLAGE BEFORE WORK COMMENCES ON EACH CATEGORY OF CONSTRUCTION, I.E. EARTH EXCAVATION FOR DETENTION PONDS, STORM SEWERS, BOX CULVERTS, PAVING AND RESTORATION IMPROVEMENTS.
- 10. EASEMENTS FOR THE EXISTING UTILITIES, BOTH PUBLIC AND PRIVATE, AND UTILITIES WITHIN PUBLIC RICHTS-OF-WAY ARE SHOWN ON THE PLANS ACCORDING TO AVAILABLE RECORDS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE EXACT LOCATION IN THE FIELD OF THESE UTILITY LINES AND THEIR PROTECTION FROM DAMAGE DUE TO CONSTRUCTION OPERATIONS. IF EXISTING UTILITY LINES OF ANY NATURE ARE ENCOUNTERED WHICH CONFLICT IN LOCATION WITH NEW CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY SO THAT THE CONFLICT MAY BE RESOLVED.
- 11. WHENEVER, DURING CONSTRUCTION OPERATIONS, ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF GUTTERS, DRAINAGE STRUCTURES, DITCHES, ETC. SUCH THAT THE NATURAL FLOW LINE OF WATER IS OBSTRUCTED, THIS LOOSE MATERIAL SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY BY THE CONTRACTOR. AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES AND FLOW LINES SHALL BE FREE FROM DIRT AND DEBRIS. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 12. ALL PERMANENT TYPE PAVEMENTS OR OTHER PERMANENT IMPROVEMENTS WHICH ABUT THE PROPOSED IMPROVEMENT AND MUST BE REMOVED SHALL BE SAWED AS DIRECTED PRIOR TO REMOVAL. ALL ITEMS SO REMOVED SHALL BE REPLACED WITH SIMILAR CONSTRUCTION MATERIALS TO THEIR ORIGINAL CONDITION OR BETTER.
- 13. REMOVED PAVEMENT, SIDEWALK, CURB AND GUTTER, ETC. SHALL BE DISPOSED OF BY THE CONTRACTOR AT HIS OWN EXPENSE AT LOCATIONS APPROVED BY THE ENGINEER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING AN OFF-SITE DUMP SITE AT HIS OWN EXPENSE.
- 14. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO REMOVE FROM THE SITE ANY AND ALL MATERIALS AND DEBRIS WHICH RESULT FROM HIS CONSTRUCTION OPERATIONS AT NO ADDITIONAL EXPENSE OF THE OWNER.
- 15. THE ENGINEER AND VILLAGE ARE NOT RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES OR PROCEDURES, TIME OF PERFORMANCE, PROGRAMS OR FOR ANY SAFETY PRECAUTIONS USED BY THE CONTRACTOR. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR EXECUTION OF HIS WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS AND SPECIFICATIONS.
- 16. ALL ELEVATIONS ARE BASED ON USGS NAVD 88' DATUM.
- 17. REMOVALS OF ANY CULVERT HEADWALLS AND EXISTING PEDESTRIAN BRIDGE FOUNDATIONS IS INCLUDED IN THE COST OF THE REMOVAL OF EXISTING STRUCTURES PAY ITEMS.


EARTHWORK SUMMARY							
EARTH	EXCAVATION				OF UNSUITABLE MATERIALS		
CUT (CY)	AGGREGATE PATH REMOVAL/INSTALLATION OUTSIDE LIMITS OF POND EXCAVATION (CY)	FILL (CY)	FILL (CY) ADJUSTED (+15%)	TOPSOIL PLACEMENT (CY)	(CY) TBD IN FIELD, ESTIMATED AT 10% OF PAVEMENT AREA	AGGREGATE SUBGRADE IMPROVEMENT (CY)	HAUL AWAY (CY)
			MAICACH PARK				
22,800	280	6	7	704	0	0	19,632
360	*			2,063			
0	0	0	0	219	0	0	
				456		•	
			DOBSON AVE		•		
25	0	0	0	120	10	10	-208
				113			
			GREENWOOD AVE		•		
25	0	0	0	111	10	10	-218
115				131			
			WOODLAWN AVE		•		
35	0	0	0	37	10	10	-89
210				87			
			PIONEER PARK				
8,455	100	36	41	552	0	0	6,802
120				1,159			
			KIMBARK AVE				
25	0	0	0	37	10	10	-12
80							
			KENWOOD AVE		•		
35	0	0	0	46	10	10	-48
150				37			
32435	380	42	48	5872	50	50	25859

	EARTHWORK QUANTITY SUMMARY				
ITEM CODE	PAY ITEM		CU YD		
20200100	EARTH EXCAVATION		32815		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL		50		
30300001	AGGREGATE SUBGRADE IMPROVEMENT		50		
STRUCTURE EXCAVATION SUMMARY		•			
20200100	EARTH EXCAVATION		5985		
50200100	STRUCTURE EXCAVATION		4329		
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES		1709		

	DATE =	05-06-2025	DESIGNED — MGP	REVISED —
	SCALE =		CHECKED — JDH	REVISED —
	PROJECT NO =	23-R0646	DRAWN — RG	REVISED —
LAST SAVED BY: NDENAULT ON 5/6/25 PLOTTED BY: JOHN HILSEN ON 5/6/25	FILE NAME =	23R0646-QUAN-01	CHECKED — AG	REVISED —







EXISTING LEGEND

KENWOOD AVENUE

- SIDEWALK REMOVAL (AS DIRECTED BY THE ENGINEER)
- EXISTING COMBINATION CURB AND GUTTER REMOVAL (AS DIRECTED BY THE ENGINEER)
- (C) PAVEMENT REMOVAL (AS DIRECTED BY THE ENGINEER)
- (D) EXISTING AGGREGATE REMOVAL TO 8" DEPTH
- (PAID AS EARTH EXCAVATION)
- ITEM TO BE REMOVED (AS DIRECTED BY THE ENGINEER)


HOT-MIX ASPHALT MIXTURE REQUIREMENTS			
MIXTURE TYPE AIR VOIDS @NDES			
PAVEMENT REPLACEMENT			
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (2")	4% @ 50 Gyr.	LR 1030-2	
HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 (4") 1 LIFT 4% @ 50 Gyr. LR 1030-		LR 1030-2	
QMP DESIGNATIONS: QUALITY CONTROL/QUALITY ASSURANCE (QC/QA) PER LOCAL ROADS SPECIFICATION 1030-2			


NOTE: UNIT WEIGHT USED TO CALCULATE ALL HMA SURFACE MIXTURE QUANTITIES IS 112 LBS/SQ YD/IN.

THE "AC TYPE" FOR POLYMERIZED HMA MIXES SHALL BE "SBS/SBR PG 76-22" AND FOR NON-POLYMERIZED HMA THE "AC TYPE" SHALL BE "PG 64-22" UNLESS MODIFIED BY DISTRICT 1 SPECIAL PROVISIONS. FOR USE OF RECYCLED MATERIALS SEE SPECIAL PROVISIONS.

QUALITY MANAGEMENT PROGRAM (QMP) IDENTIFIES THE PARTICULAR QUALITY CONTROL SPECIFICATION THAT APPLIES TO THE HMA MIXTURE.

	DATE = 05-06-2025	DESIGNED — MGP	REVISED —
	SCALE =	CHECKED — JDH	REVISED —
	PROJECT NO = 23-R0646	DRAWN — RG	REVISED —
LAST SAVED BY: JHILSEN ON 5/6/25 PLOTTED BY: JOHN HILSEN ON 5/6/25	FILE NAME = 23R0646-TYPX-01	CHECKED — AG	REVISED —






PROPOSED TYPICAL SECTION DOBSON AVENUE GREENWOOD AVENUE KIMBARK AVENUE KENWOOD AVENUE

PROPOSED LEGEND

- COMBINATION CONCRETE CURB AND GUTTER REPLACE IN KIND AS DIRECTED BY THE ENGINEER (SEE NOTE 1)
- 2" HMA SURFACE COURSE, MIX "D", N50
- 4" HMA BINDER COURSE, IL-9.5, N50
- AGGREGATE BASE COURSE, TYPE B, 8"
- PORTLAND CEMENT CONCRETE SIDEWALK, 5"
- AGGREGATE BASE COURSE, TYPE B, 4"
- TOPSOIL FURNISH AND PLACE, 6" WITH SEEDING CLASS 2A

MIN 5" AGGREGATE BASE PROVIDED UNDER THE PROPOSED CURB AND GUTTER, PAID AS AGGREGATE BASE COURSE, TYPE B, 5"








THORN DITCH FLOOD MITIGATION PROJECT TYPICAL CROSS SECTIONS


VILLAGE of SOUTH HOLLAND

SHEET NO. 3 of 71

















	DATE	=	05-06-2025	DESIGNED	_	MGP	REVISED	_	Ī
	SCALE	-	1"=20'	CHECKED	_	JDH	REVISED	_	
	PROJECT NO	=	23-R0646	DRAWN	_	BG/RG	REVISED	-	
LAST SAVED BY: JHILSEN ON 5/6/25 PLOTTED BY: JOHN HILSEN ON 5/6/25	FILE NAME	=	23R0646-RMVL-01	CHECKED	_	AG	REVISED	_	





THORN DITCH	
FLOOD MITIGATION PROJECT	
ISTING CONDITIONS & REMOVALS	

































TOPSOIL EXCAVATION AND PLACEMENT, 6" SEEDING CLASS 2A, EROSION CONTROL BLANKET


TOPSOIL EXCAVATION AND PLACEMENT, 12" SEEDING, MESIC PRAIRIE, EROSION CONTROL BLANKET


TOPSOIL EXCAVATION AND PLACEMENT, 12" SEEDING, SEDGE MEADOW MIX.


TOPSOIL EXCAVATION AND PLACEMENT, 12" PERENNIAL PLANTS, WETLAND EMERGENT

TREE, QUERCUS RUBRA (RED OAK), 3" CALIPER, BALLED AND BURLAPPED









A. REFERENCED SPECIFICATIONS

- 1. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE APPLICABLE SECTIONS OF THE FOLLOWING, EXCEPT AS MODIFIED HEREIN OR ON THE PLANS:

 * STANDARD SPECIFICATIONS FOR RODA AND BRIDGE CONSTRUCTION (LATEST EDITION), BY THE ILLINOIS DEPARTMENT OF TRANSPORTATION (IDOT SS) FOR ALL IMPROVEMENTS EXCEPT SANITARY SEWER AND WATER MAIN CONSTRUCTION;

 * STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS, LATEST EDITION (SSWS) FOR SANITARY SEWER AND WATER MAIN CONSTRUCTION;

 * VILLAGE OF SOUTH HOLLAND MUNICIPAL CODE;

 * THE METROPOLITAN WATER RECLAMATION DISTRICT OF GREATER CHICAGO (MWRD) WATERSHED MANAGEMENT ORDINANCE AND TECHNICAL GUIDANCE MANUAL;

 * IN CASE OF CONFLICT BETWEEN THE APPLICABLE ORDINANCES NOTED, THE MORE STRINGENT SHALL TAKE PRECEDENCE AND SHALL CONTROL ALL CONSTRUCTION.

- THE MWRD LOCAL SEWER SYSTEMS SECTION FIELD OFFICE MUST BE NOTIFIED AT LEAST TWO (2) WORKING DAYS PRIOR TO THE COMMENCEMENT OF ANY WORK (CALL 708-588-4055).
- 2. THE VILLAGE OF SOUTH HOLLAND ENGINEERING DEPARTMENT AND PUBLIC MUST BE NOTIFIED AT LEAST 24 HOURS PRIOR TO THE START OF CONSTRUCTION AND PRIOR TO EACH PHASE OF WORK. CONTRACTOR SHALL DETERMINE ITEMS REQUIRING INSPECTION PRIOR TO START OF CONSTRUCTION OR EACH WORK PHASE.
- 3. THE CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES PRIOR TO BEGINNING CONSTRUCTION FOR THE EXACT LOCATIONS OF UTILITIES AND FOR THEIR PROTECTION DURING CONSTRUCTION. IF EXISTING UTILITIES ARE ENCOUNTERED THAT CONFLICT IN LOCATION WITH NEW CONSTRUCTION, IMMEDIATELY NOTIFY THE ENGINEER SO THAT THE CONFLICT CAN BE RESOLVED. CALL J.U.L.I.E. AT 1-800-892-0123.

C. GENERAL NOTES

- 1. ALL ELEVATIONS SHOWN ON PLANS REFERENCE THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88)
- 2. MWRD, THE MUNICIPALITY AND THE OWNER OR OWNER'S REPRESENTATIVE SHALL HAVE THE AUTHORITY TO INSPECT, APPROVE, AND REJECT THE CONSTRUCTION IMPROVEMENTS.
- THE CONTRACTOR(S) SHALL INDEMNIFY THE OWNER, ENGINEER, MUNICIPALITY, MWRD, AND THEIR AGENTS, ETC., FROM ALL LIABILITY INVOLVED WITH THE CONSTRUCTION, INSTALLATION, OR TESTING OF THIS WORK ON THE PROJECT.
- 4. THE PROPOSED IMPROVEMENTS MUST BE CONSTRUCTED IN ACCORDANCE WITH THE ENGINEERING PLANS AS APPROVED BY MWRD AND THE MUNICIPALITY UNLESS CHANGES ARE APPROVED BY MWRD, THE MUNICIPALITY, OR AUTHORIZED AGENT. THE CONSTRUCTION DETAILS, AS PRESENTED ON THE PLANS, MUST BE FOLLOWED. PROPER CONSTRUCTION TECHNIQUES MUST BE FOLLOWED ON THE IMPROVEMENTS
- 5. THE LOCATION OF VARIOUS UNDERGROUND UTILITIES WHICH ARE SHOWN ON THE PLANS ARE FOR INFORMATION ONLY AND REPRESENT THE BEST KNOWLEDGE OF THE ENGINEER. VERIFY LOCATIONS AND ELEVATIONS PRIOR TO BEGINNING THE CONSTRUCTION OPERATIONS.
- 6. ANY EXISTING PAVEMENT, SIDEWALK, DRIVEWAY, ETC., DAMAGED DURING CONSTRUCTION OPERATIONS AND NOT CALLED FOR TO BE REMOVED SHALL BE REPLACED AT THE EXPENSE OF THE CONTRACTOR.
- 7. MATERIAL AND COMPACTION TESTING SHALL BE PERFORMED IN ACCORDANCE WITH THE REQUIREMENTS OF THE MUNICIPALITY, MWRD, AND OWNER.
- 8. THE UNDERGROUND CONTRACTOR SHALL MAKE ALL NECESSARY ARRANGEMENTS TO NOTIFY ALL INSPECTION AGENCIES
- 9. ALL NEW AND EXISTING UTILITY STRUCTURES ON SITE AND IN AREAS DISTURBED DURING CONSTRUCTION SHALL BE ADJUSTED TO FINISH GRADE PRIOR TO FINAL INSPECTION.
- 10. RECORD DRAWINGS SHALL BE KEPT BY THE CONTRACTOR AND SUBMITTED TO THE ENGINEER AS SOON AS UNDERGROUND IMPROVEMENTS ARE COMPLETED. FINAL PAYMENTS TO THE CONTRACTOR SHALL BE HELD UNTIL THEY ARE RECEIVED. ANY CHANGES IN LENGTH, LOCATION OR ALIGNMENT SHALL BE SHOWN IN RED. ALL WYES OR BENDS SHALL BE LOCATED FROM THE DOWNSTREAM MANHOLE. ALL VALVES, B-BOXES, TEES OR BENDS SHALL BE TIED TO A FIRE HYDRANT.

- 1. THE CONTRACTOR SHALL TAKE MEASURES TO PREVENT ANY POLLUTED WATER, SUCH AS GROUND AND SURFACE WATER, FROM ENTERING THE EXISTING SANITARY SEWERS.
- 2. A WATER-TIGHT PLUG SHALL BE INSTALLED IN THE DOWNSTREAM SEWER PIPE AT THE POINT OF SEWER CONNECTION PRIOR TO COMMENCING ANY SEWER CONSTRUCTION. THE PLUG SHALL REMAIN IN PLACE UNTIL REMOVAL IS AUTHORIZED BY THE MUNICIPALITY AND/OR MWRD AFTER THE SEWERS HAVE BEEN
- 3. DISCHARGING ANY UNPOLLUTED WATER INTO THE SANITARY SEWER SYSTEM FOR THE PURPOSE OF SEWER FLUSHING OF LINES FOR THE DEFLECTION TEST SHALL BE PROHIBITED WITHOUT PRIOR APPROVAL FROM THE MUNICIPALITY OR MWRD.
- 4. ALL SANITARY SEWER CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS (LATEST EDITION).
- 5. ALL FLOOR DRAINS SHALL DISCHARGE TO THE SANITARY SEWER SYSTEM
- 6. ALL DOWNSPOUTS AND FOOTING DRAINS SHALL DISCHARGE TO THE STORM SEWER SYSTEM.
- 7. ALL SANITARY SEWER PIPE MATERIALS AND JOINTS (AND STORM SEWER PIPE MATERIALS AND JOINTS IN A COMBINED SEWER AREA) SHALL CONFORM TO THE FOLLOWING:

PIPE MATERIAL	PIPE SPECIFICATIONS	JOINT SPECIFICATIONS
VITRIFIED CLAY PIPE	ASTM C-700	ASTM C-425
REINFORCED CONCRETE SEWER PIPE	ASTM C-76	ASTM C-443
CAST IRON SOIL PIPE	ASTM A-74	ASTM C-564
DUCTILE IRON PIPE	ANSI A21.51	ANSI A21.11
POLYVINYL CHLORIDE (PVC) PIPE 6-INCH TO 15-INCH DIAMETER SDR 26 18-INCH TO 27-INCH DIAMETER F/DY=46	ASTM D-3034 ASTM F-679	ASTM D-3212 ASTM D-3212
HIGH DENSITY POLYETHYLENE (HDPE)	ASTM D-3350 ASTM D-3035	ASTM D-3261,F-2620 (HEAT FUSION ASTM D-3212,F-477 (GASKETED)
WATER MAIN QUALITY PVC 4-INCH TO 36-INCH 4-INCH TO 12-INCH 14-INCH TO 48-INCH	ASTM D-2241 AWWA C900 AWWA C905	ASTM D-3:12,1-477 (GASKETED) ASTM D-3:139 ASTM D-3:139 ASTM D-3:139

THE FOLLOWING MATERIALS ARE ALLOWED ON A QUALIFIED BASIS SUBJECT TO DISTRICT REVIEW AND APPROVAL PRIOR TO PERMIT ISSUANCE. A SPECIAL CONDITION WILL BE ADDED TO THE PERMIT WHEN THE PIPE MATERIAL BELOW IS USED FOR SEWER CONSTRUCTION OR A CONNECTION IS MADE.

PIPE MATERIAL	PIPE SPECIFICATIONS	JOINT SPECIFICATIONS
POLYPROPYLENE (PP) PIPE		
12-INCH TO 24-INCH DOUBLE WALL	ASTM F-2736	D-3212, F-477
30-INCH TO 60-INCH TRIPLE WALL	ASTM F-2764	D3212, F-477

- 8. ALL SANITARY SEWER CONSTRUCTION (AND STORM SEWER CONSTRUCTION IN COMBINED SEWER AREAS), REQUIRES STONE BEDDING WITH STONE '% "TO 1" IN SIZE, WITH MINIMUM BEDDING THICKNESS EQUAL TO '% THE OUTSIDE DIAMETER OF THE SEWER PIPE, BUT NOT LESS THAN FOUR (JUNCHES NOR MORE THAN EIGHT (8) INCHES. MATERIAL SHALL BE CA-7, CA-11 OR CA-13 AND SHALL BE EXTENDED AT LEAST 12" ABOVE THE TOP OF THE PIPE WHEN USING PVC.
- 9. NON-SHEAR FLEXIBLE-TYPE COUPLINGS SHALL BE USED IN THE CONNECTION OF SEWER PIPES OF DISSIMILAR PIPE MATERIALS.
- 10. ALL MANHOLES SHALL BE PROVIDED WITH BOLTED, WATERTIGHT COVERS. SANITARY LIDS SHALL BE CONSTRUCTED WITH A CONCEALED PICKHOLE AND WATERTIGHT GASKET WITH THE WORD "SANITARY"
- 11. WHEN CONNECTING TO AN EXISTING SEWER MAIN BY MEANS OTHER THAN AN EXISTING WYE, TEE, OR AN EXISTING MANHOLE, ONE OF THE FOLLOWING METHODS SHALL BE USED:


 a) A CIRCULAR SAW-CUT OF SEWER MAIN BY PROPER TOOLS ("SHEWER-TAP" MACHINE OR SIMILAR)
 AND PROPER INSTALLATION OF HUBWYE SADDLE OR HUB-TEE SADDLE.
 b) REMOVE AN ENTIRE SECTION OF PIPE (BREAKING ONLY THE TOP OF ONE BELL) AND REPLACE WITH

 - A WYE OR TEE BRANCH SECTION. c) WITH PIPE CUTTER, NEATLY AND ACCURATELY CUT OUT DESIRED LENGTH OF PIPE FOR INSERTION OF PROPER FITTING, USING "BAND SEAL" OR SIMILAR COUPLINGS TO HOLD IT FIRMLY IN PLACE.
- 12 WHENEVER A SANITARY/COMBINED SEWER CROSSES LINDER A WATERMAIN. THE MINIMUM VERTICAL DISTANCE FROM THE TOP OF THE SEWER TO THE BOTTOM OF THE WATERMAIN SHALL BE 18 INCHES. FURTHERMORE, A MINIMUM HORIZONTAL DISTANCE OF 10 FEET BETWEEN SANITARY/COMBINED SEWERS AND WATERMAINS SHALL BE MAINTAINED UNLESS: THE SEWER IS LAID IN A SEPARATE TRENCH, KEEPING A MINIMUM 18" VERTICAL SEPARATION; OR THE SEWER IS LAID IN THE SAME TRENCH WITH THE WATERMAIN LOCATED AT THE OPPOSITE SIDE ON A BENCH OF UNDISTURBED EARTH, KEEPING A MINIMUM 18" VERTICAL SEPARATION. IF EITHER THE VERTICAL OR HORIZONTAL DISTANCES DESCRIBED CANNOT BE MAINTAINED. OR THE SEWER CROSSES ABOVE THE WATER MAIN THE SEWER SHALL BE CONSTRUCTED TO WATER MAIN STANDARDS OR IT SHALL BE ENCASED WITH A WATER MAIN QUALITY CARRIER PIPE WITH THE ENDS SEALED.
- 13. ALL EXISTING SEPTIC SYSTEMS SHALL BE ABANDONED. ABANDONED TANKS SHALL BE FILLED WITH GRANULAR MATERIAL OR REMOVED.
- 14. ALL SANITARY MANHOLES, (AND STORM MANHOLES IN COMBINED SEWER AREAS), SHALL HAVE A MINIMUM INSIDE DIAMETER OF 48 INCHES, AND SHALL BE CAST IN PLACE OR PRE-CAST REINFORCED
- 15. ALL SANITARY MANHOLES, (AND STORM MANHOLES IN COMBINED SEWER AREAS), SHALL HAVE PRECAST "RUBBER BOOTS" THAT CONFORM TO ASTM C-923 FOR ALL PIPE CONNECTIONS. PRECAST SECTIONS SHALL CONSIST OF MODIFIED GROOVE TONGUE AND RUBBER GASKET TYPE JOINTS.
- 16. ALL ABANDONED SANITARY SEWERS SHALL BE PLUGGED AT BOTH ENDS WITH AT LEAST 2 FEET LONG NON-SHRINK CONCRETE OR MORTAR PLUG.
- 17. EXCEPT FOR FOUNDATION/FOOTING DRAINS PROVIDED TO PROTECT BUILDINGS, OR PERFORATED PIPES ASSOCIATED WITH VOLUME CONTROL FACILITIES, DRAIN TILES/FIELD TILES/UNDERDRAINS/PERFORATED PIPES ARE NOT ALLOWED TO BE CONNECTED TO OR TRIBUTARY TO COMBINED SEWERS, SANITARY SEWERS, OR STORM SEWERS TRIBUTARY TO COMBINED SEWERS IN COMBINED SEWER AREAS.
 CONSTRUCTION OF NEW FACILITIES OF THIS TYPE IS PROHIBITED; AND ALL EXISTING DRAIN TILES AND PERFORATED PIPES ENCOUNTERED WITHIN THE PROJECT AREA SHALL BE PLUGGED OR REMOVED, AND SHALL NOT BE CONNECTED TO COMBINED SEWERS, SANITARY SEWERS, OR STORM SEWERS TRIBUTARY
- 18. A BACKFLOW PREVENTER IS REQUIRED FOR ALL DETENTION BASINS TRIBUTARY TO COMBINED SEWERS. . A BACKFLOW PREVENTIER IS REQUIRED FOR ALL DETENTION DASINS TRIBUTARY TO COMBINED SEWERS. REQUIRED BACKFLOW PREVENTERS SHALL BE INSPECTED AND EXERCISED ANNUALTY THE PROPERTY OWNER TO ENSURE PROPER OPERATION, AND ANY NECESSARY MAINTENANCES SHALL BE PERPORMED TO ENSURE FUNCTIONALTY. IN THE EVENT OF A SEWER SURCHARGE INTO AN OPEN DETENTION BASIN TRIBUTARY TO COMBINED SEWERS, THE PERMITTEE SHALL ENSURE THAT CLEAN UP AND WASH OUT OF SEWAGE TAKES PLACE WITHIN 48 HOURS OF THE STORM EVENT.

E. EROSION AND SEDIMENT CONTROL

- 1. THE CONTRACTOR SHALL INSTALL THE EROSION AND SEDIMENT CONTROL DEVICES AS SHOWN ON THE APPROVED EROSION AND SEDIMENT CONTROL PLAN.
- EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE FUNCTIONAL PRIOR TO HYDROLOGIC DISTURBANCE OF THE SITE.
- 3. ALL DESIGN CRITERIA, SPECIFICATIONS, AND INSTALLATION OF EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE IN ACCORDANCE WITH THE ILLINOIS URBAN MANUAL.
- 4. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE
- 5. INSPECTIONS AND DOCUMENTATION SHALL BE PERFORMED, AT A MINIMUM
- a) UPON COMPLETION OF INITIAL EROSION AND SEDIMENT CONTROL MEASURES, PRIOR TO ANY b) ONCE EVERY SEVEN (7) CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM EVENT WITH GREATER THAN 0.5 INCH OF RAINFALL OR LIQUID EQUIVALENT PRECIPITATION.
- 6. SOIL DISTURBANCE SHALL BE CONDUCTED IN SUCH A MANNER AS TO MINIMIZE EROSION. IF STRIPPING, CLEARING, GRADING, OR LANDSCAPING ARE TO BE DONE IN PHASES, THE CO-PERMITTEE SHALL PLAN FOR APPROPRIATE SOIL EROSION AND SEDIMENT CONTROL MEASURES.
- 7. A STABILIZED MAT OF CRUSHED STONE MEETING THE STANDARDS OF THE ILLINOIS URBAN MANUAL SHALL BE INSTALLED AT ANY POINT WHERE TRAFFIC WILL BE ENTERING OR LEAVING A CONSTRUCTION SITE. SEDIMENT OR SOIL REACHING AN IMPROVED PUBLIC RIGHT-OF-WAY, STREET, ALLEY OR PARKING AREA SHALL BE REMOVED BY SCRAPING OR STREET CLEANING AS ACCUMULATIONS WARRANT AND
- Transported to a controlled sediment disposal area. 8. CONCRETE WASHOUT FACILITIES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ILLINOIS URBAN MANUAL AND SHALL BE INSTALLED PRIOR TO ANY ON SITE CONSTRUCTION ACTIVITIES INVOLVING
- MORTAR WASHOUT FACILITIES SHALL BE CONSTRUCTED IN ADDITION TO CONCRETE WASHOUT
 FACILITIES FOR ANY BRICK AND MORTAR BUILDING ENVELOPE CONSTRUCTION ACTIVITIES.
- 10. TEMPORARY DIVERSIONS SHALL BE CONSTRUCTED AS NECESSARY TO DIRECT ALL RUNOFF FROM HYDROLOGICALLY DISTURBED AREAS TO AN APPROPRIATE SEDIMENT TRAP OR BASIN. VOLUME CONTROL FACILITIES SHALL NOT BE USED AS TEMPORARY SEDIMENT BASINS.
- 12. DISTURBED AREAS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED SHALL BE STABILIZED WITH TEMPORARY OR PERMANENT MEASURES WITHIN
- 13. ALL FLOOD PROTECTION AREAS AND VOLUME CONTROL FACILITIES SHALL, AT A MINIMUM, BE PROTECTED WITH A DOUBLE-ROW OF SILT FENCE (OR EQUIVALENT).
- 14. VOLUME CONTROL FACILITIES SHALL NOT BE CONSTRUCTED UNTIL ALL OF THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED.
- 15. SOIL STOCKPILES SHALL, AT A MINIMUM, BE PROTECTED WITH PERIMETER SEDIMENT CONTROLS. SOIL STOCKPILES SHALL NOT BE PLACED IN FLOOD PROTECTION AREAS OR THEIR BUFFERS.
- 16. EARTHEN EMBANKMENT SIDE SLOPES SHALL BE STABILIZED WITH APPROPRIATE EROSION CONTROL
- 17. STORM SEWERS THAT ARE OR WILL BE FUNCTIONING DURING CONSTRUCTION SHALL BE PROTECTED BY APPROPRIATE SEDIMENT CONTROL MEASURES.
- 18. THE CONTRACTOR SHALL EITHER REMOVE OR REPLACE ANY EXISTING DRAIN TILES AND INCORPORATE THEM INTO THE DRAINAGE PLAN FOR THE DEVELOPMENT. DRAIN TILES CANNOT BE TRIBUTARY TO A SANITARY OR COMBINED SEWER. DRAIN TILES ALLOWED IN COMBINED SEWER AREA FOR GREEN INFRASTRUCTURE PRACTICES.
- 19. IF DEWATERING SERVICES ARE USED, ADJOINING PROPERTIES AND DISCHARGE LOCATIONS SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION. DEWATERING SYSTEMS SHOULD BE INSPECTED DAILY DURING OPERATIONAL PERIODS. THE SITE INSPECTOR MUST BE PRESENT AT THE COMMENCEMENT OF DEWATERING ACTIVITIES.
- 20. THE CONTRCTOR SHALL BE RESPONSIBLE FOR TRENCH DEWATERING AND EXCAVATION FOR THE INSTALLATION OF SANITARY SEWERS, STORM SEWERS, WATERMAINS AS WELL AS THEIR SERVICES AND OTHER APPURTENANCES. ANY TRENCH DEWATERING, WHICH CONTAINS SEDIMENT SHALL PASS THROUGH A SEDIMENT SETLING POND OR EQUALLY EFFECTIVE SEDIMENT CONTROL DEVICE.

 ALTERNATIVES MAY INCLUDE DEWATERING INTO A SUMP PIT, FILTER BAG OR EXISTING VEGETATED LIDER OF A DEAD RATE OF THE PROPERTY OF THE PR UPSLOPE AREA. SEDIMENT LADEN WATERS SHALL NOT BE DISCHARGE TO WATERWAYS, FLOOD PROTECTION AREAS OR THE COMBINED SEWER SYSTEM
- 21. ALL PERMANENT EROSION CONTROL PRACTICES SHALL BE INITIATED WITHIN SEVEN (7) DAYS FOLLOWING THE COMPLETION OF SOIL DISTURBING ACTIVITIES.
- 22. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED AND REPAIRED AS NEEDED ON A YEAR-ROUND BASIS DURING CONSTRUCTION AND ANY PERIODS OF CONSTRUCTION SHUTDOWN UNTIL PERMANENT STABILIZATION IS ACHIEVED
- 23. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN THIRTY (30) DAYS AFTER PERMANENT SITE STABILIZATION.
- 24. THE EROSION AND SEDIMENT CONTROL MEASURES SHOWN ON THE PLANS ARE THE MINIMUM REQUIREMENTS. ADDITIONAL MEASURES MAY BE REQUIRED, AS DIRECTED BY THE ENGINEER, SITE INSPECTOR, OR MWRD.
- 25. CONTRACTOR SHALL PROVIDE WATER MANAGEMENT PLAN FOR REVIEW THAT WILL ADDRESS PLANNED APPROACH DURING CONSTRUCTION.







THORN DITCH FLOOD MITIGATION PROJECT STORM WATER POLLUTION PREVENTION NOTES

VILLAGE of **SOUTH HOLLAND**

SHEET NO. 25 of 71





4 ₹ FILTER FABRIC COARSE AGGREGATE SECTION A-A B-PLAN VIEW Α--MOUNTABLE BERM REINFORCED CONCRETE SIDE ELEVATION SECTION B-E NOTES:

1. FILTE FABRIC SHALL MEET THE REQUIREMENTS OF MATERIAL SPECIFICATION 592 GEOTEXTILE, TABLE I OR 2,
1. FILTER FABRIC SHALL MEET THE REQUIREMENTS OF MATERIAL SPECIFICATION 592 GEOTEXTILE, TABLE I OR 2,
1. FILES 1, 11 OP 117 AND SHALL BE FLACED OVER THE CLEARED AREA PROPER TO THE PLACING OF ROOK,
2. FILES FELLOWER SHALL SH MANUFACTURERS SPECIFICATIONS.

4. IF WASH RACKS ARE USED THEY SHALL BE INSTALLED ACCORDING TO THE MANUFACTURER'S SPECIFICATIONS. STABILIZED CONSTRUCTION ENTRANCE PLAN
NOT TO SCALE NRCS IL-630

PAID AS STABILIZED CONSTRUCTION ENTRANCE

6" Wire Staple or Sandbag -PLAN VIEW Liner Anchor STRAW BALE ANCHOR SECTIONS CONCRET WASHOUT AREA _ 4"x4"x6' Wood Post o 6' Steel Post Min. SIGN DETAIL Maintaining temporary concrete washout facilities shall include removing and disposing of hardened concrete and/or slurry and returning the facilities to a 3. Each straw bale is to be staked in place using (2) 2"x2"x4' wooden stakes 4. The concrete washout facility is intended for concrete, masonry and slurry. TEMPORARY CONCRETE AND BALE

10' Min 0000000

NOT MEASURED FOR PAYMENT

STORM WATER POLLUTION PREVENTION **EROSION CONTROLS AND SEDIMENT CONTROLS**

DESCRIPTION OF STABILIZATION PRACTICES AT THE BEGINNING OF CONSTRUCTION (WHERE V.

- 1) THE AREA BETWEEN THE EXISTING AND PROPOSED RIGHT-OF-WAY/TEMPORARY EASEMENT BOUNDARIES AND LIMITS OF THE PROJECT WILL BE IMPROVED AND MANAGED FOR THE PURPOSES OF CONTROLLING EROSION WITHIN THE AREA, REDUCING WATER FLOW BY TEMPORARY DIVERSION AND MINIMIZING SILTATION INTO THE CONSTRUCTION ZONE, AND ESTABLISHING VEGETATIVE COVER WHICH WILL BECOME PERMANENT VEGETATION AND ACT AS AN EROSION BARRIER. WORK AT THE BEGINNING OF CONSTRUCTION WILL CONSIST
- A) AREAS OF EXISTING VEGETATION (WOODS AND GRASSLANDS) OUTSIDE THE PROPOSED CONSTRUCTION SLOPE LIMITS SHALL BE IDENTIFIED FOR PRESERVING AND SHALL BE PROTECTED FROM MOWING, BRUSH CUTTING, TREE REMOVAL AND OTHER ACTIVITIES WHICH WOULD BE DETRIMENTAL TO THEIR MAINTENANCE AND DEVELOPMENT.
- B) DEAD, DISEASED, OR UNSUITABLE VEGETATION WITHIN THE SITE SHALL BE REMOVED AS DIRECTED BY THE ENGINEER, ALONG WITH REQUIRED TREE REMOVAL.
- AS SOON AS REASONABLE ACCESS IS AVAILABLE (SUCH AS TREES CLEARED) TO ALL LOCATIONS WHERE DITCH CHECKS ANDIOR EROSION CONTROL FENCE SHALL BE INSTALLED AS CALLED OUT IN THE PLAN AND DIRECTED BY THE ENGINEER.
- BARE AND SPARSELY VEGETATED GROUND IN HIGHLY ERODABLE AREAS AS DETERMINED BY THE ENGINEER SHALL BE TEMPORARILY SEEDED AT THE BEGINNING OF CONSTRUCTION WHERE NO CONSTRUCTION ACTIVITIES ARE IMMEDIATELY EXPECTED AS STATED IN THE SPECIAL PROVISION "TEMPORARY EROSION
- E) IMMEDIATELY AFTER TREE REMOVAL IS COMPLETED IN CERTAIN AREAS WHICH ARE HIGHLY ERODABLE AREAS AS DETERMINED BY THE ENGINEER THE AREAS SHALL BE TEMPORARILY SEEDED WHERE NO CONSTRUCTION ACTIVITIES ARE IMMEDIATELY EXPECTED AS STATED IN THE SPECIAL PROV TEMPORARY EROSION CONTROL SEEDING."
- AT LOCATIONS WHERE A SIGNIFICANT AMOUNT OF WATER DRAINING INTO THE CONSTRUCTION ZONE, RIP RAP DITCH CHECKS WILL BE UTILIZED TO LOCALLY DIVERT WATER, REDUCE FLOW RATES, AND COLLECT OUTSIDE SILTATION INSIDE THE RIGHT-OWAY LINE. EROSION CONTROL ITEMS WILL NOT BE ALLOWED TO BE INSTALLED TO CAUSE FLOODING TO UPSTREAM PRIVATE PROPERTY WHICH COULD CAUSE CROP DAMAGES OR OTHER UNDESIRABLE CONDITIONS.
- G) AT LOCATIONS WHERE WATER DRAINS AWAY FROM THE PROJECT, SEDIMENT BASINS, RIP RAP DITCH CHECKS, TEMPORARY EROSION CONTROL FENCE, OR TEMPORARY DITCH CHECKS SHALL BE USED.
- 2) ESTABLISHMENT OF THESE TEMPORARY EROSION CONTROL MEASURES WILL HAVE ADDITIONAL BENEFITS TO THE PROJECT. DESIRABLE GRASS SEED WILL BECOME ESTABLISHED IN THESE AREAS AND WILL SPREAD SEEDS ONTO THE CONSTRUCTION SITE UNTIL PERMANENT SEEDING/MOWING AND OVERSEEDING CAN BE
- A THIRD PARTY BENEFIT OF THESE FILTER AREAS IS THAT THEY WILL BEGIN TO PROVIDE A SCREEN AND BUFFER. THEY WILL HELP PROTECT THE CONSTRUCTION SITE FROM WINDS AND EXCESS SUN AND MITIGATE CONSTRUCTION NOISE AND DUST.

$\underline{\text{DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION (WHERE APPLICABLE):}}$

- DURING ROADWAY CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION SLOPE LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE PROTECTED FROM DAMAGING EFFECTS OF CONSTRUCTION. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESIGNATED ON THE PLANS OR DIRECTED BY THE ENGINEER). PARKING OF VEHICLES OR CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION RELATED ACTIVITIES.
- WITHIN THE CONSTRUCTION ZONE, CRITICAL AREAS WHICH HAVE HIGH FLOWS OF WATER AS DETERMINED BY
 THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSION.
- TOP SOIL AND EARTH STOCKPILES SHALL BE TEMPORARILY SEEDED IF THEY ARE TO REMAIN UNUSED FOR MORE THAN FOURTEEN DAYS.
- AS THE CONTRACTOR CONSTRUCTS A PORTION OF THE ROADWAY IN A FILL SECTION, HE/SHE SHALL FOLLOW THE FOLLOWING STEPS AS DIRECTED BY THE ENGINEER:
- PLACE TEMPORARY EROSION CONTROL SYSTEMS AT LOCATIONS WHERE WATER LEAVES AND ENTERS THE CONSTRUCTION ZONE.
- TEMPORARY SEED HIGHLY ERODABLE AREAS OUTSIDE THE CONSTRUCTION ZONE SLOPE LIMITS

DATE

SCALE

= 05-06-2025

PROJECT NO = 23-R0646

FILE NAME = 23R0646-SWPP-01

- CONSTRUCT ROADSIDE DITCHES AND PROVIDE TEMPORARY EROSION CONTROL SYSTEMS
- TEMPORARY DIVERT WATER AROUND PROPOSED CULVERT LOCATION

SHAPING TO THE SLOPES.

- BUILD NECESSARY EMBANKMENT AT CULVERT LOCATIONS AND THEN EXCAVATE AND PLACE CULVERT. CONTINUE BUILDING UP THE EMBANKMENT TO THE PROPOSED GRADE WHILE AT THE SAME TIME PLACING PERMANENT EROSION CONTROL SUCH AS RIP RAP DITCH LINING AND CONDUCT FINAL
- D) THE CONTRACTOR SHALL IMMEDIATELY FOLLOW MAJOR EARTH MOVING OPERATIONS WITH FINAL GRADING EQUIPMENT. AFTER MAJOR EARTH SPREAD OPERATION HAS MOVED TO A NEW LOCATION, FINAL GRADING SHALL BE COMPLETED WITHIN FOURTEEN DAYS. IF GRADING IS NOT COMPLETED WITH GRADING SPALL BE COMPLETED WITHIN FORTERN DATA. IF GRADING IS NOT COMPLETED WITHIN FOURTEEN DATA.
 FOURTEEN DAYS, ALL MAJOR EARTH MOVING OPERATIONS WILL BE STOPPED, AS DIRECTED BY THE ENGINEER, UNTIL DISTURBED AREAS ARE FINAL GRADED AND SEEDED.
- E) EXCAVATED AREAS AND EMBANKMENTS SHALL BE PERMANENTLY SEEDED WHEN FINAL GRADED. IF NOT, THEY SHALL BE TEMPORARILY SEEDED AS STATED IN THE SPECIAL PROVISION "TEMPORARY EROSION CONTROL SEEDING."
- F) CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS. ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLLUTION RUN-OFF IN COMPLIANCE WITH EPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE.
- THE RESIDENT ENGINEER SHALL INPSECT THE PROJECT DAILY DURING ACTIVITIES AND WEEKLY OR AFTER LARGE RAINS DURING THE WINTER SHUTDOWN PERIOD. THIS PROJECT SHALL ADDITIONALLY BE JANUE MINIS DIMINIO THE WITTER SHOT DOWN FERIOR. THIS PROJECT STALL AUDITIONALL I BE NEPECTED BY THE CONSTRUCTION FIELD ENGINEER ON A BIWEEKLY BASIS TO DETERMINE THA EROSION CONTROL EFFORTS ARE IN PLACE AND EFFECTIVE AND IF OTHER CONTROL WORK IS
- H) SEDIMENT COLLECTED DURING CONSTRUCTION BY THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS
 SHALL BE DISPOSED OF ON SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF
 MAINTENANCE WILL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04 OF THE STANDARD
- THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COSTS OF THIS REMOVAL SHALL BE INCLUDED IN THE UNIT BID PRICE FOR THE TEMPORARY EROSION CONTROL SYSTEM. NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

DOCUMENTATION

DESIGNED - MGP

CHECKED — JDH

CHECKED - AG

RAWN

- 1) A REPORT SUMMARIZING THE SCOPE OF INSPECTION, NAME(S) AND QUALIFICATIONS OF PERSONNEL MAKING THE INSPECTION, DATE(S) OF THE INSPECTION, MAJOR OBSERVATIONS RELATING TO THE IMPLEMENTATION OF THIS STORM WATER POLLUTION PREVENTION PLAN. AND ACTION TAKEN IN ACCORDANCE WITH SECTION 4. B. SHALL BE MADE AND RETAINED AS PART OF THE PLAN FOR AT LEAST THREE YEARS AFTER THE DATE OF INSPECTION. THE REPORT SHALL BE SIGNED IN ACCORDANCE WITH PART VI. G. OF THE GENERAL PERMIT
- IF ANY VIOLATION OF THE PROVISIONS OF THIS PLAN IS IDENTIFIED DURING THE CONDUCT OF THE CONSTRUCTION WORK COVERED BY THIS PLAN, THE RESIDENT ENGINEER OR RESIDENT TECHNICIAN SHALL COMPLETE AND FILE AN "INCIDENT OF NONCOMPLANCE ((ION)" REPORT FOR THE IDENTIFIED VIOLATION. THE RESIDENT ENGINEER OR RESIDENT TECHNICIAN SHALL USE FORMS PROVIDED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY AND SHALL INCLUDE SPECIFIC INFORMATION ON THE VANCAUMI MAKES ACTIONS MAKED HAVE AND ALLING AND NONCOMPLIANCE, ACTIONS WHICH WERE TAKEN TO PREVENT ANY FURTHER CAUSES OF NONCOMPLIANCE, AND A STATEMENT DETAILING ANY ENVIRONMENTAL IMPACT WHICH MAY HAVE RESULTED FROM THE NONCOMPLIANCE. ALL REPORTS OF NONCOMPLIANCE SHALL BE SIGNED BY A RESPONSIBLE AUTHORITY IN ACCORDANCE WITH PART VI. G. OF THE GENERAL PERMIT. THE REPORT OF NONCOMPLIANCE SHALL BE MAILED TO THE FOLLOWING ADDRESS:

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY DIVISION OF WATER POLLUTION CONTROL COMPLIANCE ASSURANCE SECTION #19 POST OFFICE BOX 19276 SPRINGFIELD, IL 62794-9276

DESCRIPTION OF INTENDED SEQUENCE OF MAJOR CONSTRUCTION ACTIVITIES WHICH WILL DISTURB EARTH AND LEAD TO POSSIBLE EROSION FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE:

- 1) EXCAVATION AND FURNISHED EXCAVATION WILL BE COMPLETED AT LOCATION AS INDICATED ON THE PLANS OR DIRECTED BY THE ENGINEER.
- DRAINAGE STRUCTURES WILL BE INSTALLED BEFORE AND/OR DURING THE CONSTRUCTION OF THE EXCAVATION AND FURNISHED EXCAVATION TO ALLOW PROPER DRAINAGE IN AREA OF THE PROPOSED ROADWAY FACILITY

REVISED

REVISED

REVISED

REVISED

- 3) PLACEMENT, MAINTENANCE, REMOVAL AND PROPER CLEANUP OF TEMPORARY EROSION CONTROL, SUCH AS EROSION CONTROL FENCE, HAY OR STRAW BALE DITCH CHECKS, RIP RAP DITCH CHECKS, TEMPORARY
- 4) PLACEMENT OF PERMANENT EROSION CONTROL, SUCH AS RIP RAP DITCH LINING, FILTER FABRIC FOR USE WITH RIP RAP, SEEDING AND MULCHING.
- 5) FINAL GRADING, AND OTHER MISCELLANEOUS ITEMS. USE WITH RIP RAP, SEEDING AND MULCHING

AREA OF DISTURBED GROUND

THE TOTAL AREA DISTURBED BY CONSTRUCTION ACTIVITIES IS APPROXIMATELY 4.78 ACRES.

THE FOLLOWING PLAN WAS ESTABLISHED AND INCLUDED IN THESE PLANS TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE UNDER NPDES. THE CONTRACTOR SHALL ABIDE TO ALL REQUIREMENTS WITHIN THIS PLAN AS PART OF THE CONTRACT.


ALL DISTURBED AREAS HAVING HIGH POTENTIAL FOR EROSION. AS DETERMINED BY THE ENGINEER. SHALL BE PERMANENTLY SEEDED AS SOON AS POSSIBLE.

DESCRIPTION OF STABILIZATION PRACTICES AFTER FINAL GRADING (WHERE APPLICABLE):

- 1) TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS SEEDED AND ESTABLISHED WITH A PROPER STAND.
- 2) ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RESEEDED. TEMPORARY RIP RAP DITCH CHECKS WILL BE ALLOWED TO REMAIN IN PLACE WHERE APPROVED BY THE

MAINTENANCE AFTER CONSTRUCTION (WHERE APPLICABLE):

- 1) CONSTRUCTION IS COMPLETE AFTER ACCEPTANCE IS RECEIVED AT THE FINAL INSPECTION.
- 2) AREAS WILL BE INSPECTED ON A REGULAR BASIS BY THE CONTRACTOR
- 4) MAINTENANCE CREWS WILL ALSO AID IN ANY DITCH LINING MAINTENANCE OR IN ANY DRAINAGE PROBLEMS
- 5) ALL MAINTENANCE WILL BE CONDUCTED AT TIMES WHEN WEATHER CONDITIONS WILL NOT CAUSE SITE
- CONTRACTOR SHALL COMPLY WITH ALL TERMS AND CONDITIONS OF IEPA NPDES PERMIT ILR 10. RESTORATION SHALL OCCUR WITHIN 7 DAYS OF DISTURBANCE.
- CONTRACTOR SHALL SUBMIT INSPECTION REPORTS TO THE **VILLAGE** AT LEAST ONCE PER SEVEN DAYS AND AFTER RAINFALL EVENTS OF A HALF INCH (OR EQUIVALENT SNOW FALL).
- CONSTRUCTION SHALL NOT COMMENCE UNTIL THE NOI IS SUBMITTED AND THE IEPA ISSUES AN EFFECTIVE DATE. THE CONSTRUCTION SCHEDULE SHOULD BE COGNIZANT OF THE IEPA REVIEW SCHEDULE
- 10) THE CONTRACTOR IS RESPONSIBLE FOR HAVING THE SWPPP ON SITE AT ALL TIMES
- 11) A NOTICE OF TERMINATION SHALL BE COMPLETED BY THE OWNER WHEN ALL PERMANENT EROSION CONTROL MEASURES ARE IN PLACE WITH A 70% ESTABLISHMENT RATE OF VEGETATION. THE NOT SHALL BE SENT TO THE IEPA AND THE VILLAGE.
- 12) TECHNIQUES SHALL BE EMPLOYED BY THE CONTRACTOR TO PREVENT THE BLOWING OF DUST OR SEDIMENT
- 13) DAILY REMOVAL OF SEDIMENT AND DEBRIS FROM ALL ROADS SHALL BE REQUIRED OF THE CONTRACTOR.




PAID AS PERIMETER EROSION BARRIER



THORN DITCH FLOOD MITIGATION PROJECT STORM WATER POLLUTION PREVENTION DETAILS

VILLAGE of SOUTH HOLLAND

SHEET NO. 26 of 71



GENERAL NOTES

- 1. Reinforcement bars designated (E) shall be epoxy coated.
- 2. Concrete Sealer shall be applied to the top, front and sides of the abutments.
- 3. No field welding is permitted except as specified in the contract documents.
- 4. All structural steel shall be AASHTO M270 Grade 50.
- 5. Plan dimensions and details relative to the existing structure have been taken from field measurements. The contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope, however, the Contractor shall be paid for the quantity actually furnished at the unit price bid for the work.

SUGGESTED CONSTRUCTION SEQUENCE

- 1. Perform construction of new abutments.
- Close pedestrian path to traffic.
- 3. Remove and Relocate Pedestrian Truss onto new abutments.
- 4. Remove existing abutments.
- 5. Open relocated pedestrian truss to traffic.

SECTION THRU ABUTMENT

- * Backfill remainder of structure excavation and over excavation with same material specified for roadway embankment.
- ** Final anchor bolt location and backwall height to be verified by the contractor.

INDEX OF DRAWINGS


- 1. General Plan and Elevation
- 2. General Data
- 3. Abutment Details
- 4. Soil Boring Logs 1
- . Soil Boring Logs 2

TOTAL BILL OF MATERIAL

Item	Unit	Total
Structure Excavation	Cu. Yd.	62
Concrete Structures	Cu. Yd.	12.4
Reinforcement Bars, Epoxy Coated	Pound	1,160
Granular Backfill for Structures	Cu. Yd.	4
Concrete Sealer	Sq. Ft.	166
Removal and Relocation of Existing Pedestrian Bridge	L Sum	1
Removal of Existing Structures	L Sum	1
Wood Decking Special	Sq. Ft.	210

BRIDGE REACTION TABLE

Item	P (lbs) Brg.	H (lbs) Abutment.	L (lbs)
Dead Load	1,900	-	-
Uni. Live Load	4,725	-	-
Vehicle Load	4,600	-	-
Uplift Wind (20 psf)	-273	-	-
Wind	±777	1,095	-
Thermal	-	-	285



All footings have been designed based on the bridge reactions shown

"P" Vertical Load Per Base Plate

"H" Horizontal Load Per Footing

"L" Longitudinal Load Per Base Plate

Bridge Lifting Weight: ±7,600 LBS

Unfactored bridge reactions table information is for reference only.

Anchor bolt sizes, layout and locations are shown for general reference. Contractor shall be responsible for final anchor bolt sizes, layouts and locations with dimensioned referenced to abutment backwall and abutment centerline.


DRAWING 2 OF 5

TRANSYSTEMS


THORN DITCH
DRAINAGE IMPROVEMENTS
WEST PEDESTRIAN BRIDGE - GENERAL DATA

VILLAGE of SOUTH HOLLAND


SHEET NO. 28 of 71




TYPICAL ABUTMENT ELEVATION




TYPICAL ABUTMENT PLAN




TYPICAL ABUTMENT SECTION



JOINT SEAL AT ABUTMENT



DOWEL BAR n(E)



ANCHOR BOLT DETAIL

*The existing anchor bolts are buried and could not be verified. Contractor to match existing anchor bolt pattern and diameter and submit to the engineer for approval of size and embedment depth for new anchor bolts.

BILL OF MATERIAL

	(P	'er Abut	ment)	
Bar	No.	Size	Length	Shape
h(E)	14	#5	8'-2"	
n(E)	18	#5	5'-2"	
s(E)	9	#5	6'-1"	
t(E)	18	#5	5'-11"	
(E)	1.0			
v(E)	18	#5	4'-0"	
w(E)	14	# 5	וור ווי	
W(E)	14	#5	8'-2"	
Concre	te Stru	ctures	Cu. Yd.	6.2
	rcemeni Coated	Bars,	Pound	580

DRAWING 3 OF 5

	DATE = 5/5/2025	DESIGNED - MJS	REVISED -	,	THORN DITCH	VILLAGE	OUEET NO
	SCALE = 2.000'/in.	CHECKED - OS	REVISED -	TR ∕ ENSYSTEMS	DRAINAGE IMPROVEMENTS	of cf	SHEET NO.
	PROJECT NO = 23-R0646	DRAWN - MJS	REVISED -	IK/KINOTOTEMO		01	29 of 71
LAST SAVED BY: omshaban PLOTTED BY: omshaban	FILE NAME = THORN_DITCH_PB1_003	CHECKED - MDS	REVISED -		WEST PEDESTRIAN BRIDGE - ABUTMENT DETAILS	SOUTH HOLLAND	

			ngineering, Ltd. 24-G0400				ME Thorn		Hollan	d II					
	COMPL						THOD _3.2			u, 12					
								â	On)					ERBE	
O DEPTH (ft)	ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)	LIQUID	PLASTIC LIMIT	PL ASTICITY
-	594.7	1. 1/2 L	6" TOPSOIL												Т
-	592.2		black and dark brown CLAY (FILL) trace gravel very stiff	X	ss 1	89	3-3-4 (7)	3.0		18.1					
	002.2		brown and gray LEAN CLAY trace silt very stiff	M	SS 2	100	2-4-5	2.0	2.2	21.5					
5				/\	2		(9)								
-				X	SS 3	100	3-5-6 (11)	2.25	2.4	23.8					
10				X	SS 4	100	3-3-4 (7)	3.75	3.7	26.8					
-	584.2		gray LEAN CLAY stiff to hard	X	SS 5	100	3-3-5 (8)	2.25	2.4	27.7					
15			moist in SS6	X	SS 6	100	4-5-10 (15)	3.5	3.4	19.9					
-				X	ss 7	100	2-3-4 (7)	1.25	1.4	19.8					
20				X	SS 8	100	2-6-4 (10)	2.5	2.5	20.1					
СОМР	DEPTH		GROUND ELEVATION Soil Cuttings			TES A 18+0	01.04 Off	set 17.	3 LT						
∇		OF DR	VELS: SILLING 38.00 ft / Elev 557.20 ft ILLING 38.00 ft / Elev 557.20 ft				ater levels the groun				-	-		y not	

			ngineering, Ltd. 24-G0400	PROJECT NAME Thorn Ditch PROJECT LOCATION South Holland, IL										
DATE	COMPL	ETED _	4/16/24 LOGGED BY TW/KE	DRILLII	NG ME	THOD 3.2	25 in. F	ISA						
OEPTH (#)	ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)	LIQUID	PLASTIC LIMIT LIMIT	PLASTICITY B
			gray LEAN CLAY stiff to hard <i>(continued)</i>	SS 9	100	4-3-7 (10)	3.0	3.1	18.8					
25				SS 10	100	7-9-13 (22)	4.5+	8.5	14.4					
				SS 11	100	6-9-15 (24)	4.5+	10.0	13.5					
30	562.2			SS 12	100	6-8-12 (20)	4.5+	9.6	13.6					
35			GRAVEL or POSSIBLE WEATHERED LIMESTONE very dense, wet poor recovery	SS 13	100	50/1"	j		5.6					
	556.6		Refusal at 38.6 feet. Bottom of borehole at 38.6 feet.	SS 14	100	50/1"			12.3					

DRAWING 4 OF 5

	DATE = 5/5/2025	DESIGNED - MJS	REVISED -
	SCALE = 2.000 ' / in.	CHECKED - OS	REVISED -
	PROJECT NO = 23-R0646	DRAWN - MJS	REVISED -
VED BY: omshaban D BY: omshaban	FILE NAME = THORN_DITCH_PB1_004	CHECKED - OS	REVISED -

TRANSYSTEMS

			EOCON FESSIONAL SERVICES						ВС	PRII	NG	. PE	
CLIEN	IT Robii	nson Er	ngineering, Ltd.	PR	OJECT N	IAME Thor	n Ditch						
PROJ	ECT NUM	/IBER	24-G0400	PR	OJECT L	OCATION _	South	Hollan	d, IL				
DATE	COMPLI	ETED _	4/17/24 LOGGED BY TW/KE	DR	ILLING N	METHOD 3.	25 in. l	ISA					
, DEРТН (ft)	ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	NUMBER RECOVERY %	(RQD) BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)	PLASTIC STIMIT LIMIT	
0	594.6	7.1 1 ₂ - 1	√ 4" TOPSOIL				+						_
			black and dark brown CLAY (FILL) trace gravel stiff	X	SS 44	2-2-2	1.5		16.2				
5	590.9		dark brown SANDY CLAY trace gravel very stiff		SS 44	2-2-3 (5)	2.0		30.8				
 	588.9		brown and gray LEAN CLAY very stiff	X	SS 78	3 2-2-3 (5)	2.0	2.2	27.9				
10				X	SS 4 89	2-2-2 (4)	2.0	2.0	23.9				
				X	SS 94	2-3-3 (6)	2.25	2.2	25.8				
15				X	SS 10	0 3-3-4 (7)	2.0	2.0	21.4				
-	578.9		gray LEAN CLAY very stiff to hard	X	SS 7 10	0 4-4-5 (9)	2.25	2.4	19.9				
20				X	SS 10	0 2-4-5 (9)	2.25	2.4	20.5				
CAVE GROU ∑ ▼	DEPTH JND WAT AT TIME AT END AFTER I	ft ER LEV OF DRI OF DRI	ILLING 16.00 ft / Elev 578.90 ft LLING 16.00 ft / Elev 578.90 ft		Ground represe constru	3+24.11 Of dwater levels ent the groui action.	s were ndwate	record r cond	itions	at the	time o		

			ngineering 24-G0400	Ltd.			ME Thorr		Jollon	4 11				
	COMPL			LOGGED BY TW/KE			THOD 3.2			u, IL				
DEPTH (ft)	ELEVATION (ft.)	GRAPHIC LOG		MATERIAL DESCRIPTION	SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)	PLASTIC IIMIT	
20 _				AN CLAY ff to hard <i>(continued)</i>	SS 9	100	5-6-8 (14)	4.5+	5.1	16.2				
					SS 10	100	5-8-10 (18)	4.0	4.4	17.7				
-					SS 11	100	5-9-16 (25)	4.5+	7.8	14.7				
30	561.9				SS 12	100	4-11-16 (27)	4.5+	6.6	15.6				
35	558.9		gray S/ with gra stiff, we	NNDY CLAY avel st	≥ SS 13	40	50/5"	1.0		17.5				
_	557.4		POSSI	BLE WEATHERED LIMESTONE										
				Refusal at 37.5 feet. Bottom of borehole at 37.5 feet.	,									

DRAWING 5 OF 5

	DATE = 5/5/2025	DESIGNED - MJS	REVISED -
	SCALE = 2.000 ' / in.	CHECKED - OS	REVISED -
	PROJECT NO = 23-R0646	DRAWN - MJS	REVISED -
LAST SAVED BY: omshaban PLOTTED BY: omshaban	FILE NAME = THORN_DITCH_PB1_005	CHECKED - OS	REVISED -

TRANSYSTEMS

Bench Mark: Spike nail in west face of power pole on north side of 165th St. at west Residence 944. Elev = 597.33 Existing Structure: No existing structure. Salvage: No salvage. 37'-2" Back-to-Back of Abutments 6'-0" 3'-0" 3'-0'' 35'-2" Face-to-Face of Abutments 35'-0" End-to-End Truss Proposed Gravel Pedestrian Path Top Chord -1" Gap - Pedestrian Truss Superstructure 🕻 Pedestrian Bridge Тур. Diagonal Safety Rail, typ. D.H.W Elev. 595.00 Toe Rail 100 yr. OHWM Limits Plank Support -Vertical Ex. Easement, typ.--Wood Deck Streambed Typ. Elev. 588.01 Btm./Ftg Btm./Ftg. 6'-3" Elev. 588.50 Bottom Chord -Тур. - Ex. Groundline 段 Thorn Ditch-Steel Stringer └ Diagonal Floor beam BRIDGE CROSS SECTION **ELEVATION** (Looking West) Bridge cross section is for reference only. Truss Manufacturer is responsible — Edge of Ex. Gravel Path for final design, dimensions and details. Wood deck shall be preservative treaded timber that is equivalent to 3x12 Select Structural Douglas Fir, or, 3x10 Southern Yellow Pine. Preservative treatment and fasteners shall comply with Article 1007.12 of the IDOT Standard Specifications. Edge of Ex. Gravel Path OHWM Limits — PB-3 -₽Thorn Ditch SEISMIC DATA LOADING 37'-2" Back-to-Back of Abutments 90 psf Live Load Seismic Performance Zone (SPZ) = 1Design Spectral Acceleration at 1.0 sec. (SD1) = 0.04g 5,000 lb Vehicle Load (Class 1) 1'-71/2" ⊈ Brg. S. Abutment 1'-7½'' € Brg. Design Spectral Acceleration at 0.2 sec. (SDS) = 0.10g N. Abutment Soil Site Class E DESIGN STRESSES <u>E</u> Bridge Bk. N. Abut DESIGN SPECIFICATIONS (FIELD UNITS) Bk. S. Abut î Proposed Station 19+82.52 Sta. 19+82.52 Sta. 19+82.52 f'c = 1,300 psi min. (Wood Deck)Pedestrian Bridge Offset 1.73' Rt. Offset 20.31' Rt Offset 16.85' Lt. 2020 AASHTO LRFD Bridge Design Specifications, 9th Edition f'c = 3,500 psiElev. 595.00 Elev. 595.25 AASHTO Guide Specifications for the Design of fy = 60,000 psi (Reinforcement)Pedestrian Bridges, 2009 $fy = 50,000 \, psi \, (M270 \, Grade \, 50)$ Ex. Easement, typ. Ex. Lightpole, to remain-Range 14E, 3rd P.M. -OHWM Limits Toe of Ex. Thorn Ditch . Toe of Ex. Channel Width Thorn Ditch Varies Proposed-Structure LOCATION SKETCH PEDESTRIAN BRIDGE PROFILE GRADE PLAN DRAWING 1 OF 5 = 5/5/2025 DESIGNED - MJS REVISED -THORN DITCH VILLAGE SHEET NO. **TRANSYSTEMS** CHECKED - OS SCALE = 8.000 ' / in. REVISED -DRAINAGE IMPROVEMENTS οf PROJECT NO = 23-R0646 DRAWN - MJS REVISED -32 of 71

FILE NAME = THORN DITCH PB2 001 CHECKED - OS

REVISED -

EAST PEDESTRIAN BRIDGE - GENERAL PLAN AND ELEVATION

SOUTH HOLLAND

GENERAL NOTES

- 1. Reinforcement bars designated (E) shall be epoxy coated.
- 2. Concrete Sealer shall be applied to the top, front and sides of the abutments.
- 3. No field welding is permitted except as specified in the contract documents.
- 4. All structural steel shall be AASHTO M270 Grade 50.
- 5. Truss shall not use weathering steel, instead, steel shall meet the requirements for AASHTO Grade 50. Fasteners shall be mechanically galvanized high-strength bolts in accordance with the requirements of Article 1006.08(a) of the Standard Specifications. Bolt size shall be determined by Pedestrian Truss Manufacturer.
- 6. Truss and appurtenances shall be painted using a three coat organic zinc rich system that conforms to Section 1008.05 of the Standard Specification. The entire system shall be shop applied with exception of areas to be masked off for connections and/or pick points. Masked off areas and damaged areas shall be touched up in the field. Finish color shall be per owner's selection. A sample of steel truss painted the exact color shall be submitted to the Engineer for approval prior to painting any truss elements. Cost of Painting is included with Pedestrian Truss Superstructure.
- 7. The substructure is designed per the current AASHTO LRFD Bridge Design Specifications and is based on the assumed bridge reactions shown in the table. If the manufacturer's design exceeds those loads and/or the substructure dimensions need to be adjusted to accommodate the truss superstructure chosen, then the Contractor shall submit the redesign to the Engineer for review and approval prior to ordering material or starting construction. The Contractor's responsibility shall include the submittal of shop drawings for the revised reinforcement bar layout and quantities, abutment cap and backwall dimensions, and, if requested, updated design calculations for the foundations signed and sealed by an Illinois Licensed Structural Engineer.
- 8. Bridge bearing seat elevations are subject to revision based on the approved pedestrian truss superstructure shop drawings.
- 9. Design of pedestrian bridge shall accommodate anticipated dead and live load deflections so that the bridge profile matches the PGL in its final position.
- 10. All temporary support systems, cribbing, crane platforms, and other temporary works necessary for the erection of the superstructure shall be included with the cost of Pedestrian Truss Superstructure. Shop drawings for all temporary works shall be submitted to the Engineer for approval.

INDEX OF DRAWINGS

- 1. General Plan and Elevation
- 2. General Data

91...

- 3. Abutment Details
- I. Soil Boring Logs 1
- 5. Soil Boring Logs 2

SUGGESTED CONSTRUCTION SEQUENCE


- Perform construction of new abutments.
- 2. Install Pedestrian Truss Superstructure.
- 3. Open pedestrian truss to traffic.

TOTAL BILL OF MATERIAL

Item	Unit	Total
Structure Excavation	Cu. Yd.	62
Concrete Structures	Cu. Yd.	12.4
Reinforcement Bars, Epoxy Coated	Pound	1,160
Granular Backfill for Structures	Cu. Yd.	4
Concrete Sealer	Sq. Ft.	166
Pedestrian Truss Superstructure	Sq. Ft.	210

BRIDGE REACTION TABLE

Item	P (Ibs) Brg.	H (lbs) Abutment.	L (lbs)
Dead Load	1,900	-	-
Uni. Live Load	4,725	-	-
Vehicle Load	4,600	-	-
Uplift Wind (20 psf)	-273	-	-
Wind	±777	1,095	-
Thermal	-	-	285



All footings have been designed based on the bridge reactions shown

"P" Vertical Load Per Base Plate

"H" Horizontal Load Per Footing

"L" Longitudinal Load Per Base Plate

Bridge Lifting Weight: 7,600 LBS

Unfactored bridge reactions table information is for reference only. Pedestrian Truss manufacturer is responsible for final design loads.

Anchor bolt sizes, layout and locations are shown for general reference. Pedestrian Truss manufacturer shall be responsible for final anchor bolt sizes, layouts and locations with dimensioned referenced to abutment backwall and abutment centerline.

Anchor bolt size general referen responsible for with dimensione

*Over excavation beyond the limits of structure excavation. This area not measured for payment.

*Structure excavation See section 502 of the Standard Specification

*Structure excavation See section 502 of the Standard Specification

- Ex. Groundline

SECTION THRU ABUTMENT

- * Backfill remainder of structure excavation and over excavation with same material specified for roadway embankment.
- ** Final anchor bolt location and backwall height to be verified by pedestrian truss supplier.

DRAWING 2 OF 5


	DATE = 5/5/2025	DESIGNED - MJS	REVISED -
	SCALE = 2.000'/in.	CHECKED - OS	REVISED -
	PROJECT NO = 23-R0646	DRAWN - MJS	REVISED -
LAST SAVED BY: omshaban PLOTTED BY: omshaban	FILE NAME = THORN_DITCH_PB2_002	CHECKED - OS	REVISED -

TRANSYSTEMS

THORN DITCH
DRAINAGE IMPROVEMENTS
EAST PEDESTRIAN BRIDGE - GENERAL DATA

VILLAGE of SOUTH HOLLAND

SHEET NO. 33 of 71




s(E), See Elevation View

v(E) bars, See Elevation View


TYPICAL ABUTMENT PLAN

h(E) bars -


1'-71/2" **€** Bearing Elev. 595.25 (S. Abut., Elev. 595.00 (N. Abut.) h(E) -2 nuts and 1 washer, * typ.-– h(E), typ. 2" typ. Back of Abut. h(E), typ. 1'-0'' 3'-0" v(E) w(E), typ.- $\frac{2^{\prime\prime}}{cI.}$ n(E), typ.— Elev. 588.75 (S. Abut.) Elev. 588.50 (N. Abut.) 7-#5 w(E) bars at 12" Cts. Top and Bott. 6'-3" TYPICAL ABUTMENT SECTION



DOWEL BAR n(E)



ANCHOR BOLT DETAIL *Per Manufacturer Recommendations



JOINT SEAL AT ABUTMENT

BILL OF MATERIAL

	(P	er Abut	ment)	
Bar	No.	Size	Length	Shape
h(E)	14	#5	8'-2"	
n(E)	18	#5	5'-2"	\neg
s(E)	9	#5	6'-1"	
t(E)	18	#5	5'-11"	
v(E)	18	#5	4'-0"	
w(E)	14	#5	8'-2"	
<u> </u>			0 1/1	
	te Stru		Cu. Yd.	6.2
	rcement	Bars,	Pound	580
Epoxy	Coated			

DRAWING 3 OF 5

	DATE = 5/5/2025	DESIGNED - MJS	REVISED -
	SCALE = 2.000'/in.	CHECKED - OS	REVISED -
	PROJECT NO = 23-R0646	DRAWN - MJS	REVISED -
LAST SAVED BY: omshaban PLOTTED BY: omshaban	FILE NAME = THORN_DITCH_PB2_003	CHECKED - MDS	REVISED -

TRANSYSTEMS

THORN DITCH DRAINAGE IMPROVEMENTS EAST PEDESTRIAN BRIDGE - ABUTMENT DETAILS

VILLAGE of SOUTH HOLLAND

SHEET NO. 34 of 71

CLIEN	IT Robin	nson E	ngineering, Ltd.	PR	OJEC	CT NA	ME Thorn	Ditch							
			24-G0400				CATION _			d, IL					_
DATE	COMPLE	ETED .	4/16/24 LOGGED BY TW/KE	DR	ILLIN	IG ME	THOD _3.2	25 in. F	ISA				A T T	ERBE	
DЕРТН (ft)	ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)		PLASTIC LIMIT	
0	594.2	.74 1×. '4	6" TOPSOIL												H
	001.2		black to dark gray CLAY (FILL) very stiff	X	SS 1	72	3-2-3 (5)	3.0		31.1					
5	588.7			X	SS 2	100	2-2-2 (4)	2.0	2.1	37.6					
	586.7		brown and gray LEAN CLAY very stiff	X	SS 3	89	2-2-3 (5)	2.0	2.0	29.8					
10			dark gray LEAN CLAY trace organics stiff	X	SS 4	100	1-1-2 (3)	1.0	1.2	26.3					
· -	583.7		brown and gray LEAN CLAY very stiff to hard	X	SS 5	89	2-2-4 (6)	3.0	2.9	24.5					
15				X	SS 6	89	3-4-6 (10)	4.5+	5.3	20.6					
	578.7		gray LEAN CLAY very stiff to hard	X	ss 7	89	4-4-6 (10)	3.5	3.4	20.4					
				X	SS 8	100	3-3-5 (8)	2.5	2.6	20.4					
CAVE GROU ∑ ▼		ft ER LE OF DF	BACKFILL Soil Cuttings EVELS: RILLING 11.00 ft / Elev 583.70 ft IILLING 18.00 ft / Elev 576.70 ft	7 ft	ST/ Gro	oundw	60.56 Offs ater levels the groun	were	ecord					y not	

	II Robi	nson E	ngineering,	Ltd.	PROJE	CT NA	ME Thorn	Ditch					
PROJ	ECT NUI	MBER	24-G0400		PROJE	CT LO	CATION _	South I	Hollan	d, IL			
DATE	COMPL	ETED _	4/16/24	LOGGED BY TW/KE	DRILLI	NG ME	THOD _3.2	25 in. F	ISA				
DEPTH (ft)	ELEVATION (ft.)	GRAPHIC LOG		MATERIAL DESCRIPTION	SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)	PLASTIC IMIT
				AN CLAY ff to hard <i>(continued)</i>	SS 9	100	3-4-9 (13)	4.0	4.4	17.0			
 25					SS 10	100	3-7-9 (16)	4.5+	5.4	16.7			
 					SS 11	100	7-10-15 (25)	4.5+	8.0	15.3			
30					SS 12	100	6-9-14 (23)	4.5+	7.3	14.3			
	562.7 561.7			BLE WEATHERED LIMESTONE Refusal at 33.0 feet. Bottom of borehole at 33.0 feet.									

DRAWING 4 OF 5

	DATE = 5/5/2025	DESIGNED - MJS	REVISED -
	SCALE = 2.000'/in.	CHECKED - OS	REVISED -
	PROJECT NO = 23-R0646	DRAWN - MJS	REVISED -
LAST SAVED BY: omshaban PLOTTED BY: omshaban	FILE NAME = THORN_DITCH_PB2_004	CHECKED - OS	REVISED -

TRANSYSTEMS

THORN DITCH

DRAINAGE IMPROVEMENTS

EAST PEDESTRIAN BRIDGE - SOIL BORING LOGS 1

VILLAGE of SOUTH HOLLAND


SHEET NO. 35 of 71


AB24-G0400 THOR		PRI	EOCON OFESSIONAL SERVICES							ВС	PRII	NG		. PB ∃ 1 0	
CLIEN	NT Robin	nson E	Engineering, Ltd.	PR	OJE	CT NAI	ME Thorn	Ditch							
PROJ			24-G0400				CATION S			d, IL					
DATE	COMPLI	TED	4/17/24 LOGGED BY TW/KE	DR	DRILLING METHOD										
CLIEN OF THE GOT START 1042 - SCIENCE SOLVER REPLACEMENTS, PRDESTRAN BRIDGES AND DETENTION, THORN DITCH, SOUTH HOLIAND, ILLABEA GOADO OF THORN DITCH, SOUTH DITCH,	ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPI F TYPE	NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)	l	IMITS	
DESTRIAN BRIDGES A	596.2		3" TOPSOIL black and brown CLAY (FILL) trace gravel and roots very stiff to hard		SS 1	67	2-3-4 (7)	2.5		18.3					
PLACEMENTS, PED	591.9		brown and gray LEAN CLAY stiff to hard		SS 2	89	3-4-6 (10)	4.5		24.1					
SGR CULVERT REI				M	SS 3	89	2-3-5 (8)	3.75	3.8	26.1					
-00400 GEO REL 3				X	SS 4	89	2-2-2 (4)	1.5	1.6	24.5					
CHNICAL/2024/24			¥	X	SS 5	100	2-2-3 (5)	2.75	2.8	24.4					
10:42 - K:\(\)GEO18				X	SS 6	100	3-4-6 (10) 3-5-6	4.0	4.1	24.2					
ATE.GDT - 6/18/24	578.4		gray LEAN CLAY stiff to hard	_X	SS 7 SS	100	3-3-0 (11)	4.0	4.3	23.0					
20					8	100	(9)	1.75	1.8	21.4					
COMF CAVE GROU	COMPLETION DEPTH 34.5 ft GROUND ELEVATION 596.4 ft NOTES CAVE DEPTH ft BACKFILL Soil Cuttings STA 19+83.04 Offset 27.0 RT GROUND WATER LEVELS: AT TIME OF DRILLING 13.50 ft / Elev 582.90 ft First State of Coundwater levels were recorded during drilling and may not represent the groundwater conditions at the time of construction.									n.					
PS STANDARD			ation represent an approximate boundary betwee and the transition may be gradual. Dashed lines ar									ervals	and be	etween	


			ngineering, Ltd.			ME Thorr								
	COMPL	_	24-G0400 4/17/24 LOGGED BY TW/KE			CATION _3.2 THOD _3.2			d, IL					
			4/11/24 LOGGLUBI IWIKL		%				# (%)	WT.	ر (%)		TERBE LIMITS	3
DEPTH (#)	ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE NUMBER	RECOVERY (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)	LIQUID	PLASTIC LIMIT	PLASTICITY
20			gray LEAN CLAY stiff to hard <i>(continued)</i>											
			moist in SS9	SS 9	100	3-5-5 (10)	2.0	1.9	20.2					
25				SS 10	100	4-6-9 (15)	4.5+	5.4	16.4	-				
	570.4		gray SILTY CLAY with sand	y ss	100	4-11-17 (28)	3.5		12.3					
	568.4		very stiff gray LEAN CLAY hard	M ss		4-9-11								
30				/ 12	100	(20)	4.5+	9.6	14.0					
	563.4		gray SANDY SILT trace gravel	∠ ss	100	50/5"			7.3					
	561.9	<u> 1471-1</u>	very dense Refusal at 34.5 feet. Bottom of borehole at 34.5 feet.	\ 13										

DRAWING 5 OF 5

	DATE = 5/5/2025	DESIGNED - MJS	REVISED -
	SCALE = 2.000'/in.	CHECKED - OS	REVISED -
	PROJECT NO = 23-R0646	DRAWN - MJS	REVISED -
LAST SAVED BY: omshaban PLOTTED BY: omshaban	FILE NAME = THORN DITCH PB2 005	CHECKED - OS	REVISED -









SECTION THRU PRECAST BOX CULVERT

* Elev. 583.00 (Sta. 22+41.00 to 23+52.00) Elev. 580.00 (Sta. 23+52.00 to 26+63.00) Elev. 583.00 (Sta. 26+63.00 to 29+45.00)




LIMITS OF MEMBRANE WATERPROOFING

Longitudinal limits of membrane waterproofing for the precast concrete culvert are along the full length between headwalls




PAY LIMITS FOR POROUS GRANULAR EMBANKMENT

(Hatched area)




DRAIN DETAIL

(All costs associated with furnishing and constructing the above drain detail will not be measured for payment but shall be included in the contract unit price for the associated work.)



PRECAST CONCRETE RISER
PLAN VIEW



SECTION A-A

GENERAL NOTES

- 1. The design fill height for this box is shown on Section Thru Box Culvert. The precast box culvert sections shall conform to the requirements of ASTM C 1577.
- Drain holes shall be provided on exterior culvert walls for each precast box segment. The drain hole shall be located within 1/3 of the clear rise of the box culvert, shall not intercept the haunch, and shall conform to the requirements of Article 503.11 of the Standard Specification.
- 3. Nonwoven geotextile fabric shall conform to the requirements of Art. 1080.01 of the Standard Specifications. The minimum weight of the fabric shall be 6 ounces per square yard.
- 4. Precast concrete box culverts and box culvert end sections shall be backfilled with Porous Granular Embankment in the required excavation areas on the sides of the box culvert from the top of the box culvert to the bottom of the box culvert. This area of PGE is included in the Porous Granular Embankment pay item. The 6-inch thick layer of porous granular material required under the precast concrete box culvert, according to Section 540.06 of the standard specifications, shall also apply to the end sections. Cost of this porous granular material will not be paid for separately but shall be included in the unit price of the work for which it is required.
- 5. The Rock Fill shall be capped with 6" of CA7 and satisfy the Standard Specifications unless otherwise indicated in the Special Provisions. The cost of the capping material shall be included in the pay item for Rock Fill.
- 6. The limits and quantities of Removal and Replacement of Unsuitable Materials for Structures shown are based on the boring data and may be modified by the Engineer for variable subsurface conditions encountered in the field.
- 7. The contractor shall be responsible to divert the stream flow during construction to keep construction area free of water. The method of the water diversion shall be subject to the approval of the engineer and the cost shall be included in the cost of Precast Concrete Box Culverts, 7'x7'.

CULVERT CONSTRUCTION SEQUENCE

- 1. Close roadway to all traffic.
- 2. Divert water from construction area.
- 3. Perform removal of existing culvert.
- 4. Perform construction of replacement structure.
- 5. Open roadway to traffic.
- 6. Remove water diversion measures.

TOTAL BILL OF MATERIAL

ITEM	UNIT	TOTAL
Earth Excavation	Cu. Yd	4,265
Porous Granular Embankment	Cu. Yd	2,688
Removal of Existing Structures No. 1	Each	1
Structure Excavation	Cu. Yd	2,667
Removal and Disposal of Unsuitable Material for Structures	Cu. Yd	1,110
Box Culvert End Sections, Culvert No. 1	Each	2
Membrane Waterproofing System for Buried Structures	Sq. Yd	793
Rock Fill	Cu. Yd	1,110
Precast Concrete Box Culverts, 7'x7'	Foot	684


DRAWING 3 OF 7

TRANSYSTEMS

THORN DITCH
DRAINAGE IMPROVEMENTS
CULVERT 1 - GENERAL DATA

VILLAGE of SOUTH HOLLAND

SHEET NO. 39 of 71



Culvert Ties (typ.) \triangleright B $\rightarrow D$ $4x4 - W6xW6 WWR (Tb \le 5")$ 4x4 - W12xW12 WWR (Tb > 5")(typ. top and bottom) 1'-0" See Section D-D 1'-0"

 $6'-0'' \ min. \ (R \leq 3'-0'') \qquad See \ General \ Notes \\ 10'-0'' \ min. \ (R > 3'-0'') \qquad regarding \ culvert \ ties.$

GENERAL NOTES

Box Culvert End Sections shall be constructed according to the requirements of Section 540 of the Standard Specifications except as modified herein. End sections will be paid for at the contract unit price per each for Box Culvert End Sections.

The Contractor may furnish the end section as a single precast concrete piece or construct the end section in the field using cast-in-place (CIP) construction. For CIP construction, the bottom slab thickness shall be increased by 2" and the clear cover to the bottom mat of reinforcement shall be increased to 3".

Box section dimensions, materials, and reinforcement details for Box Culvert End Sections shall be according to the requirements for ASTM C 1577 as required for the design of the portion of the culvert within the limits of Precast Concrete Box Culverts except as modified herein.

The number of culvert ties shall be sufficient to engage the minimum length of culvert barrel shown within the pay limits for Precast Concrete Box Culverts and will be dependent upon the length of box culvert segments furnished by the Contractor. Culvert ties are not required for box culverts having a rise (R) less than or equal to 3 ft and a span (S) greater than or equal to 10 ft.

All costs associated with furnishing and installing or constructing the toewall and culvert ties will not be measured for payment but shall be included in the unit price for Box Culvert End Sections of the culvert number specified.

Shop drawings that detail slab thickness and reinforcement layout for the Box Culvert End Sections shall be provided to the Engineer for review and approval. Reinforcement bars not detailed herein shall be detailed with a clear distance at the end of the reinforcement not less than ½" nor more than 2". For the precast option, it shall be the Contractor's responsibility for determining a method of handling and a construction procedure shall be included on the shop drawings. The Contractor shall determine and detail in the shop drawings any necessary strengthening or stiffening provisions necessary to handle the precast segment. Any required modifications shall be at no extra charge.

The Contractor may use reinforcement bars in lieu of welded wire reinforcement (WWR). Reinforcement bars shall be limited to the sizes of #3 through #5 bars, a maximum spacing of the lesser of 8" or the member thickness, and shall result in an area of reinforcement equal to or greater than that provided by the WWR. Minimum lap lengths detailed herein are applicable to WWR and reinforcement bars.

Reinforcement (circumferential and longitudinal) in the culvert barrel portion of the end section being lapped with reinforcement from the wingwalls or bottom slab of the end section shall not be less than that required by ASTM C 1577 for the design fill height or the reinforcement detailed for the end section, whichever is greater.

One drain hole shall be provided in each wingwall for end sections of box culverts having an opening with a clear rise greater than 3 ft. The drain hole shall be located within the lower 1/3 of the clear rise of the box culvert and shall conform to the requirements of Article 503.11 of the Standard Specifications.

APRON END SECTION DIMENSIONS

	Span (S)	Rise (R)	Tt	Tb	Ts	А	В	С	D	Ε	Concrete Cu. Yd.	Culvert Ties Required
ſ	7'-0"	7'-0"	8"	8"	8"	8'-5"	4'-9"	7'-11 ¹ / ₂ "	11'-3"	25'-2 ¹ / ₄ "	12.3	Yes

DRAWING 4 OF 7

PLAN

TRANSYSTEMS


THORN DITCH

DRAINAGE IMPROVEMENTS

CULVERT 1 - BOX CULVERT END SECTION DETAILS 1

VILLAGE of SOUTH HOLLAND

SHEET NO. 40 of 71



#4 s or s1 bars at spacing = Tt

SECTION E-E

31/8"

BAR s1

9"

BAR s2

BAR s3


(,,9


(Tt

9"

BAR s

(Spacing need not be less than 8")







SECTION D-D


SECTION B-B (Bottom Slab)

*** This dimension shall be increased by 2" for CIP construction.




SECTION F-F (Showing culvert tie details)





RESTRAINT ANGLE DETAIL



TIE PLATE DETAIL

TOEWALL CONSTRUCTION SEQUENCE

- 1. Perform excavation and construct toewall.
- 2. Backfill accordingly and place bedding for precast box culvert end sections.
- Set precast box culvert end section.
- 4. Drill and epoxy grout reinforcement in toewall in accordance with Section 584 of the Standard Specifications.
- 5. Pressure grout voids using non-shrink grout conforming to Section 1024 of the Standard Specifications.
- * The Contractor may furnish a precast or cast-in-place toewall. The Contractor shall be responsible for the strength and stability of the precast toewall during handling. Additional lifting points may be required depending upon the length of the toewall or the Contractor may need to modify the design of the toewall for the proposed handling method.
- ** If soil conditions permit, the sides of the toewall may be poured directly against the soil. The clear cover on the sides of the toewall shall be increased to 3" by increasing the thickness of the toewall.

SECTION C-C

1" Ø anchor rods for the culvert ties shall conform to the requirements of ASTM F1554, Grade 105. Structural steel for the tie plate and restraint angle shall conform to the requirements of Article 1006.04 of the Standard Specifications. All components of the culvert tie detail shall be galvanized according to the requirements of AASHTO M 111 or M 232 as applicable. $2\frac{1}{4}$ " $x2\frac{1}{4}$ " $x^{\frac{5}{16}}$ " plate washers shall be provided under each nut required for the anchor rods. Anchor rods connecting precast sections shall be brought to a snug tight condition followed by an additional ½ turn on one of the nuts for anchor rods installed in the walls. Match marks shall be provided on the bolt and nut to verify relative rotation between the bolt and the nut. Holes in the walls for the culvert tie assembly may be drilled using core bits in lieu of using formed holes.

DRAWING 5 OF 7

= 5/5/2025 DESIGNED - MJS REVISED -THORN DITCH VILLAGE SHEET NO. **TRANSYSTEMS** SCALE = 2.000 ' / in. CHECKED - OS REVISED -DRAINAGE IMPROVEMENTS οf PROJECT NO = 23-R0646 DRAWN - MJS REVISED -41 of 71 CULVERT 1 - BOX CULVERT END SECTION DETAILS 2 SOUTH HOLLAND FILE NAME = THORN DITCH C1 005 CHECKED - OS REVISED -

		G	EOCON OFESSIONAL SERVICES							ВС	RII			. CE ≣ 1 C	
CLIEN	IT Robii		ngineering, Ltd.		PROJE	CT NAI	ME Thorn	Ditch							
PROJ	ECT NUM	MBER	24-G0400		PROJE	CT LO	CATION _	South I	Hollan	d, IL					
DATE	COMPLI	ETED _	4/19/24 LOGGED BY TW/KE		DRILLII	IG ME	THOD _3.2	25 in. F	ISA						
DEPTH (ft)	ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	ı	SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)		PLASTIC LIMIT	
0	505.5	:3 k · 3	All TODOGU		Ø	Œ		<u>o</u>	UNC.	0					Ч
	595.5 592.8		→ 4" TOPSOIL brown and gray SILTY CLAY hard		SS 1	100	4-4-5 (9)	4.5+		18.4					
5			black, brown, and gray FAT CLAY trace organics stiff to very stiff	\ 2	SS 2	44	2-2-3 (5)	2.0	1.8	30.3					
. <u>-</u>				\ 2	SS 3	78	2-2-3 (5)	2.0	2.2	28.9					
10	584.8				SS 4	61	2-1-2 (3)	2.0	1.7	30.9			55	20	35
 	582.3		gray ORGANIC LEAN CLAY stiff	/	SS 5	89	2-1-1 (2)	1.0	1.2	62.2					
15	579.8		gray LEAN CLAY medium stiff, moist	/	SS 6	100	1-1-2 (3)	0.5	0.7	25.2					
	577.3		brown and gray LEAN CLAY hard	/	SS 7	89	5-7-10 (17)	4.5+	5.4	19.6					
20	011.0		gray LEAN CLAY very stiff to hard	/	SS 8	100	4-5-6 (11)	4.5+	5.3	18.4					
				2	SS 9	100	3-4-6 (10)	3.5	3.7	18.4			36	18	18
_ 25	570.8		Bottom of borehole at 25.0 f	feet	SS 10	100	4-6-10 (16)	4.5+	5.3	15.8					
CAVE GROU	PLETION DEPTH IND WAT AT TIME	ft ER LE	GROUND ELEVATION BACKFILL Soil Cutting	595.8 ft	ST	oundw	37.01 Offi ater levels	were i	record					ay not	
			ILLING Dry upon completion		co	nstruct	ion.								
			tion represent an approximate boundary nd the transition may be gradual. Dashed									ervals	and b	etweer	1

			ngineering						ME Thorn								
	COMPLI		24-G0400		BY TW/KE				CATION <u>_</u> THOD <u>_</u> 3.2			a, IL					
		_	# 10/L 1		1111111			10			1071				ATI	TERBE	R
O DEPTH (ft)	ELEVATION (ft.)	GRAPHIC LOG		MATERIAL D	ESCRIPTION	L	SAMPLE 17PE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)	LIQUID	PLASTIC LIMIT	l
_	595.0		4" TOF	PSOIL rown and brow	n LEAN CLAY	7											Г
-				opsoil in SS1		X	SS 1	67	3-4-6 (10)	3.25		21.0					
5						X	SS 2	56	2-3-3 (6)	3.5	3.8	20.9					
-	589.3		trace o	brown, and gra organics very stiff, mois		X	SS 3	56	2-2-3 (5)	2.5	2.6	38.5					
10			∑	very earl, more	•	X	SS 4	100	1-2-2 (4)	1.5	1.4	38.3					
10 584.3 dark gray ORGANIC LEAN CLAY stiff							SS 5	100	1-1-1 (2)	1.0	1.0	64.4					
15	581.8		gray Ll ▼ soft, ve	EAN CLAY ery, moist		X	SS 6	44	1-1-2 (3)	0.5	0.4	26.9					
-	579.3			EAN CLAY iff to hard		X	SS 7	100	4-7-9 (16)	4.5+	7.4	16.8					
20						X	SS 8	100	3-5-7 (12)	4.5+	5.2	19.0					
-						X	SS 9	100	3-4-5 (9)	3.0	3.2	18.9					
_ 25	570.3					X	SS 10	100	3-5-6 (11)	3.5	3.8	18.5					
25	570.3	<u> </u>		Bottom of bore	ehole at 25.0 feet.		10	100	(11)	0.0	0.0	10.0					L
	DEPTH		25 ft		ELEVATION 595.3 f	ft		TES A 24+	56.55 Off	set 9.1	RT						
Ī,	AT END	OF DR	ILLING _8	3.50 ft / Elev 58 5.00 ft / Elev 5			- rep		ater levels t the groun ion.				-	_		ay not	

DRAWING 6 OF 7

DATE = 5/5/2025	DESIGNED - MJS	REVISED -
SCALE = 2.000 ' / in.	CHECKED - OS	REVISED -
PROJECT NO = 23-R0646	DRAWN - MJS	REVISED -
FILE NAME = THORN DITCH C1 006	CHECKED - OS	REVISED -

TRANSYSTEMS

THORN DITCH
DRAINAGE IMPROVEMENTS
CULVERT 1 - SOIL BORING LOGS 1

VILLAGE of SOUTH HOLLAND


SHEET NO. 42 of 71


		G	EOCON DEESSIONAL SERVICES							ВС	RIN			CE	
CLIEN	IT Robin		ngineering, Ltd.	PR	OJEC	T NAI	ME Thorn	Ditch							
PROJ	ECT NUM	/BER	24-G0400	PR	OJEC	T LO	CATION _	South I	Hollan	d, IL					
DATE	COMPLE	TED	4/19/24 LOGGED BY TW/KE	DR	ILLIN	G ME	THOD _3.2	25 in. F	HSA						
CLIEN PROJ DATE HLddd 0 0	ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPI F TYPE	NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)		PLASTIC LIMIT	
0		: A L : A	411. T.O.D.O.G.					ă	Š						
	595.8 / 593.1		— 4" TOPSOIL brown SILTY CLAY very stiff		SS 1	56	3-5-5 (10)	3.5	-	20.7					
5			brown and gray LEAN CLAY trace roots in SS2 and SS3 very stiff to hard	X	SS 2	67	3-4-5 (9)	3.0	2.8	21.4					
				X	SS 3	100	3-2-4 (6)	2.5	2.3	24.2					
10				X	SS 4	100	2-3-5 (8)	3.5	3.4	26.8					
 				X	SS 5	100	5-5-7 (12)	4.0	3.8	23.4			36	21	15
15 20 25	580.1			X	SS 6	100	3-6-9 (15)	4.5+	6.0	20.7					
			gray LEAN CLAY very stiff to hard	X	SS 7	100	3-5-8 (13)	3.5	3.4	18.9					
20				X	SS 8	100	4-4-7 (11)	3.5	3.4	18.8					
 				X	SS 9	100	4-4-7 (11)	3.75	3.8	18.6					
 25	571.1			X	SS 10	100	4-5-9 (14)	4.25	4.4	14.6					
	PLETION DEPTH IND WAT	ft	BACKFILL Soil Cuttings	1 ft		TES	17.15 Off	set 10.	.7 RT						
	GROUND WATER LEVELS: AT TIME OF DRILLING None AT END OF DRILLING Dry upon completion AFTER DRILLING														
L b			ation represent an approximate boundary betward the transition may be gradual. Dashed lines									ervals	and be	etween	


AB/24-G0400 THO	\prec		G	EOCON DESSIONAL SERVICES						ВС	RIN	NG I		CB	
일 C	LIEN	T Robii	nson E	ngineering, Ltd.	PRO	JECT NA	ME Thorn	Ditch							
P				24-G0400			CATION S		Holland	d, IL					
Ĭ D.	ATE (COMPLI	ETED	4/19/24 LOGGED BY TW/KE	DRIL	LING ME	THOD _3.2	25 in. F	ISA						
OITCH, SOU					й	%		(Qp)	1 (Qu)	(%	Ŀ.	(%)		ERBE	
EMPLATE GDT - 6/18/24 1041 - K:\GEOTECHNICAL\2024/24/24/G0400 GEO REL SGR CULVERT REPLACEMENTS, PEDESTRIAN BRIDGES AND DETENTION, THORN DITCH, SOUTH HOLLAND, ILLABS24-69/400 THOR	(#)	ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	RECOVERY 9 (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT (pcf)	ORGANIC CONTENT (%)	LIQUID	PLASTIC LIMIT	PLASTICITY INDEX
S AN	-	596.6		─ 4" TOPSOIL											
IAN BRIDGE				dark brown to brown SILTY CLAY trace topsoil in SS1 very stiff		S 67	3-4-4 (8)	2.5		20.6					
S, PEDESTR	5					S 78	3-4-5 (9)	2.0	2.0	25.4					
ACEMENTS	+	590.9	33332	brown CLAYEY SILT loose, moist		S 100	5-5-4 (9)			27.1					
LVERT REPI	0	588.4		brown and gray LEAN CLAY very stiff		S 100	2-3-4 (7)	3.5	3.5	24.7					
REL SGR CU	-	500.0				S 100	2-3-4 (7)	2.5	2.2	25.4					
30400 GEO F	15	583.9		gray LEAN CLAY trace silt stiff to hard		S 100	2-3-3 (6)	2.0	1.9	19.4					
1L\2024\24-0	-			moist in SS6		S 89	3-3-4 (7)	2.25	2.2	21.5					
OTECHNIC	20					S 100	2-3-4 (7)	2.25	2.3	20.8					
10:41 - K:\GE	_					S 100	4-4-7 (11)	3.5	3.4	19.0					
DT - 6/18/24	-	571 O			M s	S 100	3-6-9 (15)	4.5+	5.4	13.0					
TEMPLATE.G	25	571.9	<i>\////</i>	Bottom of borehole at 25.0 feet.		-	(.0)								
DATA		LETION DEPTH		H _25 ft GROUND ELEVATION _596.9 BACKFILL _Soil Cuttings	ft	NOTES	83.75 Offs	set 0 2	ΙT						
GTS ZO		ND WAT								no-ti-	dua *		2004 t	roo-	
.06-0	AT TIME OF DRILLING None Boring offset approximately 12 ft north due to overhead trees.														
GPS STANDARD GEOTECH LOG - OZ STD DATA				ILLING Dry upon completion	were r dwatei							n.			
ANDARD 6				ation represent an approximate boundary between and the transition may be gradual. Dashed lines a								ervals	and be	etween	
GPS STA															

DRAWING 7 OF 7

	DATE = 5/5/2025	DESIGNED - MJS	REVISED -
	SCALE = 2.000'/in.	CHECKED - OS	REVISED -
	PROJECT NO = 23-R0646	DRAWN - MJS	REVISED -
omshaban ishaban	FILE NAME = THORN DITCH C1 007	CHECKED - OS	REVISED -









LIMITS OF MEMBRANE WATERPROOFING

Longitudinal limits of membrane waterproofing for the precast concrete culvert are along the full length between headwalls




<u>PAY LIMITS FOR POROUS</u> <u>GRANULAR EMBANKMENT</u>

(Hatched area)




DRAIN DETAIL

(All costs associated with furnishing and constructing the above drain detail will not be measured for payment but shall be included in the contract unit price for the associated work.)



PRECAST CONCRETE RISER
PLAN VIEW



SECTION A-A

GENERAL NOTES

- 1. The design fill height for this box is shown on Section Thru Box Culvert. The precast box culvert sections shall conform to the requirements of ASTM C 1577.
- 2. Drain holes shall be provided on exterior culvert walls for each precast box segment. The drain hole shall be located within 1/3 of the clear rise of the box culvert, shall not intercept the haunch, and shall conform to the requirements of Article 503.11 of the Standard Specification.
- 3. Nonwoven geotextile fabric shall conform to the requirements of Art. 1080.01 of the Standard Specifications. The minimum weight of the fabric shall be 6 ounces per square yard.
- 4. Precast concrete box culverts and box culvert end sections shall be backfilled with Porous Granular Embankment in the required excavation areas on the sides of the box culvert from the top of the box culvert to the bottom of the box culvert. This area of PGE is included in the Porous Granular Embankment pay item. The 6-inch thick layer of porous granular material required under the precast concrete box culvert, according to Section 540.06 of the standard specifications, shall also apply to the end sections. Cost of this porous granular material will not be paid for separately but shall be included in the unit price of the work for which it is required
- 5. The limits and quantities of Removal and Replacement of Unsuitable Materials for Structures shown are based on the boring data and may be modified by the Engineer for variable subsurface conditions encountered in the field.
- 6. The contractor shall be responsible to divert the stream flow during construction to keep construction area free of water. The method of the water diversion shall be subject to the approval of the engineer and the cost shall be included in the cost of Precast Concrete Box Culverts, 7'x7'.

CULVERT CONSTRUCTION SEQUENCE

- 1. Close roadway to all traffic.
- 2. Divert water from construction area.
- 3. Perform removal of existing culvert.
- 4. Perform construction of replacement structure.
- 5. Open roadway to traffic.
- 6. Remove water diversion measures.

TOTAL BILL OF MATERIAL

ITEM	UNIT	TOTAL
Earth Excavation	Cu. Yd	850
Porous Granular Embankment	Cu. Yd	792
Removal of Existing Structures No. 2	Each	1
Structure Excavation	Cu. Yd	668
Removal and Disposal of Unsuitable Material for Structures	Cu. Yd	222
Box Culvert End Sections, Culvert No. 1	Each	1
Box Culvert End Sections, Culvert No. 2	Each	1
Membrane Waterproofing System for Buried Structures	Sq. Yd	205
Helical Pier	Each	72
Porous Granular Embankment, Special	Cu. Yd	217
Biaxial Geogrid	Sq. Yd	588
Precast Concrete Box Culverts, 7'x7'	Foot	172


DRAWING 2 OF 8

TRANSYSTEMS

THORN DITCH
DRAINAGE IMPROVEMENTS
CULVERT 2 - GENERAL DATA

VILLAGE of SOUTH HOLLAND

SHEET NO. 45 of 71



Culvert Ties (typ.) \triangleright B $\rightarrow D$ $4x4 - W6xW6 WWR (Tb \le 5")$ 4x4 - W12xW12 WWR (Tb > 5")(typ. top and bottom) 1'-0" See Section D-D 1'-0"

 $6'-0'' \ min. \ (R \leq 3'-0'') \qquad See \ General \ Notes \\ 10'-0'' \ min. \ (R > 3'-0'') \qquad regarding \ culvert \ ties.$

GENERAL NOTES

Box Culvert End Sections shall be constructed according to the requirements of Section 540 of the Standard Specifications except as modified herein. End sections will be paid for at the contract unit price per each for Box Culvert End Sections, Culvert No. 1.

The Contractor may furnish the end section as a single precast concrete piece or construct the end section in the field using cast-in-place (CIP) construction. For CIP construction, the bottom slab thickness shall be increased by 2" and the clear cover to the bottom mat of reinforcement shall be increased to 3".

Box section dimensions, materials, and reinforcement details for Box Culvert End Sections shall be according to the requirements for ASTM C 1577 as required for the design of the portion of the culvert within the limits of Precast Concrete Box Culverts except as modified herein.

The number of culvert ties shall be sufficient to engage the minimum length of culvert barrel shown within the pay limits for Precast Concrete Box Culverts and will be dependent upon the length of box culvert segments furnished by the Contractor. Culvert ties are not required for box culverts having a rise (R) less than or equal to 3 ft and a span (S) greater than or equal to 10 ft.

All costs associated with furnishing and installing or constructing the toewall and culvert ties will not be measured for payment but shall be included in the unit price for Box Culvert End Sections, Culvert No. 1.

Shop drawings that detail slab thickness and reinforcement layout for the Box Culvert End Sections shall be provided to the Engineer for review and approval. Reinforcement bars not detailed herein shall be detailed with a clear distance at the end of the reinforcement not less than ½" nor more than 2". For the precast option, it shall be the Contractor's responsibility for determining a method of handling and a construction procedure shall be included on the shop drawings. The Contractor shall determine and detail in the shop drawings any necessary strengthening or stiffening provisions necessary to handle the precast segment. Any required modifications shall be at no extra charge.

The Contractor may use reinforcement bars in lieu of welded wire reinforcement (WWR). Reinforcement bars shall be limited to the sizes of #3 through #5 bars, a maximum spacing of the lesser of 8" or the member thickness, and shall result in an area of reinforcement equal to or greater than that provided by the WWR. Minimum lap lengths detailed herein are applicable to WWR and reinforcement bars.

Reinforcement (circumferential and longitudinal) in the culvert barrel portion of the end section being lapped with reinforcement from the wingwalls or bottom slab of the end section shall not be less than that required by ASTM C 1577 for the design fill height or the reinforcement detailed for the end section, whichever is greater.

One drain hole shall be provided in each wingwall for end sections of box culverts having an opening with a clear rise greater than 3 ft. The drain hole shall be located within the lower 1/3 of the clear rise of the box culvert and shall conform to the requirements of Article 503.11 of the Standard Specifications.

APRON END SECTION DIMENSIONS

Span (S)	Rise (R)	Tt	Tb	Ts	А	В	С	D	Е	Concrete Cu. Yd.	Culvert Ties Required
7'-0"	7'-0"	8"	8"	8"	8'-5"	4'-9"	7'-11 ¹ / ₂ "	11'-3"	25'-2 ¹ / ₄ "	12.3	Yes

DRAWING 3 OF 8

PLAN

TRANSYSTEMS


THORN DITCH

DRAINAGE IMPROVEMENTS

CULVERT 2- BOX CULVERT END SECTION DETAILS 1

VILLAGE of SOUTH HOLLAND


SHEET NO. 46 of 71




#4 s or s1 bars at spacing = Tt

SECTION E-E

(Spacing need not be less than 8")






SECTION D-D

SECTION B-B (Bottom Slab)

#4 s3 bar

 $\overline{(typ. for R > 3'-0")}$

*** This dimension shall be increased by 2" for CIP construction.



[1" Ø anchor rods with

SECTION F-F (Showing culvert tie details)


~ 1/4" Tie ₽

TOEWALL CONSTRUCTION SEQUENCE

- 1. Perform excavation and construct toewall.
- 2. Backfill accordingly and place bedding for precast box culvert end sections.
- Set precast box culvert end section.
- 4. Drill and epoxy grout reinforcement in toewall in accordance with Section 584 of the Standard Specifications.
- 5. Pressure grout voids using non-shrink grout conforming to Section 1024 of the Standard Specifications.
- * The Contractor may furnish a precast or cast-in-place toewall. The Contractor shall be responsible for the strength and stability of the precast toewall during handling. Additional lifting points may be required depending upon the length of the toewall or the Contractor may need to modify the design of the toewall for the proposed handling method.
- ** If soil conditions permit, the sides of the toewall may be poured directly against the soil. The clear cover on the sides of the toewall shall be increased to 3" by increasing the thickness of the toewall.


Q 11/4" Ø hole for 1" Ø anchor rod with 21/4" x 21/4" x 5/16" bottom leg of angle

RESTRAINT ANGLE DETAIL



SECTION C-C


1" Ø anchor rods for the culvert ties shall conform to the requirements of ASTM F1554, Grade 105. Structural steel for the tie plate and restraint angle shall conform to the requirements of Article 1006.04 of the Standard Specifications. All components of the culvert tie detail shall be galvanized according to the requirements of AASHTO M 111 or M 232 as applicable. $2\frac{1}{4}$ " $x2\frac{1}{4}$ " $x^{\frac{5}{2}}$ 16" plate washers shall be provided under each nut required for the anchor rods. Anchor rods connecting precast sections shall be brought to a snug tight condition followed by an additional ½ turn on one of the nuts for anchor rods installed in the walls. Match marks shall be provided on the bolt and nut to verify relative rotation between the bolt and the nut. Holes in the walls for the culvert tie assembly may be drilled using core bits in lieu of using formed holes.




TIE PLATE DETAIL


DRAWING 4 OF 8


= 5/5/2025 DESIGNED - MJS REVISED -THORN DITCH VILLAGE SHEET NO. TRANSYSTEMS SCALE = 2.000 ' / in. CHECKED - OS REVISED -DRAINAGE IMPROVEMENTS οf PROJECT NO = 23-R0646 DRAWN - MJS REVISED -47 of 71 CULVERT 2 - BOX CULVERT END SECTION DETAILS 2 SOUTH HOLLAND FILE NAME = THORN DITCH C2 004 CHECKED - OS REVISED -





SECTION C-C





As1m REINFORCEMENT (in.2/ ft) Rise (fi 12 5 6 9 10 11 0.40 0.35 0.43 0.39 0.36 0.34 0.40

(As1m reinforcement based upon welded wire reinforcement conforming to AASHTO M 55 or M 221).

1 DIMENSION

 $#3 \ bar = 2'-0"$ $#4 \ bar = 2'-8''$

 $\#6 \ bar = 3'-11''$

 $#5 \ bar = 3'-4''$


Notes:


Alternate Section D-D is provided to allow the Contractor the option of casting the bottom slab of the end section first followed by construction of the sidewalls using conventional forming methods. Shop drawings that detail slab thickness and reinforcement layout shall be submitted to the Engineer for review and approval when using Alternate Section D-D.


The size and spacing of the v2 bars shall provide a minimum reinforcement area along each face of the walls (in.²/ft.) equal to 1.10*(As1m). v2 bars may consist of #3 thru #6 size reinforcement bars and the longitudinal spacing shall not exceed the lesser of the wall thickness or 8 inches.

Bonded construction joints shall be prepared according to Article 503.09 of the Standard Specifications.

SECTION D-D ALTERNATE SECTION D-D








TOEWALL CONSTRUCTION SEQUENCE

- 1. Perform excavation and construct toewall.
- 2. Backfill according to the applicable paragraphs of Article 502.10 of the Standard Specifications and place bedding for precast box culvert end sections.
- 3. Set precast box culvert end section.
- 4. Drill and epoxy grout reinforcement in toewall in accordance with Section 584 of the Standard Specifications.
- 5. Pressure grout voids using non-shrink grout conforming to Section 1024 of the Standard Specifications.
- The Contractor may furnish a precast or cast-in-place toewall. The Contractor shall be responsible for the strength and stability of the precast toewall during handling. Additional lifting points may be required depending upon the length of the toewall or the Contractor may need to modify the design of the toewall for the proposed handling the method.
- ** If soil conditions permit, the sides of the toewall may be poured directly against the soil. The clear cover on the sides of the toewall shall be increased to 3" by increasing the thickness of the toewall.



SECTION F-F

DRAWING 6 OF 8

3" Ø corrugated PE pipe

Standard Specifications.

Fill with non-shrink grout

#4 v1 bars drilled and grouted into toewall in 9" min.

deep holes at 1'-6" cts., max.

per Article 1040.04 of the

6-#5 h1 bars

placed as shown

#4 s1 bars at

1'-0" cts., max

SECTION E-E

DATE	=	5/5/2025	DESIGNED	_	MJS	REVISED	_	
SCALE	=	2.000 ' / in.	CHECKED	_	os	REVISED	_	
PROJECT NO	=	23-R0646	DRAWN	_	MJS	REVISED	_	
FILE NAME	=	THORN_DITCH_C2_006	CHECKED	_	os	REVISED	_	


1½" cl.

1'-0"

TRANSYSTEMS

THORN DITCH DRAINAGE IMPROVEMENTS CULVERT 2 - PRECAST TAPERED END SECTION DETAILS 2

VILLAGE οf **SOUTH HOLLAND** SHEET NO. 49 of 71



AB\24-G0400 THO			PR	EC	OCON NAL SERVICES							ВС	RII	NG I		CE	
Ğ, [[LIEN	IT Robii	nson E	Engineering	, Ltd.		PROJE	CT NA	ME Thorn	Ditch							
A F	ROJ	ECT NUM	MBER	24-G0400	1		PROJE	CT LO	CATION _S	South I	Hollan	d, IL					
를 C	ATE	COMPLI	ETED	4/19/24	LOGGED BY	TW/KE	DRILLI	NG ME	THOD _3.2	25 in. F	HSA						
EMPLATE.GDT - 6/18/24 10:41 - K:\GEOTECHNICAL\2002424-G04.00 GEO REL SGR CULVERT REPLACEMENTS, PEDESTRIAN BRIDGES AND DETENTION, THORN DITCH, SOUTH HOLLAND, ILVABS24-G04.00 THOR	(#) O	ELEVATION (ft.)	GRAPHIC LOG		MATERIAL DESCF	RIPTION	SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)		PLASTIC STIMIT LIMIT	
AN BRIDGES AN	-	594.7 592.0		hard	SILTY CLAY		ss 1	72	4-4-5 (9)	4.0		18.2					
ITS, PEDESTRI	5	589.0		brown trace s stiff	and gray LEAN CLA and	·Υ	SS 2	67	2-3-4 (7)	1.75		27.5					
REPLACEMEN	-				dark brown, and gra n stiff to stiff	y ORGANIC CLAY	SS 3	44	2-1-2 (3)	1.25	1.2	40.8					
R CULVERT	10 	584.0		gray L	EAN CLAY		SS 4	83	1-2-1 (3)	0.75		43.3					
REL SG	-	582.0		mediur			SS 5	100	1-1-1 (2)	0.75	0.6	68.4			46	23	23
/24-G0400 GEC	- 15				ay and black ORGA oft to soft	NIC CLAY	SS 6	100	1-1-1 (2)	0.5	0.4	49.6	-				
NICAL\2024	-	577.0					SS 7	83	WOH-1-1 (2)	0.25		80.6		9.0			
к:\GEОТЕСН	- 20				EAN CLAY iff to hard		SS 8	100	1-2-3 (5)	3.0	3.0	22.8					
18/24 10:41 - 1	-						SS 9	100	8-5-9 (14)	4.5+	5.2	17.9					
E.GDT - 6/	- 25	570.0			Bottom of borehole	at 25 0 foot	SS 10	100	4-5-7 (12)	4.5+	4.6	17.8					
PLAT					bottom of potenole	at 20.0 1661.											
-	OMF	PLETION	DEPT	H _25 ft	GROUND ELEV	/ATION 595 ft											
DAT		DEPTH		11 <u>25 it</u>				TES A 33+	36.50 Offs	set 8.4	RT						
ZSTE		JND WAT															
0-90		AT TIME	OF D	RILLING	None		Bo	ring of	fset approx	imatel	ly 5 ft e	east di	ue to c	verhe	ad po	wer lin	es.
S STANDARD GEOTECH LOG - OZ STD DATA				rilling ng	- Dry upon completion	on	Groundwater levels were recorded during drilling and may not represent the groundwater conditions at the time of construction.										
DARD G					ent an approximate sition may be gradual.									ervals	and be	etween	ı
SSTAN		J	,		, , ,							<u> </u>					

			ngineering, Ltd.			ME Thorn								_
	COMPL		24-G0400 4/19/24 LOGGED BY TW/KE			CATION _S THOD _3.2			d, IL					_
DAIL	OOM L		4/10/24 LOGGLD DT 1W//CL	_ DIVIE				10/1				ATI	ΓERΒΙ	EF
O DEPTH (ft)	ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE NIMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)		PLASTIC LIMIT	
	595.2		4" TOPSOIL dark brown CLAY (FILL)											T
	592.5		trace topsoil very stiff	X s		3-4-4 (8)	3.75	-	20.6	-				
5			black, brown, and gray LEAN CLAY trace organics stiff to very stiff	X S		3-3-3 (6)	2.0	2.0	32.4					
				X s		2-2-3 (5)	2.0	2.2	26.8					
10			slight manure odor in SS4	X s		1-2-2	1.5	1.4	28.2	-				
- 				X s		2-2-3 (5)	1.0	1.1	27.1	_				
15				X s		2-2-3 (5)	1.0	1.0	15.9	_				
	579.5		dark gray and black ORGANIC LEAN CLAY medium stiff	X 5.		2-1-1 (2)	0.5	0.6	94.7	-	5.9			
20	577.0		gray LEAN CLAY stiff to hard	X S		WOH-2-3 (5)	1.0	1.0	27.2					
- 			moist in SS8 and SS9	X s		2-3-5 (8)	1.0	1.1	26.0					
 25	570.5		¥	S 1		4-5-8 (13)	4.5+	4.8	17.6					
			Bottom of borehole at 25.0 feet.				4.5+	4.8	17.6					
	DEPTH		H _25 ft GROUND ELEVATION _595.5 ft BACKFILL Soil Cuttings		NOTES STA 34+	-11.09 Off	set 12	.9 RT						
GROU ∑	IND WAT	OF DR	VELS: RILLING _23.50 ft / Elev 572.00 ft ILLING _23.50 ft / Elev 572.00 ft		Groundy	vater levels at the groun	were	record		-	-		ay not	

DRAWING 8 OF 8


	DATE =	5/5/2025	DESIGNED	_	MJS	REVISED	-
	SCALE =	2.000 ' / in.	CHECKED	-	OS	REVISED	-
	PROJECT NO =	23-R0646	DRAWN	_	MJS	REVISED	-
SAVED BY: omshaban ED BY: omshaban	FILE NAME =	THORN DITCH C2 008	CHECKED	_	OS	REVISED	_


TRANSYSTEMS

THORN DITCH
DRAINAGE IMPROVEMENTS
CULVERT 2 - SOIL BORING LOGS


VILLAGE of SOUTH HOLLAND

SHEET NO. 51 of 71







SECTION THRU PRECAST BOX CULVERT




LIMITS OF MEMBRANE WATERPROOFING

Longitudinal limits of membrane waterproofing for the precast concrete culvert are along the full length between headwalls







<u>SECTION A-A</u>

GENERAL NOTES

- 1. The design fill height for this box is shown on Section Thru Box Culvert. The precast box culvert sections shall conform to the requirements of ASTM C 1577.
- 2. Drain holes shall be provided on exterior culvert walls for each precast box segment. The drain hole shall be located within 1/3 of the clear rise of the box culvert, shall not intercept the haunch, and shall conform to the requirements of Article 503.11 of the Standard Specification.
- Nonwoven geotextile fabric shall conform to the requirements of Art. 1080.01 of the Standard Specifications. The minimum weight of the fabric shall be 6 ounces per square yard.
- 4. Precast concrete box culverts and box culvert end sections shall be backfilled with Porous Granular Embankment in the required excavation areas on the sides of the box culvert from the top of the box culvert to the bottom of the box culvert. This area of PGE is included in the Porous Granular Embankment pay item. The 6-inch thick layer of porous granular material required under the precast concrete box culvert, according to Section 540.06 of the standard specifications, shall also apply to the end sections. Cost of this porous granular material will not be paid for separately but shall be included in the unit price of the work for which it is required.
- 5. The limits and quantities of Removal and Replacement of Unsuitable Materials for Structures shown are based on the boring data and may be modified by the Engineer for variable subsurface conditions encountered in the field.
- 6. The contractor shall be responsible to divert the stream flow during construction to keep construction area free of water. The method of the water diversion shall be subject to the approval of the engineer and the cost shall be included in the cost of Precast Concrete Box Culverts, 10'x7'.

CULVERT CONSTRUCTION SEQUENCE

- 1. Close roadway to all traffic.
- 2. Divert water from construction area.
- 3. Perform removal of existing culvert.
- 4. Perform construction of replacement structure.
- 5. Open roadway to traffic.
- 6. Remove water diversion measures.

TOTAL BILL OF MATERIAL

ITEM	UNIT	TOTAL
Earth Excavation	Cu. Yd	455
Porous Granular Embankment	Cu. Yd	541
Removal of Existing Structures No. 3	Each	1
Structure Excavation	Cu. Yd	420
Removal and Disposal of Unsuitable Material for Structures	Cu. Yd	185
Box Culvert End Sections, Culvert No. 3	Each	2
Membrane Waterproofing System for Buried Structures	Sq. Yd	143
Helical Pier	Each	48
Porous Granular Embankment, Special	Cu. Yd	183
Biaxial Geogrid	Sq. Yd	496
Precast Concrete Box Culverts, 10' x 7'	Foot	88


DRAWING 2 OF 6

TRANSYSTEMS

THORN DITCH
DRAINAGE IMPROVEMENTS
CULVERT 3 - GENERAL DATA

VILLAGE of SOUTH HOLLAND

SHEET NO. 53 of 71



Adjust drain hole location to accommodate storm sewer pipe See detail A for reinforcement

PLAN

GENERAL NOTES

Box Culvert End Sections shall be constructed according to the requirements of Section 540 of the Standard Specifications except as modified herein. This work will be measured for payment as each, with each end of each culvert being one each. End sections will be paid for at the contract unit price per each for Box Culvert End Sections, Culvert No. 3.

Typical box section dimensions, materials, and reinforcement details for Box Culvert End Sections shall be according to the requirements of ASTM C 1577 as required for the design of the portion of the culvert within the limits of Precast Concrete Box Culverts except as modified herein.

Number of segments shown in Elevation is for example only. Length and number of precast box sections required to construct Box Culvert End Sections shall be determined by the Contractor.

See roadway plans for embankment slope (V:H).

1" Ø anchor rods for the culvert ties shall conform to the requirements of ASTM F1554, Grade 105. Structural steel for tie plate and restraint angle shall conform to the requirements of Article 1006.04 of the Standard Specifications. All components of the culvert tie detail shall be galvanized according to the requirements of AASHTO M 111 or M 232 as applicable. 21/4" x anchor rods. Anchor rods connecting precast sections shall be brought to a snug tight condition followed by an additional 1/2 turn on one of the nuts for anchor rods installed in the walls. Match marks shall be provided on the bolt and nut to verify relative rotation between the bolt and the nut. Holes in the walls for the culvert tie assembly may be drilled using core bits in lieu of using formed holes.

All costs associated with furnishing and installing or constructing the toewall and culvert ties will not be measured for payment but shall be included in the contract unit price for Box Culvert End Sections, Culvert No. 3. Drain holes shall conform to the requirements of Article 503.11 of the

Standard Specifications unless noted otherwise.

Nonwoven geotextile fabric shall conform to the requirements of Article 1080.01. The minimum weight of the fabric shall be 6 oz. / sq. yd..

For end sections with traversable pipe grate systems, see grate detail sheet for required modifications.

typ. $\frac{1''}{\sqrt{2}}$ $\frac{1}{\sqrt{2}}$ $\frac{1}{\sqrt{2}}$ $\frac{1}{\sqrt{4}}$ $\frac{1}{\sqrt{4}$

typ.


Porous granular

embankment, special

RESTRAINT ANGLE DETAIL


Span

END VIEW




SECTION A-A

(All costs associated with furnishing and constructing the above drain detail will not be measured for payment but shall be included in the contract unit price for the associated work.)



<u>SECTION B-B</u> (Showing end section tie details)




TIE PLATE DETAIL

DRAWING 3 OF 6

	DATE = 5/5/2025	DESIGNED - MJS	REVISED -
	SCALE = 2.000'/in.	CHECKED - OS	REVISED -
	PROJECT NO = 23-R0646	DRAWN - MJS	REVISED -
LAST SAVED BY: omshaban PLOTTED BY: omshaban	FILE NAME = THORN_DITCH_C3_003	CHECKED - OS	REVISED -

Headwall

SHEET NO. 54 of 71



(Design Earth Cover < 2 ft)

SECTION C-C

3" Ø corrugated PE pipe

Standard Specifications.

Fill with non-shrink grout

#4 v1 bars drilled and

grouted into toewall in 9" min.

deep holes at 1'-6" cts., max.

per Article 1040.04 of the


6-#5 h1 bars

placed as shown


#4 s1 bars at

1'-0" cts., max

SECTION E-E



SECTION D-D



ALTERNATE SECTION D-D

As1m REINFORCEMENT $(in.^2/ft)$ 6 7 9 10 11 8 Ts (in.)

(As1m reinforcement based upon welded wire reinforcement conforming to AASHTO M 55 or M 221).


Alternate Section D-D is provided to allow the Contractor the option of casting the bottom slab of the end section first followed by construction of the sidewalls using conventional forming methods. Shop drawings that detail slab thickness and reinforcement layout shall be submitted to the Engineer for review and approval when using Alternate Section D-D.

The size and spacing of the v2 bars shall provide a minimum reinforcement area along each face of the walls (in.2/ft.) equal to 1.10*(As1m). v2 bars may consist of #3 thru #6 size reinforcement bars and the longitudinal spacing shall not exceed the lesser of the wall thickness or 8 inches.

Bonded construction joints shall be prepared according to Article 503.09 of the Standard Specifications.


11" R

BAR s2



TOEWALL CONSTRUCTION SEQUENCE

- 1. Perform excavation and construct toewall.
- 2. Backfill according to the applicable paragraphs of Article 502.10 of the Standard Specifications and place bedding for precast box culvert end sections.
- 3. Set precast box culvert end section.
- 4. Drill and epoxy grout reinforcement in toewall in accordance with Section 584 of the Standard Specifications.
- 5. Pressure grout voids using non-shrink grout conforming to Section 1024 of the Standard Specifications.
- The Contractor may furnish a precast or cast-in-place toewall. The Contractor shall be responsible for the strength and stability of the precast toewall during handling. Additional lifting points may be required depending upon the length of the toewall or the Contractor may need to modify the design of the toewall for the proposed handling the method.
- ** If soil conditions permit, the sides of the toewall may be poured directly against the soil. The clear cover on the sides of the toewall shall be increased to 3" by increasing the thickness of the toewall.




 ℓ_1 DIMENSION


 $#3 \ bar = 2'-0"$

 $#4 \ bar = 2'-8''$

 $#5 \ bar = 3'-4"$

 $\#6 \ bar = 3'-11''$





SECTION F-F

¾" "∆" Drip notch

full length of span

1'-0"

DETAIL A

2-#5 s2 bars

DRAWING 4 OF 6

= 5/5/2025 DESIGNED - MJS REVISED -SCALE = 2.000 ' / in. CHECKED - OS REVISED -PROJECT NO = 23-R0646 DRAWN - MJS REVISED -FILE NAME = THORN DITCH C3 004 CHECKED - OS REVISED -

1½" cl.


1'-0"

TRANSYSTEMS

THORN DITCH DRAINAGE IMPROVEMENTS CULVERT 3 - PRECAST TAPERED END SECTION DETAILS 2

VILLAGE οf **SOUTH HOLLAND**

SHEET NO. 55 of 71





LAB/24-G0400 THO				CON AL SERVICES							ВС	PRIN			CB 1 0	-
길 의 CLI	ENT Robi	nson E	ngineering, l	_td.		PROJE	CT NA	ME Thorn	Ditch							
PR	OJECT NUI	MBER	24-G0400			PROJE	CT LO	CATION S	South F	Hollan	d, IL					
를 DA	TE COMPL	ETED	4/18/24	LOGGED BY	TW/KE	DRILLI	NG ME	THOD _3.2	25 in. F	ISA						
EMPIATE GDT - 6/18/24 10:41 - K/GEOTECHNICAL/200446-G0400 GEO REL SGR CUL/VERT REPLACEMENTS, PEDESTRAIN BRIDGES AND DETENTION, THORN DITCH, SOUTH HOLLAND, ILL/AB/24-G0400 THOR	<u> </u>	GRAPHIC		MATERIAL DESC	CRIPTION	SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)		PLASTIC LIMIT LIMIT	
N BRIDGES A	594.4		dark bro trace gra stiff	wn CLAY (FILL)		SS 1	44	3-3-3 (6)	1.5		19.7					
S, PEDESTRIA			brown S stiff	LTY CLAY		SS 2	61	2-3-2 (5)	1.5		21.0					
PLACEMENT	588.7		black LE trace org very stiff			X ss 3	67	2-3-5 (8)	2.0	2.1	35.0					
CULVERT RE	-		stiff	nd gray LEAN CL	.AY	SS 4	83	2-1-3 (4)	1.75	1.8	30.2					
24-G0400 GEO REL SGR	_ _ _ 5		gray FA very soft			SS 5	100	1-2-1 (3) 1-1-1 (2)	0.5	0.6	58.3 66.5					
GEOTECHNICAL/2024			with she	lls in SS7 and SS	58	SS 7	100	1-1-1 (2) 1-1-1 (2)	0.25	1.1	74.0		5.0			
- 6/18/24 10:41 - K	573.7		gray LEA stiff to ha			SS 9	100	1-2-2 (4)	1.25	1.1	27.2					
25	569.7					10	89	(14)	4.5+	6.8	18.7					
CA,	AT END	ft TER LE OF DI	H _25 ft EVELS: RILLING	_ BACKFILL _S	EVATION 594.7 ft Soil Cuttings	Gi	oundw	27.15 Off ater levels t the groun ion.	were r	ecord		-	-		y not	
SSTANDARD					e boundary between so al. Dashed lines are inc								ervals	and be	etween	

		gineering, Ltd. 24-G0400			ME Thorn		Hollan	d II				TERBERGLIMITS AUSTRICITY AND THE STATE OF					
DATE COMPL	_				THOD 3.2			u, 1L									
							ŝ										
O C(ft) (ft) ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)	LIQUID						
593.4		√ 4" TOPSOIL brown SILTY CLAY											Г				
- - -		very stiff	SS 1		3-5-5 (10)	2.0		17.3	-								
5 587.7			SS 2		3-5-6 (11)	3.75		17.4	-								
		dark brown and gray LEAN CLAY trace sand very stiff	SS 3		3-3-5 (8)	3.0		27.3									
10		gray and black LEAN CLAY stiff	SS 4		2-2-3 (5)	1.75	1.6	27.3	_								
582.7		dark gray FAT CLAY medium stiff, moist	SS 5		1-1-1 (2)	0.5	0.6	51.1									
15			SS 6		WOH-1-1 (2)	0.75	0.8	67.7		3.6							
577.7		black and gray ORGANIC SILT trace shells very loose	X 55 7	5 100	1-1-1 (2)			78.8			63	48	1				
20			X SS 8		WOH-1-1 (2)			74.6		7.3							
572.7		gray LEAN CLAY very soft to hard	X 55		WOH-1-2 (3)	<0.25		25.1									
		very moist in SS9	S 5		3-6-9 (15)	4.5+	6.0	20.8									


DRAWING 6 OF 6

	DATE = 5/5/2025	DESIGNED - MJS	REVISED -
	SCALE = 2.000'/in.	CHECKED - OS	REVISED -
	PROJECT NO = 23-R0646	DRAWN - MJS	REVISED -
ED BY: omshaban BY: omshaban	FILE NAME = THORN_DITCH_C3_006	CHECKED - OS	REVISED -






SECTION THRU PRECAST BOX CULVERT




LIMITS OF MEMBRANE WATERPROOFING

Longitudinal limits of membrane waterproofing for the precast concrete culvert are along the full length between headwalls



<u>PRECAST CONCRETE RISER</u> PLAN VIEW



SECTION A-A

GENERAL NOTES

- 1. The design fill height for this box is shown on Section Thru Box Culvert. The precast box culvert sections shall conform to the requirements of ASTM C 1577.
- Drain holes shall be provided on exterior culvert walls for each precast box segment. The drain hole shall be located within 1/3 of the clear rise of the box culvert, shall not intercept the haunch, and shall conform to the requirements of Article 503.11 of the Standard Specification.
- 3. Nonwoven geotextile fabric shall conform to the requirements of Art. 1080.01 of the Standard Specifications. The minimum weight of the fabric shall be 6 ounces per square yard.
- 4. Precast concrete box culverts and box culvert end sections shall be backfilled with Porous Granular Embankment in the required excavation areas on the sides of the box culvert from the top of the box culvert to the bottom of the box culvert. This area of PGE is included in the Porous Granular Embankment pay item. The 6-inch thick layer of porous granular material required under the precast concrete box culvert, according to Section 540.06 of the standard specifications, shall also apply to the end sections. Cost of this porous granular material will not be paid for separately but shall be included in the unit price of the work for which it is required.
- 5. The limits and quantities of Removal and Replacement of Unsuitable Materials for Structures shown are based on the boring data and may be modified by the Engineer for variable subsurface conditions encountered in the field.
- 6. The contractor shall be responsible to divert the stream flow during construction to keep construction area free of water. The method of the water diversion shall be subject to the approval of the engineer and the cost shall be included in the cost of Precast Concrete Box Culverts, 10'x7'.

CULVERT CONSTRUCTION SEQUENCE

- 1. Close roadway to all traffic.
- 2. Divert water from construction area.
- 3. Perform removal of existing culvert.
- 4. Perform construction of replacement structure.
- 5. Open roadway to traffic.
- 6. Remove water diversion measures.

TOTAL BILL OF MATERIAL

ITEM	UNIT	TOTAL
Earth Excavation	Cu. Yd	415
Porous Granular Embankment	Cu. Yd	585
Removal of Existing Structures No. 4	Each	1
Structure Excavation	Cu. Yd	450
Removal and Disposal of Unsuitable Material for Structures	Cu. Yd	192
Box Culvert End Sections, Culvert No. 3	Each	2
Membrane Waterproofing System for Buried Structures	Sq. Yd	155
Helical Pier	Each	52
Porous Granular Embankment, Special	Cu. Yd	189
Biaxial Geogrid	Sq. Yd	523
Precast Concrete Box Culverts, 10' x 7'	Foot	96


DRAWING 2 OF 6

TRANSYSTEMS

THORN DITCH
DRAINAGE IMPROVEMENTS
CULVERT 4 - GENERAL DATA

VILLAGE of SOUTH HOLLAND

SHEET NO. 59 of 71



GENERAL NOTES

Box Culvert End Sections shall be constructed according to the requirements of Section 540 of the Standard Specifications except as modified herein. This work will be measured for payment as each, with each end of each culvert being one each. End sections will be paid for at the contract unit price per each for Box Culvert End Sections, Culvert No. 4.

Typical box section dimensions, materials, and reinforcement details for Box Culvert End Sections shall be according to the requirements of ASTM

the design of the portion of the culvert within the limits of Precast Concrete Box Culverts except as modified herein.

Number of segments shown in Elevation is for example only. Length and number of precast box sections required to construct Box Culvert End Sections shall be determined by the Contractor.

See roadway plans for embankment slope (V:H).


1" \emptyset anchor rods for the culvert ties shall conform to the requirements of ASTM F1554, Grade 105. Structural steel for tie plate and restraint angle shall conform to the requirements of Article 1006.04 of the Standard Specifications. All components of the culvert tie detail shall be galvanized according to the requirements of AASHTO M 111 or M 232 as applicable. $2\frac{1}{4}$ " x $2\frac{1}{4}$ " x $\frac{5}{16}$ " plate washers shall be provided under each nut required for the anchor rods. Anchor rods connecting precast sections shall be brought to a snug tight condition followed by an additional $\frac{1}{2}$ turn on one of the nuts for anchor rods installed in the walls. Match marks shall be provided on the bolt and nut to verify relative rotation between the bolt and the nut. Holes in the walls for the culvert tie assembly may be drilled using core bits in lieu of using formed holes.

All costs associated with furnishing and installing or constructing the toewall and culvert ties will not be measured for payment but shall be included in the contract unit price for Box Culvert End Sections, Culvert No. 4

Drain holes shall conform to the requirements of Article 503.11 of the Standard Specifications unless noted otherwise.

Nonwoven geotextile fabric shall conform to the requirements of Article 1080.01. The minimum weight of the fabric shall be 6 oz. / sq. yd..


For end sections with traversable pipe grate systems, see grate detail sheet for required modifications.



♀ 1" Ø anchor rods with $2\frac{1}{4}$ " x $2\frac{1}{4}$ " x $\frac{5}{16}$ " R washers installed in $1\frac{1}{8}$ " Ø formed holes

in culvert walls

SECTION B-B (Showing end section tie details)



TIE PLATE DETAIL

(All costs associated with furnishing and constructing the above drain detail will not be measured for payment but shall be included in the contract unit price for the associated work.)

DRAWING 3 OF 6


= 5/5/2025 DESIGNED - MJS REVISED -SCALE = 2.000 ' / in. CHECKED - OS REVISED -PROJECT NO = 23-R0646 DRAWN - MJS REVISED -FILE NAME = THORN DITCH C4 003 CHECKED - OS REVISED -

TRANSYSTEMS

THORN DITCH DRAINAGE IMPROVEMENTS CULVERT 4 - PRECAST TAPERED END SECTION DETAILS 1

VILLAGE οf **SOUTH HOLLAND**

SHEET NO. 60 of 71



SECTION C-C

3" Ø corrugated PE pipe

Standard Specifications.

Fill with non-shrink grout

#4 v1 bars drilled and grouted into toewall in 9" min.

deep holes at 1'-6" cts., max.

per Article 1040.04 of the

6-#5 h1 bars

placed as shown

#4 s1 bars at

1'-0" cts., max

SECTION E-E

Optional bonded construction joint typ. As1mJ typ.

ALTERNATE SECTION D-D

As1m REINFORCEMENT $(in.^2/ft)$ 6 7 8 11 Ts (in.)

(As1m reinforcement based upon welded wire reinforcement conforming to AASHTO M 55 or M 221).

l, DIMENSION

 $#3 \ bar = 2'-0"$ $#4 \ bar = 2'-8''$


 $#5 \ bar = 3'-4"$ $\#6 \ bar = 3'-11''$

Alternate Section D-D is provided to allow the Contractor the option of casting the bottom slab of the end section first followed by construction of the sidewalls using conventional forming methods. Shop drawings that detail slab thickness and reinforcement layout shall be submitted to the Engineer for review and approval when using Alternate Section D-D.

The size and spacing of the v2 bars shall provide a minimum reinforcement area along each face of the walls (in.2/ft.) equal to 1.10*(As1m). v2 bars may consist of #3 thru #6 size reinforcement bars and the longitudinal spacing shall not exceed the lesser of the wall thickness or 8 inches.

Bonded construction joints shall be prepared according to Article 503.09 of the Standard Specifications.

#4 s bars at spacing = Tt (Spacing need not be less than 8") 4-h bars (See Section F-F) HEADWALL ELEVATION (Allow sidewall reinforcement to extend into end of headwall.)




TOEWALL CONSTRUCTION SEQUENCE

1. Perform excavation and construct toewall.

SECTION D-D

- 2. Backfill according to the applicable paragraphs of Article 502.10 of the Standard Specifications and place bedding for precast box culvert end sections.
- 3. Set precast box culvert end section.
- 4. Drill and epoxy grout reinforcement in toewall in accordance with Section 584 of the Standard Specifications.
- 5. Pressure grout voids using non-shrink grout conforming to Section 1024 of the Standard Specifications.
- The Contractor may furnish a precast or cast-in-place toewall. The Contractor shall be responsible for the strength and stability of the precast toewall during handling. Additional lifting points may be required depending upon the length of the toewall or the Contractor may need to modify the design of the toewall for the proposed handling the method.
- ** If soil conditions permit, the sides of the toewall may be poured directly against the soil. The clear cover on the sides of the toewall shall be increased to 3" by increasing the thickness of the toewall.



SECTION F-F

DRAWING 4 OF 6

= 5/5/2025 DESIGNED - MJS REVISED -CHECKED - OS SCALE = 2.000 ' / in. REVISED -DRAWN - MJS PROJECT NO = 23-R0646 REVISED -FILE NAME = THORN DITCH C4 004 CHECKED - OS REVISED -


1'-0"

1½" cl.

TRANSYSTEMS

THORN DITCH DRAINAGE IMPROVEMENTS CULVERT 4 - PRECAST TAPERED END SECTION DETAILS 2

VILLAGE οf **SOUTH HOLLAND** SHEET NO. 61 of 71





LAB24-G0400 THO				CON AL SERVICES							ВС	PRIN	IG I		CB 1 0	
⊒ Ģ CLIE	NT Robi	nson E	ngineering, l	_td.		PROJE	CT NA	ME Thorr	Ditch							
PRO			24-G0400			PROJE	CT LO	CATION S	South I	Hollan	d, IL					
풀 DAT	E COMPL	ETED	4/18/24	LOGGED BY	TW/KE	_ DRILLI	NG ME	THOD _3.2	25 in. F	ISA						
EMPIATE: GDT - 6/18/24-1041 - K/GEOTIECHNICAL/DXB474-G0400 GEO REL SGR CULVERT REPLACEMENTS, PEDESTRAIN BRIDGES AND DETENTION, THORN DITCH, SOUTH HOLLAND, ILVARSA-G0400 THOS	□ □	GRAPHIC LOG		∕/ATERIAL DESC	CRIPTION	SAMPLE TYPE NUMBER	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)		PLASTIC STIMIT LIMIT	
AN BRIDGES A	595.2			WIN and black LEA WIN and organics		SS 1	67	2-2-3 (5)	4.0		20.0					
rs, Pedestri	-					SS 2	78	2-3-6 (9)	4.25		21.8	-				
EPLACEMENT	587.1					SS 3	61	3-4-4 (8)	4.0	4.1	22.2					
OULVERT RE			stiff to ha	nd gray LEAN CL ard id trace roots in S		SS 4	67	2-1-3 (4)	1.5		24.7					
EO REL SGR	-		Y			SS 5	83	2-2-3 (5)	2.0	2.0	25.2					
15 15	-		-			SS 6	100	2-3-5 (8)	4.0	3.7	21.8					
HNICAL\2024	-					SS 7	89	4-3-5 (8)	4.5	4.4	21.3					
20 20 20	574.6					SS 8	100	5-6-10 (16)	4.5+	8.0	20.3					
18/24 10:41	-		gray LEA hard	AN CLAY		SS 9	100	5-6-9 (15)	4.5+	4.4	18.4					
9-100	570.6					SS 10	100	3-5-6 (11)	4.5+	4.6	18.4					
CON CAV GRO																
ARD GEOTECH	AFTER D	ORILLI emarca	NG		e boundary between s	soil types.		ions may o					ervals	and be	etween	
SSTANDA					al. Dashed lines are in											

PROJE			ngineering, Ltd. 24-G0400			ME Thorn		Hollan	d, IL					LIMIT						
DATE	COMPLI	ETED _	4/18/24 LOGGED BY TW/KE	DRIL	LING ME	THOD 3.2	25 in. F	ISA												
					.0		(dg	(Qn)					TERBE							
O DEPTH	ELEVATION (ft.)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE	RECOVERY % (RQD)	BLOW COUNTS (N VALUE)	POCKET PEN. (Qp) (tsf)	UNC. STRENGTH (Qu) (tsf)	MOISTURE CONTENT (%)	DRY UNIT WT. (pcf)	ORGANIC CONTENT (%)	LIQUID	PLASTIC LIMIT	PI ASTICITY						
-	594.5	****	─ 4" TOPSOIL																	
-	591.8		dark brown CLAY (FILL) trace topsoil and gravel stiff	X s		3-3-2 (5)	1.0		21.5											
5			brown LEAN CLAY stiff	X s		3-3-2 (5)	2.0	1.9	20.3											
	588.8																			
-			black, brown, and gray LEAN CLAY stiff to very stiff	X		2-2-3 (5)	2.5	2.8	31.1											
10				X s		2-1-2 (3)	1.5	1.2	37.5											
-	583.8		dark gray FAT CLAY very soft to soft	X s		1-1-1 (2)	0.25	0.3	46.8											
15				X		1-1-1 (2)	0.25	0.4	62.7			51	28	2						
-				X s		WOH-1-1 (2)	0.25	0.4	77.1		8.0									
-				\ s		WOH-1-1	0.25	0.3	75.4											
20	573.8				3	(2)														
+	5,5.0		gray LEAN CLAY medium stiff to stiff, moist	X s		2-1-1 (2)	1.0	1.0	27.3											
-				V s		2-2-3	0.75	0.8	24.8											
25	569.8	<u>/////</u>	Bottom of borehole at 25.0 feet.	/\ 1	0 09	(5)														

DRAWING 6 OF 6

	DATE =	5/5/2025	DESIGNED	_	MJS	REVISED	_
	SCALE =	2.000 ' / in.	CHECKED	_	OS	REVISED	-
	PROJECT NO =	23-R0646	DRAWN	_	MJS	REVISED	-
ST SAVED BY: omshaban DTTED BY: omshaban	FILE NAME =	THORN_DITCH_C4_006	CHECKED	_	OS	REVISED	-








EXISTING PIPE CONNECTION TO

PROPOSED STRUCTURE

NOT TO SCALE



























	DATE = 05-06-2025	DESIGNED — MIGP	REVISED —
	SCALE =	CHECKED — JDH	REVISED —
	PROJECT NO = 23-R0646	DRAWN — RG	REVISED —
T SAVED BY: NDENAULT ON 5/6/25 TTED BY: JOHN HILSEN ON 5/6/25	FILE NAME = 23R0646-DTLS-01	CHECKED — AG	REVISED —















	DATE	=	05-06-2025	DESIGNED		MGP	REVISED	_
	SCALE :	=		CHECKED	_	JDH	REVISED	_
	PROJECT NO	=	23-R0646	DRAWN	_	RG	REVISED	_
5/6/25 /6/25	FILE NAME	=	23R0646-DTLS-01	CHECKED	_	AG	REVISED	_















	DATE = 05-06-2025	DESIGNED — MGP	REVISED —
	SCALE =	CHECKED — JDH	REVISED —
	PROJECT NO = 23-R0646	DRAWN — RG	REVISED —
LAST SAVED BY: NDENAULT ON 5/8/25 PLOTTED BY: JOHN HILSEN ON 5/8/25	FILE NAME = 23R0646-DTLS-01	CHECKED — AG	REVISED —











	DATE = 05-06-2025	DESIGNED — MGP	HEVISED —
	SCALE =	CHECKED — JDH	REVISED —
	PROJECT NO = 23-R0646	DRAWN — RG	REVISED —
LAST SAVED BY: NDENAULT ON 5/6/25 PLOTTED BY: JOHN HILSEN ON 5/6/25	FILE NAME = 23R0646-DTLS-01	CHECKED — AG	REVISED —





- OVERVIEW

 Complete package includes motor unit, control panel, float with screen, mooring lines, cable.

 Cable is UL, CSA & NEC rated for underwater use.

 Total package Listed by ETL to UL/CSA standards.

 Intake near surface allows for shallow operation
- Saltwater compatible
- Packaged for convenient shipping Optional lighting available

- FLOAT

 UV-resistant polyethylene

 Single-piece float

 Series 300 stainless steel hardware

· Custom thermoplastic propeller

- UV-resistant thermoplastic draft tube and fountain disc
- · Series 300 stainless steel hardware

POWER CABLE

- 3 wire (L, N, G)
 Quick Disconnect standard on 12+ AWG cords
 (otherwise optional)
- (orderwise optionar)
 Stainless steel strain relief on 12+ AWG cords
 6' flex sleeving protection standard (optional for entire cord length)

Float diameter: 28 Unit height with float: 16"

- MOTOR UNIT


 1/2HP, 120Vac operating voltage, single phase
 1750 RPM
- Oil cooled
- Continuous duty rated 17mm top and bottom bearings Thermal overload protection
- Fully unitized heavy-duty carbon-ceramic mechanical seal
- Series 300 stainless steel can Engineering grade thermoplastic top
- Sacrificial anode installed on 316 stainless shaft

CONTROL PANEL

- UL type 3R/4X thermoplastic enclosure Human-rated GFCI protection 24-hour mechanical fountain timer
 - Photo eve for optional lighting
 - 120V plug on 3' power cord





PAID FOR AS POND AERATING FOUNTAIN





MODEL SPECIFICATIONS

2400VFX FOUNTAIN









CASING SPACER INSTALLATION

	DATE = 05-06-2025	DESIGNED — MGP	REVISED —
	SCALE =	CHECKED — JDH	REVISED —
	PROJECT NO = 23-R0646	DRAWN — RG	REVISED —
LAST SAVED BY: NDENAULT ON 6/6/25 PLOTTED BY: JOHN HILSEN ON 5/6/25	FILE NAME = 23R0646-DTLS-01	CHECKED — AG	REVISED —



THORN DITCH	
FLOOD MITIGATION PROJECT	
CONSTRUCTION DETAILS	

