

Current Date	Letting Date	Item-Contract	District	DBE Goal	VBP Goal	County	Major Work Category	Bulletin Description
4/13/2026	4/24/2026	004-62V08	1	0.000	0.00%	Kane, DuPage, Cook	Pavement	
Pay Item #	UOM	Description	Type	Quantity	Unit Price	Extended		
20101100	EACH	TREE TRUNK PROTECTION	Base items		66.000			
20200100	CU YD	EARTH EXCAVATION	Base items		2,930.000			
20201200	CU YD	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	Base items		790.000			
20300100	CU YD	CHANNEL EXCAVATION	Base items		635.000			
20700220	CU YD	POROUS GRANULAR EMBANKMENT	Base items		38.000			
20800150	CU YD	TRENCH BACKFILL	Base items		10.000			
21000310	CU YD	GRANULAR EMBANKMENT, SPECIAL	Base items		90.000			
21001000	SQ YD	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	Base items		743.000			
21101615	SQ YD	TOPSOIL FURNISH AND PLACE, 4"	Base items		9,836.000			
21101625	SQ YD	TOPSOIL FURNISH AND PLACE, 6"	Base items		1,147.000			
21400100	FOOT	GRADING AND SHAPING DITCHES	Base items		5,481.000			The work on this
25000115	ACRE	SEEDING, CLASS 1B	Base items		2.000			project consists of
25000210	ACRE	SEEDING, CLASS 2A	Base items		1.000			ditch regrading,
25000300	ACRE	SEEDING, CLASS 3	Base items		0.750			culvert replacement,
25000400	POUND	NITROGEN FERTILIZER NUTRIENT	Base items		236.000			and various other
25000600	POUND	POTASSIUM FERTILIZER NUTRIENT	Base items		236.000			drainage
25100645	SQ YD	WILDLIFE FRIENDLY EROSION CONTROL BLANKET	Base items		8,729.000			improvements. This
28000250	POUND	TEMPORARY EROSION CONTROL SEEDING	Base items		307.000			project is in DuPage
28000305	FOOT	TEMPORARY DITCH CHECKS	Base items		930.000			County, This project
28000315	TON	AGGREGATE DITCH CHECKS	Base items		66.000			is in DuPage County,
28000400	FOOT	PERIMETER EROSION BARRIER	Base items		11,038.000			Cook County and
28000500	EACH	INLET AND PIPE PROTECTION	Base items		15.000			Kane County.
28000510	EACH	INLET FILTERS	Base items		2.000			
28001105	SQ YD	TEMPORARY WILDLIFE FRIENDLY EROSION CONTROL BLANKET	Base items		14,691.000			
28100105	SQ YD	STONE RIPRAP, CLASS A3	Base items		1,046.000			
28100107	SQ YD	STONE RIPRAP, CLASS A4	Base items		551.000			
28100109	SQ YD	STONE RIPRAP, CLASS A5	Base items		564.000			
28200200	SQ YD	FILTER FABRIC	Base items		1,597.000			
28400100	CU YD	GABIONS	Base items		105.000			
28401000	SQ YD	SLOPE MATTRESS 12"	Base items		133.000			
30300001	CU YD	AGGREGATE SUBGRADE IMPROVEMENT	Base items		20.000			
30300112	SQ YD	AGGREGATE SUBGRADE IMPROVEMENT 12"	Base items		433.000			
40600275	POUND	BITUMINOUS MATERIALS (PRIME COAT)	Base items		706.000			
40600290	POUND	BITUMINOUS MATERIALS (TACK COAT)	Base items		706.000			
40600370	FOOT	LONGITUDINAL JOINT SEALANT	Base items		100.000			
40701881	SQ YD	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	Base items		140.000			
44000100	SQ YD	PAVEMENT REMOVAL	Base items		50.000			
44004250	SQ YD	PAVED SHOULDER REMOVAL	Base items		226.000			
48101202	CU YD	AGGREGATE SHOULDERS, TYPE B	Base items		10.000			
48102100	TON	AGGREGATE WEDGE SHOULDER, TYPE B	Base items		5.000			
48203029	SQ YD	HOT-MIX ASPHALT SHOULDERS, 8"	Base items		226.000			
48203037	SQ YD	HOT-MIX ASPHALT SHOULDERS, 10"	Base items		45.000			
50100100	EACH	REMOVAL OF EXISTING STRUCTURES	Base items		1.000			
50200450	CU YD	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	Base items		84.000			
50201101	EACH	COFFERDAM (TYPE 1) (LOCATION - 1)	Base items		2.000			
52200020	SQ FT	TEMPORARY SOIL RETENTION SYSTEM	Base items		1,170.000			
54001001	EACH	BOX CULVERT END SECTIONS, CULVERT NO. 1	Base items		2.000			
54010302	FOOT	PRECAST CONCRETE BOX CULVERTS 3' X 2'	Base items		39.000			
54213660	EACH	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	Base items		1.000			
550A0070	FOOT	STORM SEWERS, CLASS A, TYPE 1 15"	Base items		15.000			
55100200	FOOT	STORM SEWER REMOVAL 6"	Base items		4.000			
55100500	FOOT	STORM SEWER REMOVAL 12"	Base items		19.000			
55100700	FOOT	STORM SEWER REMOVAL 15"	Base items		15.000			
59100100	SQ YD	GEOCOMPOSITE WALL DRAIN	Base items		27.000			
60255500	EACH	MANHOLES TO BE ADJUSTED	Base items		1.000			
60402210	EACH	GRATES, TYPE 8	Base items		1.000			
60920015	FOOT	PIPE CULVERTS TO BE CLEANED 15"	Base items		19.000			
60920018	FOOT	PIPE CULVERTS TO BE CLEANED 18"	Base items		64.000			
60920030	FOOT	PIPE CULVERTS TO BE CLEANED 30"	Base items		18.000			
63000001	FOOT	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	Base items		37.500			
63100089	EACH	TRAFFIC BARRIER TERMINAL, TYPE 6B	Base items		1.000			
63100167	EACH	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	Base items		1.000			
63200310	FOOT	GUARDRAIL REMOVAL	Base items		112.500			
64200108	FOOT	SHOULDER RUMBLE STRIPS, 8 INCH	Base items		100.000			
66400205	FOOT	CHAIN LINK FENCE, 5'	Base items		1,723.000			
66900200	CU YD	NON-SPECIAL WASTE DISPOSAL	Base items		2,075.000			
66900530	EACH	SOIL DISPOSAL ANALYSIS	Base items		8.000			
66901001	L SUM	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	Base items		1.000			
66901003	L SUM	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	Base items		1.000			
66901006	CAL DA	REGULATED SUBSTANCES MONITORING	Base items		13.000			
67100100	L SUM	MOBILIZATION	Base items		1.000			
70100310	L SUM	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	Base items		1.000			
70100450	L SUM	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	Base items		1.000			
70100460	L SUM	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	Base items		1.000			
70100600	L SUM	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	Base items		1.000			
70102620	L SUM	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	Base items		1.000			
70102625	L SUM	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	Base items		1.000			
70102630	L SUM	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	Base items		1.000			
70102635	L SUM	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	Base items		1.000			
70102640	L SUM	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	Base items		1.000			
70300100	FOOT	SHORT TERM PAVEMENT MARKING	Base items		200.000			
70300150	SQ FT	SHORT TERM PAVEMENT MARKING REMOVAL	Base items		67.000			
72501000	EACH	TERMINAL MARKER - DIRECT APPLIED	Base items		1.000			
78000200	FOOT	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	Base items		200.000			
78100100	EACH	RAISED REFLECTIVE PAVEMENT MARKER	Base items		2.000			
78200005	EACH	GUARDRAIL REFLECTORS, TYPE A	Base items		1.000			
78300200	EACH	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	Base items		2.000			
K0036120	SQ YD	MULCH PLACEMENT 4"	Base items		20.000			
X0325207	FOOT	TELEVISION INSPECTION OF SEWER	Base items		672.000			
X2010400	UNIT	STUMP REMOVAL ONLY	Base items		2,081.000			
X2020410	CU YD	EARTH EXCAVATION (SPECIAL)	Base items		161.000			
X2501800	ACRE	SEEDING, CLASS 4 (MODIFIED)	Base items		2.000			
X2501820	ACRE	SEEDING, CLASS 5 (MODIFIED)	Base items		2.000			
X5400005	FOOT	BOX CULVERT REMOVAL	Base items		42.000			

X5427600	EACH	REMOVE AND RELOCATE END SECTIONS	Base items	2.000		
X5510008	FOOT	STORM SEWER REPAIR	Base items	50.000		
X5537900	FOOT	STORM SEWERS TO BE CLEANED 15"	Base items	89.000		
X5538600	FOOT	STORM SEWERS TO BE CLEANED 36"	Base items	583.000		
X5810103	SQ YD	MEMBRANE WATERPROOFING SYSTEM FOR BURIED STRUCTURES	Base items	27.000		
X6640104	FOOT	FENCE REMOVAL	Base items	92.000		
X6700407	CAL MO	ENGINEER'S FIELD OFFICE, TYPE A (D1)	Base items	12.000		
X7200061	SQ FT	TEMPORARY INFORMATION SIGNING	Base items	151.700		
X7200203	L SUM	DETOUR SIGNING	Base items	1.000		
X7240205	EACH	REMOVE SIGN COMPLETE	Base items	1.000		
X7240600	EACH	REMOVE AND RE-ERECT EXISTING SIGN	Base items	6.000		
X8900104	EACH	TEMPORARY TRAFFIC SIGNAL TIMING	Base items	3.000		
Z0013798	L SUM	CONSTRUCTION LAYOUT	Base items	1.000		
Z0018300	EACH	DRAINAGE STRUCTURE REPAIR	Base items	1.000		
Z0018500	EACH	DRAINAGE STRUCTURES TO BE CLEANED	Base items	1.000		
Z0018600	EACH	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	Base items	2.000		
Z0054400	CU YD	ROCK FILL	Base items	104.000		
Z0076604	HOUR	TRAINEES TRAINING PROGRAM GRADUATE	Base items	500.000	15	7500

Contract Specifics

75 Working Days

*** Do not import this pay item list into the IDOT electronic bidding system. You can only import the pay items that were exported from the IDOT electronic bidding system.