

ITEM	DESCRIPTION	QUANTITY	UNIT	TYPE	UNIT RATE	TOTAL PRICE
85	1 - ROADWAY					
100	Clearing & Grubbing	1.000	LS		\$ -	\$ -
200	Tree Removed, 18" Size	2.000	EA		\$ -	\$ -
300	Tree Removed, 30" Size	5.000	EA		\$ -	\$ -
400	Pipe Removed, 24" Dia. & Under	10.000	FT		\$ -	\$ -
500	Pipe Removed, Over 24" Dia.	23.000	FT		\$ -	\$ -
600	Guardrail Removed For Reuse	50.000	FT		\$ -	\$ -
700	Guardrail Rebuilt, Type 5	50.000	FT		\$ -	\$ -
800	Fence Removed: Chainlink	734.000	FT		\$ -	\$ -
900	Excavation	2,474.000	CY		\$ -	\$ -
1000	Linear Grading	40.000	STA		\$ -	\$ -
1100	Fence Removed & Replaced, Wood	269.000	FT		\$ -	\$ -
1200	Fence, Chainlink	1,099.000	FT		\$ -	\$ -
1300	Fence, Orange Safety Fence	1,400.000	FT		\$ -	\$ -
1400	Gate Type CLT, 13 To 18 FT	3.000	EA		\$ -	\$ -
1500	Walk Removed	2,843.000	SF		\$ -	\$ -
1600	6" Concrete Walk	1,721.000	SF		\$ -	\$ -
1700	Shared Use Path	1,122.000	SF		\$ -	\$ -
1800	6" Concrete Channel Bottom	143.000	SY		\$ -	\$ -
1885	SUBTOTAL					
1895	2 - EROSION CONTROL					
1900	Cofferdams & Excavation Bracing	1.000	LS		\$ -	\$ -
2000	Seeding & Mulching, Sideslope	12,830.000	SY		\$ -	\$ -
2100	Seed & Mulch, Low Maint. Lawn	20,000.000	SY		\$ -	\$ -
2200	Slope Erosion Protection	12,830.000	SY		\$ -	\$ -
2300	Tree Protection, As Directed By Engineer	30.000	EA		\$ -	\$ -
2400	Existing Culverts Cleaned	3.000	EA		\$ -	\$ -
2500	R.C.P., TY-A W/ Filter, 3/4 - 2" Filter Stone, Rock We	11.000	CY		\$ -	\$ -
2600	R.C.P., TY-D, Rock Weir	40.000	CY		\$ -	\$ -
2700	Storm Water Pollution Prevention Plan	1.000	LS		\$ -	\$ -
2800	Erosion Control	60,000.000	DLR		\$ -	\$ -
2885	SUBTOTAL					
2895	3 - DRAINAGE					
2900	4" Conduit, Type B, Schedule 40 Pvc	50.000	FT		\$ -	\$ -
3000	4" Conduit, Type C, Schedule 40 Pvc	50.000	FT		\$ -	\$ -
3100	6" Conduit, Type B, Schedule 40 Pvc	50.000	FT		\$ -	\$ -
3200	6" Conduit, Type C, Schedule 40 Pvc	50.000	FT		\$ -	\$ -
3300	8" Conduit, Type B, Schedule 40 Pvc	50.000	FT		\$ -	\$ -
3400	8" Conduit, Type C, Schedule 40 Pvc	50.000	FT		\$ -	\$ -
3500	12" Conduit, Type B, 707.33	50.000	FT		\$ -	\$ -
3600	12" Conduit, Type C, 707.33	50.000	FT		\$ -	\$ -
3700	15" Conduit, Type B, 707.33	50.000	FT		\$ -	\$ -
3800	15" Conduit, Type C, 707.33	50.000	FT		\$ -	\$ -
3900	18" Conduit, Type B, 707.33	50.000	FT		\$ -	\$ -
4000	18" Conduit, Type C, 707.33	50.000	FT		\$ -	\$ -

4100	18" Conduit, Type C, 706.02	33.000	FT	\$	-	\$	-
4200	24" Conduit, Type B, 707.33	50.000	FT	\$	-	\$	-
4300	24" Conduit, Type C, 707.33	50.000	FT	\$	-	\$	-
4400	30" Conduit, Type B, 707.33	50.000	FT	\$	-	\$	-
4500	30" Conduit, Type C, 707.33	50.000	FT	\$	-	\$	-
4600	36" Conduit, Type B, 707.33	50.000	FT	\$	-	\$	-
4700	36" Conduit, Type C, 707.33	50.000	FT	\$	-	\$	-
4800	66" Conduit, Type C 706.02	14.000	FT	\$	-	\$	-
4900	Manhole, No. 3, 8' Dia.	1.000	EA	\$	-	\$	-
5000	Topsoil Stockpiled	1,751.000	CY	\$	-	\$	-
5100	Placing Stockpiled Topsoil	1,751.000	CY	\$	-	\$	-
5200	R.C.P., Type C	20.000	CY	\$	-	\$	-
5300	R.C.P., With Grout, 601.05	240.000	CY	\$	-	\$	-
5400	Clean & Televis Ex Storm Drain <24"	3,300.000	FT	\$	-	\$	-
5500	Clean & Televis Ex Storm Drain >24"	1,000.000	FT	\$	-	\$	-
5585	SUBTOTAL						
5595	4 - PAVEMENT						
5600	Pavement Repair	1,100.000	SY	\$	-	\$	-
5685	SUBTOTAL						
5695	5 - TRAFFIC CONTROL						
5700	Removal Of Ground Mounted Sign & Reerection	1.000	EA	\$	-	\$	-
5785	SUBTOTAL						
5795	6 - INCIDENTALS						
5800	Cpm Progress Schedule	1.000	LS	\$	-	\$	-
5900	Maintaining Traffic	1.000	LS	\$	-	\$	-
6000	Construction Layout Stakes & Surveying	1.000	LS	\$	-	\$	-
6100	Mobilization	1.000	LS	\$	-	\$	-
6200	Hydro-Exc. Util. Exposure	7.000	EA	\$	-	\$	-
6300	Contingency	450,000.000	DLR	\$	-	\$	-
6385	SUBTOTAL						